





Historic Asbestos-Containing Materials Data
University of Toronto Scarborough
Bladen Wing and Academic Resource Centre

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
ALL	ALL AREAS	GREY INSULATION MATERIAL	INSULATION MATERIAL WITHIN CAVITY DOOR	DOOR	UNKNOWN	A01a	50	CHRYSTOTILE	YES	GOOD	B	FRIABLE	SAMPLED IN BV306 DOOR BY WSP (PROJECT #23595185), AND PRESUMED TO BE PRESENT IN OTHER DOORS THROUGHOUT THE BUILDING. ADDITIONAL SAMPLING IS RECOMMENDED PRIOR TO REMOVAL OR REPAIRS.		N/A
B100T	STEAM TUNNEL	NO SUSPECT ACM OBSERVED							NO						N/A
B200	MEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING		SA-1A-G		ND	NO				SAMPLED BY GOLDER IN 2021 (PROJECT #21460953-1000). ROOM WAS RENOVATED IN 2008. REFER TO PROJECT DCM2008-11.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		SA-2A-F & SA4-A-C		ND	NO				SAMPLED BY GOLDER IN 2021 (PROJECT #21460953-1000). ROOM WAS RENOVATED IN 2008. REFER TO PROJECT DCM2008-11.		N/A
		DEBRIS	DARK GREY CEILING DEBRIS	CEILING SPACE		SA-5A-C	<0.5	CHRYSTOTILE	NO				SAMPLED BY GOLDER IN 2021 (PROJECT #21460953-1000).		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO					THE ROOM WAS RENOVATED IN 2005. REFER TO PROJECT DCM2008-11.	N/A
B202	CLEANER	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	3	R-SA69	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE	LIMITED ACCESS ABOVE CEILING		4
B202A	ELECTRICAL	NO SUSPECT ACM OBSERVED							NO						N/A
B203	SINGLE USER WASHROOM	FIRESTOP	PIPE JOINT	CEILING SPACE	4	R-SA76	5	AMOSITE	YES	GOOD	C	FRIABLE			4
		CERAMIC FLOOR TILES							NO						N/A
B204	MEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		25622-024-1A-C		ND	NO				SAMPLED BY OHE IN 2022 (PROJECT #25622-024)		N/A
		CERAMIC FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B205E	ELEVATOR	NO SUSPECT ACM OBSERVED							NO						N/A
B206	TIM HORTON'S	PARGING CEMENT ON PIPE FITTINGS	BLUE ENCAPSULATED	CEILING SPACE	19	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE	LIMITED ACCESS ABOVE CEILING		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	800 SQ. FT	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B206A	TIM HORTON'S KITCHEN	NEW DRYWALL CEILING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	800 SQ. FT	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		PARGING CEMENT ON PIPE FITTINGS	BLUE ENCAPSULATED	CEILING SPACE	1	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE	VERY LIMITED ACCESS ABOVE CEILING DURING ASSESSMENT		4
		PARGING CEMENT ON PIPE FITTINGS	BLUE ENCAPSULATED	CEILING SPACE	2	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE	VERY LIMITED ACCESS ABOVE CEILING DURING ASSESSMENT		4
B206B	ELECTRICAL / ELEVATOR 9 ACCESS	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	800 SQ. FT	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL CEILING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	7 SQ. FT.	R-SA66	0.5	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B207A	KITCHEN STORAGE / PREP	NEW DRYWALL CEILING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	800 SQ. FT	18765B-20 & 18765-24	1	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (PROJECT #18765B).		4
		PARGING CEMENT ON PIPE FITTINGS	BLUE ENCAPSULATED	CEILING SPACE	1	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE	VERY LIMITED ACCESS ABOVE CEILING DURING ASSESSMENT		4
B210L	STORAGE	NO SUSPECT ACM OBSERVED							NO						N/A
B210S	STAIRCASE	NO SUSPECT ACM OBSERVED							NO						N/A
B220	WOMEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		S01A-C & SA-1A-5C		ND	NO				SAMPLED BY MAPLE IN 2020 (PROJECT #18765) ALSO RENOVATED BY GOLDER IN 2021 (PROJECT #21460953). THE ROOM WAS RENOVATED IN 2008. REFER TO PROJECT DCM2008-11.		N/A
		NEW DRYWALL CEILING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW CERAMIC FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B220E	ELEVATOR	NO SUSPECT ACM OBSERVED							NO						N/A
B220K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM AND CEILING SPACE	45	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE	MANY HAVE BEEN REPAIRED TO FG & PVC, 2 REPAIRED IN 2018 (MAPLE PROJECT #16940)		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL, EXTERIOR OF B200		SA 3A-C		ND	NO				SAMPLED BY GOLDER IN 2021 (PROJECT #21460953-1000).		N/A
		FIRESTOP	PIPE JOINT	GENERAL ROOM AND CEILING SPACE		R-SA76	5	AMOSITE	YES	GOOD	A	FRIABLE			4
B222	ELECTRICAL ROOM	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	10	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.





Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B224S	STAIRWELL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	9	R-SA60	50-75	CHRYSOTILE	YES	GOOD	B	FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA60	50-75	CHRYSOTILE	YES	POOR	B	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B230	LOCKER AREA	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	10	R-SA60	50-75	CHRYSOTILE	YES	GOOD	A	FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA60	50-75	CHRYSOTILE	YES	POOR	A	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		VINYL FLOOR TILES	12 X 12 GREEN FLOOR TILE	FLOOR BELOW VSF AND UNDER LOCKERS	UNKNOWN				NO	GOOD	C	NON-FRIABLE	PRESUMED ACM TILES AND MASTIC MAY BE PRESENT BENEATH VINYL SHEET FLOORING AND UNDER LOCKERS.		N/A
B230K	CORRIDOR	VINYL FLOOR TILES	12 X 12 GREEN FLOOR TILE	FLOOR BELOW VSF AND UNDER LOCKERS	UNKNOWN				NO	GOOD	C	NON-FRIABLE	PRESUMED ACM TILES AND MASTIC MAY BE PRESENT BENEATH VINYL SHEET FLOORING AND UNDER LOCKERS.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	BULKHEAD	UNKNOWN	S01A	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18264). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	32	R-SA60	50-75	CHRYSOTILE	YES	GOOD	A	FRIABLE	FOUR FITTINGS REMOVED IN 2020 (OHE REPORT #26206)		4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	8	R-SA60	50-75	CHRYSOTILE	YES	POOR	A	FRIABLE	WATER STAINED AND VISUALLY IDENTIFIED MOULD GROWTH. THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B230S	STAIRWELL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA60	50-75	CHRYSOTILE	YES	GOOD	A	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT	R-SA66	0.25	CHRYSOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B240E	ELEVATOR	NO SUSPECT ACM OBSERVED							NO						N/A
B240K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING	35-40	R-SA60	50-75	CHRYSOTILE	YES	GOOD	A	FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B242	VESTIBULE	LEVELLING COMPOUND	BELOW CARPET	FLOOR		17973 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		BLACK FOAM	BELOW CARPET	FLOOR		17973 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		BROWN MASTIC	BASEBOARDS	WALL		17973 S03A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	SOUTH WALL	50 SQ. FT.	17973 S01A	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	17973 S01A	0.5	CHRYSTILE	YES	FAIR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B242A	STORAGE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	6	R-SA60	50-75	CHRYSTILE	YES	GOOD	B	FRIABLE			4
		LEVELLING COMPOUND	BELOW CARPET	FLOOR		17973 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		BLACK FOAM	BELOW CARPET	FLOOR		17973 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	17973 S01A	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	4 SQ. FT.	17973 S01B.C	0.5	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B246	ELECTRICAL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTILE	YES	GOOD	B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	R-SA17 (A-C)-08	1.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	9 SQ. FT.	R-SA17 (A-C)-08	1.5	CHRYSTILE	YES	FAIR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B248S	STAIRWELL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTILE	YES	GOOD	A	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	3 SQ. FT.	R-SA17 (A-C)-08	1.5	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT.	R-SA17 (A-C)-08	1.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected



Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B250	WOMEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	200 SQ. FT	18765 S02A-C	1-2	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (PROJECT #18765)		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	2 SQ. FT.	18765 S02A-C	2	CHRYSOTILE	YES	FAIR	A	NON-FRIABLE	HOLE IN DRYWALL CEILING. THE EDGES OF THE DRYWALL FINISH SHOULD BE REPAIRED USING TYPE E 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. NOT ACCESSIBLE IN 2022.		2
B250V	WOMEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	11 SQ. FT	18765 S03A-C	2	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	1 SQ. FT	18765 S03A-C	2	CHRYSOTILE	YES	FAIR	A	NON-FRIABLE	HOLE IN DRYWALL CEILING. THE EDGES OF THE DRYWALL FINISH SHOULD BE REPAIRED USING TYPE E 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. NOT ACCESSIBLE IN 2022.		2
B252	CLEANER	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	12	R-SA60	50-75	CHRYSOTILE	YES	GOOD	B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	200 SQ. FT	R-SA66	0.25	CHRYSOTILE	SUSPECT	GOOD	A	NON-FRIABLE	DRYWALL CEILING - ADDITIONAL SAMPLING IS RECOMMENDED		4
B254	MEN'S WASHROOM	VINYL SHEET FLOORING	WHITE VINYL SHEET FLOORING	FLOOR		S01A-C		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17196). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL SHEET FLOORING	BLACK MASTIC	BELOW FLOOR		S01A-C		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17196). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B254V	MEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	72 SQ. FT	R-SA66	0.25	CHRYSOTILE	SUSPECT	GOOD	A	NON-FRIABLE	DRYWALL CEILING - ADDITIONAL SAMPLING IS RECOMMENDED		4
B260	CLASSROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	<1 SQ.FT	17973 S04A	0.5	CHRYSOTILE	YES	FAIR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1250 SQ. FT	17973 S04A	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM / CEILING SPACE	15	R-SA60	50-75	CHRYSOTILE	YES	GOOD	A	FRIABLE	LIMITED ACCESS TO FITTINGS - VIEWED THROUGH HATCHES		4
		DOOR CAULKING	YELLOW CAULKING	DOOR TO BV242		17973 S05A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR		17059 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17059). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B260K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	NORTH WALL		18474 S02A-C		ND	NO		A		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18474). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	3	R-SA60	50-75	CHRYSOTILE	YES	GOOD	C	FRIABLE			4
B264	CLASSROOM	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	75+	R-SA60	50-75	CHRYSOTILE	YES	GOOD	C	FRIABLE	SELECT FITTINGS REMOVED IN 2018 (MAPLE PROJECT #17222). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL					NO				ALL DRYWALL REMOVED IN 2018 DUE TO RENOVATIONS (MAPLE PROJECT #17178). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR		17059 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17059). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
	TRANSITION AREAS BETWEEN BLADEN WING AND HIGHLAND HALL	REMNANTS OF RECREATION WING							SUSPECT				ANY MATERIAL THAT IS A REMNANT OF THE RECREATIONAL BUILDING SHOULD BE ASSESSED FOR THE PRESENCE OF ASBESTOS PRIOR TO DISTURBANCE.		N/A
B300E	ELEVATOR	NO SUSPECT ACM OBSERVED							NO						N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Historic Asbestos-Containing Materials Data
University of Toronto Scarborough
Bladen Wing and Academic Resource Centre

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B300K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE			4
		VINYL SHEET FLOORING	GREY COLORED SHEET FLOORING	FLOOR	600 SQ. FT	17892 S03		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DOOR CAULKING	GREY DOOR CAULKING	DOUBLE DOORS OUTSIDE B304	150 SQ. FT	17892 S01	2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT	17892 S02	1	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	17892 S02	1	CHRYSTOTILE	YES	FAIR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B300L	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WEST WALL	150 SQ. FT.	18009 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18009). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B300S	STAIRWELL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1500 SQ. FT	R-SA19 (A-C)-08	1.25	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		MASTIC ASSOCIATED WITH STAIRCASE	YELLOW AND WHITE MASTIC	STAIRCASE TREADS		17892 S04		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B300V	VESTIBULE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	VESTIBULE	7	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE			4
B304	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		25622-024-2A-C		ND	NO				SAMPLED BY OHE IN 2022 (OHE PROJECT #25622-024)		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B306	EMRG OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B308	STORAGE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	520 SQ. FT.	R-SA96	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	VERY MINOR DAMAGES BEHIND THE DOOR		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B309	WOMEN'S WASHROOM	NEW DRYWALL CEILING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS. RENOVATED IN 2015. REFER TO PROJECT DCM2015-05.		N/A
B309V	WOMEN'S WASHROOM	NEW DRYWALL CEILING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS. RENOVATED IN 2015. REFER TO PROJECT DCM2015-05.		N/A
B309K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	ELBOWS	GENERAL ROOM	6	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE			4
B310	CLEANERS	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B311	MEN'S WASHROOM	NEW DRYWALL CEILING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS. RENOVATED IN 2015. REFER TO PROJECT DCM2015-05.		N/A
B311V	MEN'S WASHROOM	NEW DRYWALL CEILING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS. RENOVATED IN 2015. REFER TO PROJECT DCM2015-05.		N/A
B316	STORAGE ROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	446 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	VERY MINOR DAMAGES AT THE OLD CABINETRY		4
B318	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.	SA66	0.25	CHRYSTOTILE	NO	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED. MONITOR MINOR CRACKS PRESENT DURING FUTURE ASSESSMENTS.		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B320	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED. MONITOR MINOR CRACKS PRESENT DURING FUTURE ASSESSMENTS.		4
		NEW 2'X4' LAY-IN CEILING TILES				ND			NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B322	STORAGE	VINYL FLOOR TILE	12"X12" RED FLOOR TILES	FLOOR	40 SQ. FT.	R-SA65	5	CHRYSTOTILE	YES	GOOD	B	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		S05A-C		ND	NO				SAMPLED BY MAPLE IN 2020 (PROJECT #18765)		N/A
B324 & B325	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		NEW CARPET FLOOR							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B326	STORAGE	VINYL FLOOR TILE	12"X12" RED FLOOR TILES	FLOOR	100 SQ. FT.	R-SA65	5	CHRYSTOTILE	YES	GOOD	B	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	90 SQ. FT.	R-SA20(A-E)-08	2	CHRYSTOTILE	YES	GOOD	B	NON-FRIABLE			4
B326K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	3000 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		PARGING CEMENT ON PIPE FITTINGS	ELBOWS AND FITTINGS	CEILING SPACE	85-100	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
B328S	STAIRWELL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1000 SQ. FT	R-SA20(A-E)-08	2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B328V	VESTIBULE	PARGING CEMENT ON PIPE FITTINGS	ELBOWS	GENERAL ROOM	13	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	72 SQ. FT.	R-SA20(A-E)-08	2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B330	LOCKER ROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	585 SQ. FT.	SA20(A-E)-08	2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WINDOW	3 SQ. FT.	SA20(A-E)-08	2	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B330S	STAIRCASE	NO SUSPECT ACM OBSERVED							NO						N/A
B332V	VESTIBULE	PARGING CEMENT ON PIPE FITTINGS	ELBOWS	GENERAL ROOM	2	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4

Level of Accessibility


A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions


ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B334	OFFICE	PARGING CEMENT ON PIPE FITTINGS	ELBOWS	GENERAL ROOM	14	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		25622-024-3A-C		ND	NO				SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-024).		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B335	OFFICE	NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B335A	STORAGE	PARGING CEMENT ON PIPE FITTINGS	ELBOWS	ABOVE CEILING TILES	6	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	D	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	50 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
B335K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	25	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM - MIDDLE OF HALLWAY	3	R-SA60	50-75	CHRYSTOTILE	YES	POOR	A	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	200 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
B337	CLEANERS	NO SUSPECT ACM OBSERVED							NO						N/A
B339	ELECTRICAL ROOM	NO SUSPECT ACM OBSERVED													
B340	CLASSROOM	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	BULKHEAD / CEILING		25948-1A-E	1	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY OHE in 2020 (Project #25948)		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17475 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17475). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	NORTH, EAST & WEST		17779 S01-S03		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17779). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	NORTH WALL		18098 S02A,B		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18098, SITE REPORT 11). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	SOUTH WALL		S04A-C	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17779). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	BULKHEAD		S02A-C AND S03A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17779). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW VINYL SHEET FLOORING	BEIGE VINYL SHEET FLOORING	FLOOR		17779 S05		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17779). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		BLACK & BROWN MASTIC	FLOORING MASTIC	FLOOR		18098		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18098 SITE REPORT 11). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		BLACK & YELLOW MASTIC	FLOORING MASTIC	FLOOR		18179 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18179 S01A-C). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	RED 12"X12" VINYL FLOOR TILE	BELOW CARPET	500 SQ. FT.	17779 S06	1	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	NOT OBSERVED DURING THE 2020 REASSESSMENT. SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17779). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		VINYL FLOOR TILE	BLACK MASTIC	BELOW CARPET		17779 S06		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17779). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B340A	STORAGE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL (PERIMETER -OLD)	1000 SQ. FT	16737-S01 & R-SA66	2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2017 (PROJECT #16737). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		NEW DRYWALL WALLS		WALL (PARTITION - NEW)					NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.




Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B342	ELECTRICAL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
B344E	ELEVATOR	NO SUSPECT ACM OBSERVED													
B344K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.	R-SA66	0.25	CHRYSTOTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
B344S	STAIRWELL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	4 SQ. FT.	25622-024-4A-C	1	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-024). THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	596 SQ. FT.	25622-024-4A-C	1	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-024).		4
B344V	VESTIBULE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	430 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B346	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL AT ENTRANCE	50 SQ. FT.	17972 S04A		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	FIRST EXAM DESK PARTITION WALL	25 SQ. FT.	17972 S04B		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	SECOND EXAM DESK PARTITION WALL	25 SQ. FT.	17972 S04C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		YELLOW & BLACK MASTIC	MASTIC BELOW CARPET	ENTRANCE OF ROOM		17972 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILE	12"X12" RED FLOOR TILES	FLOOR		R-SA65	5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	REMOVED ACCORDING TO UTSC NOTICE OF PROJECT - JULY 2020.		
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS			R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE	REMOVED ACCORDING TO UTSC NOTICE OF PROJECT - JULY 2020.		
B346A	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346B	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346C	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346D	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346E	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346F	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346G	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346H	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346J	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B346L	TESTING CENTRE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B347	WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B349	WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	30 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B355	CLASSROOM	VINYL FLOOR TILE	12"X12" RED FLOOR TILES	FLOOR	1165 SQ. FT.	R-SA65	5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	REMOVED ACCORDING TO UTSC NOTICE OF PROJECT - JULY 2020. CARPET OBSERVED THROUGHOUT THE ROOM. ASBESTOS FLOOR TILES MAY STILL BE PRESENT BENEATH THE CARPET.		4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS			R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE	REMOVED ACCORDING TO UTSC NOTICE OF PROJECT - JULY 2020.		4
		BLACK MASTIC	MASTIC ASSOCIATED WITH VINYL FLOOR TILE BELOW CARPET	FLOOR		17972 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		CAULKING	AROUND BLACKBOARDS	WALLS		17972 S03A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B357K	CORRIDOR	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.




Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B358K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	88	R-SA60	50-75	CHRYSTILE	YES	GOOD	A	FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA60	50-75	CHRYSTILE	YES	POOR	A	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		25980-2A & 3A	0.5-1	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY OHE IN 2020 (PROJECT #25980)		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	25980-2A & 3A	0.5-1	CHRYSTILE	YES	FAIR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B359	CLASSROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT	R-SA21 (A-C)-08	1.75	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILE	12"X12" RED FLOOR TILES	FLOOR BELOW CARPET	1165 SQ. FT	R-SA65	5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	CARPET OBSERVED THROUGHOUT THE ROOM. ASBESTOS FLOOR TILES MAY STILL BE PRESENT BENEATH THE CARPET.		4
B360	CLASSROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT	R-SA21 (A-C)-08	1.75	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B361	CLASSROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA21 (A-C)-08	1.75	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	4 SQ. FT.	R-SA21 (A-C)-08	1.75	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA21 (A-C)-08	1.75	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
B363	CLASSROOM	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B366	STORAGE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	SMALL ADJACENT STORAGE ROOM	5	R-SA60	50-75	CHRYSTILE	YES	GOOD	A	FRIABLE	LOCATED AT ENTRANCE TO THE ROOM		4
B368	ELECTRICAL ROOM	NO SUSPECT ACM OBSERVED							NO						N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.





Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B369K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	9	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	SA21(A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	3 SQ. FT.	SA21(A-C)-08	1.75	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B369S	STAIRWELL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM							A				N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1500 SQ. FT.	R-SA21(A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	R-SA21(A-C)-08	1.75	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B370	ART GALLERY	NO SUSPECT ACM OBSERVED	NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS						NO						N/A
B370A	ART GALLERY	NO SUSPECT ACM OBSERVED	NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS						NO						N/A
B370K	ART GALLERY	NO SUSPECT ACM OBSERVED	NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS						NO						N/A
B371	ART GALLERY	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17167 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17167). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B373	ELECTRICAL	NO SUSPECT ACM OBSERVED	NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS						NO						N/A
B375	ART GALLERY	NO SUSPECT ACM OBSERVED	NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS						NO						N/A
B380	RALPH CAMPBELL LOUNGE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17323 S01-S03		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17323). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	9	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A/B	FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A/B	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B380A	ELECTRICAL	NEW DRYWALL WALLS							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B380V	VESTIBULE	NEW DRYWALL WALLS							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A/B	FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B390	BOOK STORE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	65	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A/B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILE	12"X12" RED FLOOR TILES	FLOOR	63 SQ. FT.	R-SA65	5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B390A	BOOK STORE - STORAGE ROOM	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING	24	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING	1	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	227 SQ. FT.	R-SA21(A-C)-08	1.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	AT PIPE PENETRATE	3 SQ.FT.	R-SA21(A-C)-08	1.75	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B390B	BOOK STORE	NEW VINYL FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A/B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B390C	BOOK STORE	NEW VINYL FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	3 SQ.FT.	R-SA21(A-C)-08	1.75	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	20	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A/B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B390D	BOOK STORE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1500 SQ. FT.	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY MAPLE AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	8 SQ. FT.	R-SA68	0.5	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW VINYL FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NO SUSPECT ACM OBSERVED	NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS												
B390E	ELEVATOR	NO SUSPECT ACM OBSERVED	NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS												
B390V	BOOK STORE - VESTIBULE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	R-SA21(A-C)-08	1.75	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
B400	OFFICE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	4	R-SA60	50-75	CHRYSTILE	YES	GOOD	A	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	420 SQ. FT.	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	AT PIPE PENETRATE	1 SQ. FT.	R-SA68	0.5	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NO SUSPECT ACM OBSERVED													N/A
B400E	ELEVATOR	NO SUSPECT ACM OBSERVED													

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B400K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	10 SQ. FT.	R-SA68	0.5	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		WINDOW CAULKING	BLACK CAULKING	INTERIOR CAULKING		17892 S05		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		WINDOW CAULKING	GREY CAULKING	INTERIOR CAULKING		17892 S06	1	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		WINDOW CAULKING	DARK AND LIGHT GREY CAULKING	EXTERIOR CAULKING		17892 S07		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	18	R-SA60	50-75	CHRYSTILE	YES	GOOD	C	FRIABLE	1 FITTING REPAIRED IN 2014.		4
B400S	STAIRCASE	PARGING CEMENT ON PIPE FITTINGS	ELBOWS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTILE	YES	GOOD	B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT.	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B405	JANITOR'S CLOSET	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA60	50-75	CHRYSTILE	YES	GOOD	C	FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B428K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT	SA23(A-G)-08	2.25	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	25	R-SA60	50-75	CHRYSTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	SA23(A-G)-08	2.25	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CORRIDOR WALL BY THE STAIRS	UNKNOWN	S01B	1	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18521). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B428S	STAIRWELL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1500 SQ. FT.	R-SA23(A-G)-08	2.25	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1 SQ. FT.	R-SA23(A-G)-08	2.25	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CORRIDOR WALL BY THE STAIRS			1	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18521). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
B430	REFER TO B428K														N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B430K	CORRIDOR	NEW FIBREGLASS INSULATION	FITTINGS	GENERAL ROOM					NO				PREVIOUSLY IDENTIFIED ASBESTOS-CONTAINING PARGING CEMENT OBSERVED TO BE REPLACED WITH FIBERGLASS INSULATION AND COVERED IN PVC		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	2000 SQ. FT	SA23(A-G)-08	2.25	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	3 SQ. FT.	SA23(A-G)-08	2.25	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B432	4TH FLOOR STUDY AREA	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILINGS / WALLS	UNKNOWN			SUSPECT	NO	GOOD	A	NON-FRIABLE	SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01.		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS. THE SPACE WAS RENOVATED IN 2011. REFER TO PROJECT DCM2011-01.		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS. THE SPACE WAS RENOVATED IN 2011. REFER TO PROJECT DCM2011-01.		N/A
B442	4TH FLOOR STUDY AREA	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILINGS / WALLS	UNKNOWN			SUSPECT	NO	GOOD	A	NON-FRIABLE	SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01.		N/A
B444	4TH FLOOR STUDY AREA	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILINGS / WALLS	UNKNOWN			SUSPECT	NO	GOOD	A	NON-FRIABLE	SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01.		N/A
B445	CUSTODIAL ROOM	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE			4
B446	4TH FLOOR STUDY AREA	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILINGS / WALLS	UNKNOWN			SUSPECT	NO	GOOD	A	NON-FRIABLE	SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01.		N/A
B447	BELL ROOM	NO SUSPECT ACM OBSERVED							NO						N/A
B448	4TH FLOOR STUDY AREA	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILINGS / WALLS	UNKNOWN			SUSPECT	NO	GOOD	A	NON-FRIABLE	SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01.		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	3	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING / WALLS	150 SQ. FT.	R-SA24(A-C)-08	1.25	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B450	ELECTRICAL ROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	4 SQ. FT.	R-SA24(A-C)-08	1.25	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. NO ACCESS IN 2021.		2
		PARGING CEMENT ON PIPE FITTINGS	ELBOWS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE			4
B450E	ELEVATOR	NO SUSPECT ACM OBSERVED													
B450K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	200 SQ. FT	SA23(A-G)-08	2.25	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS										REMOVED IN 2014		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Historic Asbestos-Containing Materials Data
University of Toronto Scarborough
Bladen Wing and Academic Resource Centre


Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B450S	STAIRWELL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSOTILE	YES	GOOD	B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	25622-024-SA-C	1	CHRYSOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B450V	VESTIBULE	NEW CARPET FLOOR							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	35	R-SA24(A-C)-08	1.25	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
B452	STUDY AREA	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	4 SQ.FT.	R-SA24(A-C)-08	1.25	CHRYSOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	10 L. FT.	R-SA24(A-C)-08	1.25	CHRYSOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	200 SQ. FT.	R-SA96	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
B455	WOMEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	200 SQ. FT.	R-SA96	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
B457	STUDY AREA	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B460K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	25-30	R-SA70	50-75	CHRYSOTILE	YES	GOOD	B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT	SA23(A-G)-08 & 18521 S01A			SUSPECT	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18521). DESPITE SAMPLE RESULT, FURTHER SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B466	COMPUTER LAB	PARGING CEMENT ON PIPE FITTINGS	REMOVED						NO				OBSERVED TO BE REMOVED. ROOM WAS RECENTLY RENOVATED		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.	R-SA96	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B469	COMPUTER ROOM	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	25	R-SA60	50-75	CHRYSOTILE	YES	GOOD	B	FRIABLE			4
		NEW DRYWALL WALLS							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B469K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	40-50	R-SA70	50-75	CHRYSOTILE	YES	GOOD	B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17016 S01A-C & 18521 S01C,D		ND	NO				SAMPLED BY MAPLE IN 2018 AND 2020 (MAPLE PROJECT #17016 & 18521 RESPECTIVELY). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B471	COMPUTER LAB	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	10	R-SA60	50-75	CHRYSOTILE	YES	GOOD	B	FRIABLE	AREA/ROOM RECENTLY RENOVATED		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17167 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17167). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B472	COMPUTER OFFICE	NEW DRYWALL WALLS							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	35	R-SA70	50-75	CHRYSOTILE	YES	GOOD	C	FRIABLE	AREA/ROOM RECENTLY RENOVATED		4
B473	COMPUTER LAB	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL WALLS							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		DJC01A-C & DL-01		ND	NO				SAMPLED BY WSP GOLDER IN 2022 (GOLDER PROJECT #22532220). NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
B476	DATA CENTRE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
		NEW VINYL FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSOTILE	YES	GOOD	B	FRIABLE	AREA/ROOM RECENTLY RENOVATED		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected


Historic Asbestos-Containing Materials Data
University of Toronto Scarborough
Bladen Wing and Academic Resource Centre

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B478	ELECTRICAL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL/CEILING	150 SQ. FT.	R-SA24(A-C)-08	1.25	CHRYSTILE	YES	GOOD	B	NON-FRIABLE			4
		CAULKING	GREY CAULKING	EXTERIOR CAULKING (ON ROOF)		27295-4A-C		ND	NO				SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	18	R-SA60	50-75	CHRYSTILE	YES	GOOD	B	FRIABLE	AREA/ROOM RECENTLY RENOVATED		4
B478K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	25622-024-6A-C	2	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	3 SQ. FT.	25622-024-6A-C	2	CHRYSTILE	YES	POOR	A	NON-FRIABLE	SAMPLED BY OHE IN 2022 (PROJECT 25622-024). THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTILE	YES	GOOD	B	FRIABLE	AREA/ROOM RECENTLY RENOVATED		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT	R-SA66	0.25	CHRYSTILE	SUSPECT	GOOD	A	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B478S	STAIRWELL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL					NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW FIBERGLASS PIPE INSULATION							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B480	DATA CENTRE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW CERAMIC FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL WALLS							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		CAULKING	BLACK CAULKING	EXTERIOR (ROOF) PIPING FOR HVAC UNIT		27295-3B,C			NO				SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW FIBERGLASS PIPE INSULATION							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B480A	DATA CENTRE	NEW CERAMIC FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1000 SQ. FT.	R-SA97	0.75	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	NEW DRYWALL WALLS ARE ALSO LIKELY PRESENT. PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED. MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY MAPLE AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL					NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B480K	CORRIDOR (RENOVATED IN 2009-2010)	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		S01A-4C		ND	NO				SAMPLED BY MAPLE IN 2020 (OHE PROJECT #18629). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	NORTH WALL AND WEST WALL		27295-2A-C		ND	NO				SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		CAULKING	BLACK CAULKING	EXTERIOR, BEHIND THE DOOR AND ON ROOF		27295-3A, D, E, F & G		ND	NO				SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILES	12"X12" BEIGE WITH GREY AND BROWN STREAKS	FLOOR		27295-5A-C		ND	NO				SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		MASTIC ASSOCIATED WITH TILES	BLACK MASTIC	FLOOR		27295-5A-C		ND	NO				SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW FIBERGLASS PIPE AND DUCT INSULATION							NO				RENOVATED IN 2009-2010		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B480V	VESTIBULE	NEW CERAMIC FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		27295-1A-C & 18629 S05A-C		ND	NO				SAMPLED BY MAPLE IN 2020 (OHE PROJECT #18629) AND OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B481	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	NORTH, SOUTH & WEST WALL		18104 S01A-C & DUC01-06		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18104). ALSO SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT #21507744). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B481A	ELECTRICAL	NO SUSPECT ACM OBSERVED							NO						N/A
B482	COMPUTER LAB	DRYWALL	GYPSUM BOARD & PAPER	WALL		A01a-c		ND	NO				SAMPLED BY WSP IN 2023 (WSP PROJECT #23595185). SAMPLE TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	NORTH, WALL RECEPTACLE	700 SQ. FT.	S02B	1	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18442). SAMPLE TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B483	MEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	< 1 SQ. FT.	R-SA97	0.75	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA97	0.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B485	WOMEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA97	0.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B486	STORAGE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	3	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
B487	COMPUTING HELP DESK	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	14	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE	AREA/ROOM RECENTLY RENOVATED. INCLUDES FORMED ROOM B488		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1300 SQ. FT.	S01E	1	CHRYSTOTILE	YES	GOOD	4	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18521). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B490	COMPUTER LAB	PARGING CEMENT ON PIPE FITTINGS	ELBOWS AND FITTINGS	CEILING	20	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA97	0.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	4 L. FT.	R-SA97	0.75	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B494	COMPUTER LAB	PARGING CEMENT ON PIPE FITTINGS	ELBOWS AND FITTINGS	CEILING	20	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA97	0.75	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B498	COMPUTER LAB	SPRAYED FIREPROOFING	SPRAY APPLIED INSULATION	CEILING SPACE	1575 SQ. FT.	17994 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		25622-024-7A-C		ND	NO				SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-024)		N/A
B498A	OFFICE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	6	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
B498C	STORAGE	SPRAY APPLIED FIREPROOFING	SPRAY APPLIED INSULATION	CEILING SPACE	100 SQ. FT.	17994 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B498D	DATA CLOSET	SPRAY APPLIED FIREPROOFING	SPRAY APPLIED INSULATION	CEILING SPACE	132 SQ. FT.	17994 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
5TH FLOOR	OFFICE AREAS	NEW DRYWALL JOINT COMPOUND & WALLS	DRYWALL JOINT COMPOUND	WALLS	7500 SQ. FT.	N/A			NO				THE MAJORITY OF THE 5TH FLOOR OFFICE AREAS WERE RENOVATED IN EARLY 2012. SEVERAL AREAS/OFFICE ROOMS WERE RENOVATED OR CONSTRUCTED WHERE NEW, NON-ASBESTOS DRYWALL JOINT COMPOUND WAS USED. REFER TO DRAWING A2 OF THE 2015 GOLDER REPORT FOR FURTHER DETAIL REGARDING LOCATIONS OF BOTH NEW, AS WELL AS ORIGINAL, ASBESTOS-CONTAINING DRYWALL JOINT COMPOUND EXIST.		N/A
B500	OFFICE	NEW VINYL SHEET FLOORING	NEW 2009	FLOOR					NO				VINYL SHEET FLOORING IS NOW OVERLAIN BY 2'X2' CARPET TILE FLOORING. THIS RENOVATION REPORTEDLY TOOK PLACE EARLY IN 2012.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B500E	ELEVATOR	NO SUSPECT ACM OBSERVED							NO						N/A
		NEW VINYL SHEET FLOORING	NEW 2009	FLOOR					NO						N/A
B500K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	678 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	10 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B500S	STAIRCASE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALLS	600 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B502	OFFICE	VINYL FLOOR TILE	12"X12" LIGHT BROWN FLOOR TILE	FLOOR	150 SQ. FT	R-SA67	5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	CONCEALED WITH CARPETING		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B503	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW CARPET FLOOR							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B504	OFFICE	VINYL FLOOR TILE	12'X12" LIGHT BROWN FLOOR TILE	FLOOR	150 SQ. FT	R-SA67	5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	CONCEALED WITH CARPETING		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B505	KITCHENETTE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL OF ASBESTOS-CONTAINING DRYWALL IN SEPTEMBER 2011.		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B506	OFFICE	NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B507	WOMEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING SPACE	90 SQ. FT.	R-SA68 & S06A-B	1-2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (PROJECT #18765)		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING SPACE	1 SQ. FT.	R-SA68 & S06A-B	2	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B508	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B509	MEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING SPACE	90 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B510	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B510K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	48	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	A	FRIABLE			4
		NEW VINYL SHEET FLOORING	NEW 2009	FLOOR					NO				VINYL SHEET FLOORING IS NOW OVERLAIN BY 2'X2' CARPET TILE FLOORING. THIS RENOVATION REPORTEDLY TOOK PLACE EARLY IN 2012.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1275 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B511	BELL ROOM	NO SUSPECT ACM OBSERVED							NO						N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	R-SA68 & S07C	2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (PROJECT #18765)		4
B512	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT	R-SA68 & S07C	2	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B513	OFFICE	NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B513A	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
		NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B514	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1332 SQ. FT	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B515	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	720 SQ. FT	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1 SQ. FT.	R-SA68	0.5	CHRYSOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B516	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	675 SQ. FT	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	REMOVED						NO				ACM FITTINGS REMOVED IN 2012		N/A
B517	OFFICE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	3	R-SA60	50-75	CHRYSOTILE	YES	GOOD	C	FRIABLE	NOT OBSERVED. MAYBE LOCATED WITHIN RADIATOR UNITS.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	450 SQ. FT	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
B518	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE			4
		CARPET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B519	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011 - ADDITIONAL SAMPLING IS RECOMMENDED		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	< 1 SQ. FT.	R-SA68	0.5	CHRYSOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		CARPET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B519A	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011 - ADDITIONAL SAMPLING IS RECOMMENDED		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B519K	CORRIDOR	NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	800 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		S08A-C		ND	NO				SAMPLED BY MAPLE IN 2020 (PROJECT #18765)		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	3 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B519S	STAIRWELL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	750 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 L. FT.	R-SA68	0.5	CHRYSTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT ON PIPE FITTINGS	REMOVED						NO				OBSERVED TO BE REMOVED		N/A
B520	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B521	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	25	R-SA60	50-75	CHRYSTILE	YES	GOOD	B/C	FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	456 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
B522	MEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	100 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B523	WOMEN'S WASHROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	100 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B524	ELECTRICAL	NO SUSPECT ACM OBSERVED							NO						N/A
B525	CLEANERS	NO SUSPECT ACM OBSERVED							NO						N/A
B526	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B526A	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B526B	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	POOR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B526C	OFFICE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE	MANY FITTINGS WERE OBSERVED TO BE REMOVED		4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
B526D	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
B526E	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
B526K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE (BY ROOM B526C)	24	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	340 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B527	OFFICE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	4	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	C	FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	C	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B528	OFFICE	PARGING CEMENT ON PIPE FITTINGS	REMOVED						NO				OBSERVED TO BE REMOVED		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO						N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
B529	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	480 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	PARTIAL REMOVAL IN SEPTEMBER 2011		4
B530	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	480 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B530K	CORRIDOR	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B534	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	480 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B536	OFFICE	PARGING CEMENT ON PIPE FITTINGS	REMOVED						NO				OBSERVED TO BE REMOVED		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B538	ELECTRICAL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	125 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B538E	ELEVATOR	NO SUSPECT ACM OBSERVED							NO						N/A
B538K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE			4
B538S	STAIRWELL	NO SUSPECT ACM OBSERVED							NO				NEW DRYWALL WALLS OBSERVED		N/A
B538V	VESTIBULE	NO SUSPECT ACM OBSERVED							NO						N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B540	BOARDROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	6 L. FT.	R-SA68	0.5	CHRYSTOTILE	YES	FAIR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B544	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B546	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B548	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B550	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B551	WAITING AREA	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17005 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2017 (PROJECT #17005). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	2 SF OF MOULD-IMPACTED DRYWALL REMOVED IN 2018 (MAPLE PROJECT #17753). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
B560	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B560K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	60	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B/C	FRIABLE	2 FITTINGS REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17005 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2017 (PROJECT #17005). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B562	OFFICE	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B563	KITCHENETTE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B564	OFFICE	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B566	OFFICE	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B570	OFFICE	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	MONITOR MINOR CRACKS		4
B572	OFFICE	NEW CARPET FLOOR							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B573	COPY ROOM / OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B574	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	MONITOR MINOR CRACKS		4
B575	BOARDROOM	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	450 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B576	OFFICE	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE	MONITOR MINOR CRACKS		4

Level of Accessibility



A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions


ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B578	OFFICE	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B580	ELECTRICAL	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	8	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B/C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	B	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	R-SA68	0.5	CHRYSTOTILE	YES	POOR	B	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B580K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS			R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B/C	FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	330 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
B580S	STAIRWELL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	2 SQ. FT.	16556	1	CHRYSTOTILE	YES	FAIR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
B584	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW CARPET FLOOR							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B586	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	MONITOR MINOR CRACKS		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	8 L. FT.	R-SA68	0.5	CHRYSTILE	YES	FAIR	A	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
									NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B587	CLOSET	NO SUSPECT ACM OBSERVED							NO						N/A
B588	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW CARPET FLOOR							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B590	OFFICE	NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
B590K	CORRIDOR	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA60	50-75	CHRYSTILE	YES	GOOD	C	FRIABLE	LOCATED ABOVE THE DOOR TO ROOM B592. 6 FITTINGS AT PARTITION WALL REMOVED IN 2019 (MAPLE PROJECT #17974). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B592	OFFICE	NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
B593	OFFICE	NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	460 SQ. FT	17634 S01A-E	1	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17634). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
B594	OFFICE	NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	324 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.

B - Accessible only to maintenance staff and exposed to view without moving a building compound.

C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.

4 – Regular inspection/surveillance of ACM for compliance with the regulations.

N/A – Not applicable.

Definitions

ACM – Asbestos-Containing Materials

SA – Sample representative

R-SA – Sample referenced to a visually similar homogeneous sample material.

ND – None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
B595	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL (WEST)	300 SQ. FT	R-SA68 & 27641-3A	0.5-1	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	WEST WALL SAMPLED BY OHE IN 2022 (PROJECT #27641). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL (NORTH AND EAST)		27641-2A-C		ND	NO				NORTH AND EAST DRYWALL WALLS ARE NEW. ABATED IN 2019 (MAPLE PROJECT #17974).		N/A
		CAULKING	BLACK	WINDOW		27641-1A-C		ND	NO				SAMPLED BY OHE IN 2022 (PROJECT 27641). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		MASTIC	YELLOW	BASEBOARD		27641-4A-C		ND	NO				SAMPLED BY OHE IN 2022 (PROJECT #27641). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X2' CARPET FLOOR TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	7	R-SA60	50-75	CHRYSTILE	YES	GOOD	C	FRIABLE			4
B596	OFFICE	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA60	50-75	CHRYSTILE	YES	GOOD	C	FRIABLE			4
		NEW VINYL SHEET FLOORING		FLOOR, CONCEALED BELOW CARPET					NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW 2'X4' LAY-IN CEILING TILES							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NO SUSPECT ACM OBSERVED							NO						N/A
B598	MECHANICAL	GASKET	BROWN	PIPE		27540-1A-C		ND	NO				SAMPLED BY OHE IN 2022 (PROJECT #27540). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		MECHANICAL SYSTEM INSULATION	PIPE INSULATION	AHU 1 ON THE ROOF		27186-1A-C		ND	NO				SAMPLED BY OHE IN 2022 (PROJECT #27186). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
5TH FLOOR ROOF	ROOFTIOP MECHANICAL ROOM	CAULKING	DARK GREY	VENT ALONG WALL		28244-01A-C			NO				SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). ABATED BY CURMANN IN 2022 (CURMANN PROJECT #22078)		N/A
		CAULKING	BLACK	METAL PANEL BELOW VENT		28244-02A-C		ND	NO				SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		MASTIC	DARK GREY	DUCT WORK		28244-03A-C		ND	NO				SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		MASTIC	GREY	DUCT WORK		28244-04A-C		ND	NO				SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		MASTIC	LIGHT GREY	DUCT WORK		28244-05A-C		ND	NO				SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		CAULKING	GREY-BLACK	BOTTOM OF SOUTHEAST CONCRETE WALL		28244-06A-C		ND	NO				SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
B610	AHU ON ROOF	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	6	R-SA60	50-75	CHRYSTILE	YES	GOOD	B	FRIABLE			4
B610S	STAIRWELL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT	R-SA68	0.5	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
B620	AHU ON ROOF	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	9	R-SA60	50-75	CHRYSTILE	YES	GOOD	B	FRIABLE			4
B620S	STAIRWELL	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT	16556-S01	1	CHRYSTILE	YES	GOOD	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2017 (PROJECT #16556). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		4
		NEW VINYL SHEET FLOORING							NO				NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
ACADEMIC RESOURCE CENTRE (FORMERLY BLADEN WING)															
ARC/BV	HALLWAY	MASTIC	YELLOW MASTIC	FLOOR		MAS01A-C		ND	NO				SAMPLED BY GOLDER IN 2022 (PROJECT #22532220/3000)).		N/A
AC 200	IT SERVICES	VINYL FLOOR TILE	12"X12" BLACK FLECK	FLOOR		17994 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" BLACK FLECK	YELLOW MASTIC ASSOCIATED WITH FLOOR TILE		17994 S01A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' FLAT TEXTURED	CEILING					NO				DATE STAMPED (09/19/2005)		N/A
AC 200V	VESTIBULE/CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	1000 SQ. FT	SA18 (A-C)-08	2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
AC201	IT OFFICE	VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		MAPLE SAMPLE No.: 17994 S03A-G and OHE SAMPLE No.: 26377-1A to 26377-1E.		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). SAMPLED BY OHE IN 2021 (PROJECT #26377). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
AC201K	CORRIDOR	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL									DATE STAMPED (05/20/2003)		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
AC201S	STAIRCASE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL		26377-2A to 26377-2E	2	CHRYSTOTILE	YES	GOOD	A	NON-FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	10	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE			4
AC202	ELECTRICAL	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	CEILING	75 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DUCT MASTIC	YELLOW-GREY DUCT MASTIC	DUCT WORK					SUSPECT	GOOD	C	NON-FRIABLE	MATERIAL NOT SAMPLED DURING THE 2020 ASSESSMENT		4
AC 203	OFFICE	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	UNKNOWN	R-SA60	50-75	CHRYSTOTILE	SUSPECT	GOOD	B	FRIABLE	ALL PIPE FITTINGS PRESENT ABOVE CEILING ARE PAINTED BLACK AND ARE INACCESSIBLE. PARGING CEMENT MAY BE PRESENT ON PIPE FITTINGS THAT WERE NOT IDENTIFIED DURING THE 2019 ASSESSMENT.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
AC 204	IT HELP DESK	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	8 EACH	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE	PRESENT ABOVE CEILING ONCE YOU ENTER ROOM AT THE SECOND FAN DIFFUSER		4
AC205	MEETING ROOM	PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	1 EACH	28445-1A-C	60	CHRYSTOTILE	YES	GOOD	B	FRIABLE	SAMPLED BY OHE IN 2023 (PROJECT 28445)		4
AC205A	KITCHENETTE	VINYL SHEET FLOORING	DARK GREY SPECKLED	FLOOR		17994 S04A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	10 EACH	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE	PRESENT ABOVE CEILING AT WALL TO AC203		4
AC206	OFFICE	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
AC206K	CORRIDOR	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	750 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	2 EACH	R-SA60	50-75	CHRYSTOTILE	YES	GOOD	B	FRIABLE	PRESENT ABOVE CEILING IN FRONT OF AC205A		4
		DUCT MASTIC	YELLOW-GREY DUCT MASTIC	DUCT WORK					SUSPECT	GOOD	C	NON-FRIABLE	MATERIAL NOT SAMPLES DURING THE 2019 ASSESSMENT		4
AC207	OFFICE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	350 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
	SMALL SECTION OF OFFICE SPACE	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	BULKHEAD	10 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' FLAT TEXTURED	CEILING					NO				DATE STAMPED (09/19/2005)		N/A
AC207A	OFFICE	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
AC207S	STAIRCASE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A
AC207T	STAIRCASE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' TEXTURED PINHOLE	CEILING					NO				DATE STAMPED (05/20/2003)		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area	Material	Description	Location	Qty/Unit	Sample Number	%	Type	ACM (Yes, No, Suspect)	Condition	Accessibility	Friability	Comments	Photograph of Damaged ACM	Action Required
AC209	OFFICE	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
AC280	SMALL SECTION OF LIBRARY	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	10 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' FLAT TEXTURED	CEILING					NO				DATE STAMPED (09/19/2005)		N/A
AC284	ELECTRICAL ROOM	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	50 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' FLAT TEXTURED	CEILING					NO				DATE STAMPED (09/19/2005)		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
AC284A	ELECTRICAL ROOM	VINYL FLOOR TILE	12"X12" YELLOW-BEIGE FLECK	FLOOR	20 SQ. FT	17994 S05A	1	CHRYSTILE	YES	GOOD	A	NON-FRIABLE			4
		VINYL FLOOR TILE	12"X12" YELLOW-BEIGE FLECK	FLOOR	2 SQ. FT.	17994 S05A	1	CHRYSTILE	YES	FAIR	A	NON-FRIABLE	NO ACM OBSERVED IN 2022; RECENTLY RENOVATED		N/A
		VINYL FLOOR TILE	12"X12" YELLOW-BEIGE FLECK	BROWN & BLACK MASTIC ASSOCIATED WITH FLOOR TILE	20 SQ. FT	17994 S05A-C		ND	NO						N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	7EACH	R-SA60	50-75	CHRYSTILE	YES	GOOD	B	FRIABLE			4
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA60	50-75	CHRYSTILE	YES	POOR	B	FRIABLE	NO ACM OBSERVED IN 2022; RECENTLY RENOVATED		N/A
AC290	OPEN LIBRARY SPACE	VINYL FLOOR TILE	12"X12" GREY FLECK	FLOOR		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		VINYL FLOOR TILE	12"X12" GREY FLECK	BLACK MASTIC ASSOCIATED WITH FLOOR TILE		17994 S02A-C		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	BULKHEAD	1000 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	5000 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A
		NEW 2'X4' LAY-IN CEILING TILES	2'X4' FLAT TEXTURED	CEILING					NO				DATE STAMPED (09/19/2005)		N/A
		PARGING CEMENT ON PIPE FITTINGS	FITTINGS	CEILING SPACE	UNKNOWN	R-SA60	50-75	CHRYSTILE	SUSPECT	GOOD	B	FRIABLE	ALL PIPE FITTINGS PRESENT ABOVE CEILING ARE PAINTED BLACK AND ARE INACCESSIBLE. PARGING CEMENT MAY BE PRESENT ON PIPE FITTINGS THAT WERE NOT IDENTIFIED DURING THE 2021 ASSESSMENT.		4
AC390A															
AC390B															
AC390M	OFFICE MEZZANINE	DRYWALL JOINT COMPOUND	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT	17994 S03A-G		ND	NO				SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected