

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
THROUGHOUT SCIENCE WING	VARIOUS	VINYL FLOOR TILES	9X9	UNDER FURNITURE AND MILLWORK	N/A						SUSPECT	NON-FRIABLE	SUSPECTED TO BE PRESENT, CONCEALED UNDER FURNITURE/MILLWORK THROUGHOUT THE BUILDING		4
THROUGHOUT SCIENCE WING	VARIOUS	WOVEN MATERIAL PRESENT BEHIND WOOD PANELLING	WOVEN MATERIAL PRESENT BEHIND WOOD PANELLING	WALLS AND CEILING	N/A	16365-S04A-C	ND	ND			NO		SAMPLED FROM ROOM 319 IN AUGUST 2017		N/A
ROOF	ROOF	BLACK ROOFING MATERIALS	ROOFING MATERIALS	MIDDLE, LOWER & UPPER ELEVATION, S8.1		16945 S01 & S02	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16945). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DARK GREY CAULKING	ROOFING MATERIALS	PERIMETER FLASHING S8.1		16945 S01	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16945). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		BLACK TAR	ROOFING MATERIALS	PERIMETER FLASHING S8.1		16945 S01C	5	CHRYSTILE	GOOD	B	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16945). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		LIGHT GREY CAULKING	ROOFING MATERIALS	S8.1		16945 S02A-C	1	CHRYSTILE	GOOD	B	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16945). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		ROOFING MATERIALS	ROOFING MATERIALS	WEST SECTION		27545-1E	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27545). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CAULKING	GREY	MECHANICAL UNIT, SOUTH ROOF SECTION		27545-4A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27545). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
ROOF	ROOF (5TH FLOOR)	ROOFING MATERIALS	ROOFING MATERIALS	ROOFING SYSTEM		27545-5A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27545). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CAULKING	WHITE	METAL FLASHING, NORTHEAST		27545-6A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27545). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		ROOFING MATERIALS	ROOFING MATERIALS	ROOFING SYSTEM (ROOF S3.3)		28566-1A-C	ND	ND			NO		SAMPLED BY OHE IN 2023 (OHE PROJECT #28566).		N/A
		CAULKING	GREY, HARD	PERIMETER CONCRETE WALL		28566-2A-C	ND	ND			NO		SAMPLED BY OHE IN 2023 (OHE PROJECT #28566).		N/A
		CAULKING	DARK GREY, SOFT	METAL PANELS		28566-3A-C	ND	ND			NO		SAMPLED BY OHE IN 2023 (OHE PROJECT #28566).		N/A
		CAULKING	CLEAR	METAL PANELS		28566-4A-C	ND	ND			NO		SAMPLED BY OHE IN 2023 (OHE PROJECT #28566).		N/A
		DUCT MASTIC	WHITE	DUCT, MECHANICAL EQUIPMENT		28566-5A-C	ND	ND			NO		SAMPLED BY OHE IN 2023 (OHE PROJECT #28566).		N/A
		CAULKING	DARK GREY, HARD	METAL PANELS		28566-6A-C	ND	ND			NO		SAMPLED BY OHE IN 2023 (OHE PROJECT #28566).		N/A
		CAULKING	BLACK	WINDOW		28566-7A-C	ND	ND			NO		SAMPLED BY OHE IN 2023 (OHE PROJECT #28566).		N/A
		TAR	BLACK	AROUND ACCESS HATCH		28566-8A-C	ND	ND			NO		SAMPLED BY OHE IN 2023 (OHE PROJECT #28566).		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
ROOF	ROOF (6TH Floor)	ROOFING MATERIALS	CEMENT BOARD	SOUTH SIDE OF LOWER ROOF, S6.8		27098-1A	3-7	CHRYSTILE & AMOSITE	GOOD	B	YES	NON-FRIABLE	SAMPLED BY OHE IN OCTOBER 2021 (OHE PROJECT #27098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		GREY CAULKING	ROOFING MATERIALS	SOUTH SIDE OF LOWER ROOF, S6.8		27098-3A-3C	ND	ND			NO		SAMPLED BY OHE IN OCTOBER 2021 (OHE PROJECT #27098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		BLACK CAULKING	ROOFING MATERIALS	SOUTH SIDE OF LOWER ROOF, S6.8		27098-2A-2C	ND	ND			NO		SAMPLED BY OHE IN OCTOBER 2021 (OHE PROJECT #27098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CAULKING	DARK GREY	METAL FLASHING		27545-2A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27545). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CAULKING	BLACK	METAL FLASHING		27545-3A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27545). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		ROOFING MATERIALS	ROOFING MATERIALS	ROOFING SYSTEM		27545-1A-F		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27545). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		BUILT-UP ROOF MEMBRANE	ROOFING MATERIALS	ROOFING SYSTEM		S01A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18407). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		BLACK CONSOLIDATED MATERIAL	ROOFING MATERIALS	ROOFING SYSTEM		S02A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18407). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		BLACK TAR	ROOFING MATERIALS	ROOFING SYSTEM		S02A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18407). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CAULKING	BROWN	SKYLIGHT FLASHING		S03A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18407). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
R110 (B129 Highland Hall)	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HOT WATER HEATING RETURN	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	CONVERTOR FEED HEATING LINE	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	TERMINAL HEAT RETURN	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES COLD WATER	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES HOT WATER	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	CONDENSATE	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	CHILLER WATER SUPPLY	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	CHILLER WATER RETURN	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	STEAM LINE	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HEAT AND STEAM EXCHANGER	GENERAL ROOM/CEILING SPACE									DURING THE 2022 REASSESSMENT, THE ROOM WAS NOTED TO BE FULLY RENOVATED AND ALL ACMS HAD BEEN REMOVED.		N/A
B100T	TUNNEL (BETWEEN R-WING AND S-WING)	NO SUSPECT ACM OBSERVED									NO		ALL PIPE AND FITTING INSULATION APPEARED TO BE FIBERGLASS		N/A
S100	OPEN GARAGE BAY	PLASTER		GENERAL SPACE	120 SQ. FT.	R-SA10 & R-SA129-(A-C)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	BELOW AND ABOVE CEILING SPACE	9	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PLASTER		CEILING		R-SA10 & R-SA129-(A-C)-06		ND			NO				N/A
S101	STORAGE	NO SUSPECT ACM OBSERVED									NO		PIPE FITTINGS SUSPECTED TO BE PRESENT ABOVE SOLID CEILING		N/A
S101A	OPEN GARAGE BAY	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL	1	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		PLASTER	PLASTER	CEILING	120 SQ. FT.	S01(A-C)	0.5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18630). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S102	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		PLASTER	PLASTER MATERIAL	CEILING	200 SQ. FT.	R-SA10 & R-SA129-(A-C)-06		ND			NO				N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S102K	CORRIDOR	TEXTURE COAT/PLASTER FROM CEILING	TEXTURE COAT/PLASTER	CEILING		SA129-(A-C)-05		ND			NO				N/A
S103A	WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	GENERAL ROOM/CEILING SPACE	12	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	ONE FITTING REMOVED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S103B	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DIESEL GENERATOR	GENERAL ROOM/CEILING SPACE	10	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	MANY FITTINGS REMOVED AND REPLACED WITH NON-ASBESTOS FIBERGLASS INSULATION WITH PVC JACKETING. 3 SPORADIC FITTINGS REPAIRED IN SEPTEMBER, 2017 JUST OUTSIDE OF VESTIBULE (MAPLE PROJECT #16495 AND #16671). SELECTED FITTINGS REMOVED IN 2019 (MAPLE PROJECT #18149). SELECTED FITTINGS REMOVED IN 2019 (MAPLE PROJECT		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	STEAM GENERATOR BREACHING	GENERAL ROOM/CEILING SPACE	223	R-SA8	35-50	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		BREACHING INSULATION ON TANKS	DOMESTIC LINES HOT WATER TANKS	GENERAL ROOM/CEILING SPACE	1600 SQ. FT.	SA6	35-50	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HEADER SUPPLY	GENERAL ROOM/CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HEADER RETURN	GENERAL ROOM/CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	STEAM LINE	GENERAL ROOM/CEILING SPACE	3	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES HOT WATER	GENERAL ROOM/CEILING SPACE	23	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	TANK LINE 1	GENERAL ROOM/CEILING SPACE	7	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		GASKET	STEAM GENERATING UNIT 2	GENERAL ROOM/CEILING SPACE	100 SQ. FT.	SA5	35-50	CHRYSTILE	GOOD	B/C	YES	NON-FRIABLE	ONE GASKET PER UNIT WAS OBSERVED		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	CHILL WATER RET VESSEL	GENERAL ROOM/CEILING SPACE	UNKNOWN	R-SA4		ND	GOOD	B	NO	FRIABLE	UNKNOWN AMOUNT, ASSUME ALL PARGING CEMENT TO BE ASBESTOS-CONTAINING.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S103B	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HEATING RETURN	GENERAL ROOM/CEILING SPACE	8	17568 S01A	50	CHRYSTILE	GOOD	B/C	YES	FRIABLE	9 FITTINGS REMOVED IN 2018 (MAPLE PROJECT #17568). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	KITCHEN SUPPLY	GENERAL ROOM/CEILING SPACE	8	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	AREA 1,2,3,SUPPLY	GENERAL ROOM/CEILING SPACE	8	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	AREA 4,5 SUPPLY	GENERAL ROOM/CEILING SPACE	5	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	PUMP SUCTION HEAT RETURN	GENERAL ROOM/CEILING SPACE	12	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	KITCHEN RETURN	GENERAL ROOM/CEILING SPACE	4	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	AREA 4,5 RETURN	GENERAL ROOM/CEILING SPACE	4	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT ON BOILER BREACHING	PARGING CEMENT	CHILLED WATER LINES	500 SQ. FT.	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	2 FITTINGS ASSOCIATED WITH BOILER REMOVED IN 2018 (MAPLE PROJECT #16807). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	AREA 1,2,3 RETURN	GENERAL ROOM/CEILING SPACE	5	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HOT WATER HEADER PIPES	GENERAL ROOM							NO		28 ACM FITTINGS & 82 LN.FT REMOVED IN 2020 (OHE PROJECT #25828)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	BOOSTER COILS RETURN	GENERAL ROOM/CEILING SPACE	5	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	PRESENT AT HIGH ELEVATION ADJACENT TO DUCTWORK	2	R-SA1	50-75	CHRYSTILE	FAIR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT ON FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.




Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S103B	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	NEAR RED EXPANSION TANK	1	R-SA1	50-75	CHRYSTILE	FAIR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT ON FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		SUSPECT ACM CEMENT BOARD AND CABLE WRAP	ELECTRICAL EQUIPMENT	GENERAL ROOM/CEILING SPACE	UNKNOWN				GOOD	A	SUSPECT	NON-FRIABLE	ACM IS SUSPECTED TO BE PRESENT WITHIN LIVE ELECTRICAL EQUIPMENT- NO ACCESS		4
		DRYWALL	DRYWALL JOINT COMPOUND	AT LOADING DOCK		16733 S02A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16733). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PACKING MATERIAL	FIBROUS MATERIAL	HEAT EXCHANGER, CONDENSATE & HPSS		16762 S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16762). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DUCT GASKET	GASKET	ASSOCIATED WITH DUCT BREECHING		17381 S01	90	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17381). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		NEW FIBERGLASS INSULATION WITH PVC JACKET	THROUGHOUT MECHANICAL ROOMS	GENERAL ROOM/CEILING SPACE	UNKNOWN						NO				N/A
		INSULATION MATERIAL	PIPE WRAP, BLACK PAPER AND GREY MASTIC	GENERAL ROOM/CEILING SPACE		26929-1A-C & 26929 2A-C		ND			NO		SAMPLED BY OHE IN AUGUST 2021 (OHE PROJECT #26929). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		INSULATION MATERIAL	THREE (3) PIPES ASSOCIATED WITH SECONDARY CHILLED WATER PUMPS	GENERAL ROOM		26498-1A to 26498-1C, 26498-2A to 26498-2C and 26498-3A to 26498-3C	ND	ND			NO		SAMPLED BY OHE IN MARCH 2021 (OHE PROJECT #26498). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S103C	COMPRESSOR ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	GENERAL ROOM/CEILING SPACE	4	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	VARIOUS FITTINGS REPAIRED IN 2017 (MAPLE PROJECT #16643). THREE FITTINGS REMOVED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	3	R-SA1	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	PRESENT ABOVE THE SINK WHERE PIPE ENTERS WALL. THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT ON FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S103D	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A
S103E	ELECTRICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S103F	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	75-100	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SOME OF THE ASBESTOS-CONTAINING INSULATION ON PIPE FITTINGS MAY HAVE BEEN REPLACED WITH NEW, NON-ASBESTOS INSULATION. SELECT FITTINGS REMOVED IN JULY 2019 ACCORDING TO UTSC NOTICE OF PROJECTS.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ACROSS FROM LOCATION 103J AT THE CONCRETE SLAB	3	R-SA1	35-50	CHRYSTILE	POOR	B/C	YES	FRIABLE	MOULD-IMPACTED FITTINGS. THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		TAR ON STRAIGHT RUN	CHILLED WATER SUPPLY	GENERAL ROOM/CEILING SPACE	20 LN. FT.	R-SA7	15	CHRYSTILE	GOOD	B/C	YES	NON-FRIABLE			4
		TAR ON STRAIGHT RUN	CHILLED WATER RETURN	GENERAL ROOM/CEILING SPACE	20 LN. FT.	R-SA7	15	CHRYSTILE	GOOD	B/C	YES	NON-FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	CHILLED WATER RETURN	GENERAL ROOM/CEILING SPACE	8	R-SA2	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM - NEAR DOOR TO SW103R	2	R-SA2	50-75	CHRYSTILE	POOR	B/C	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT ON FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM - NEAR DOOR TO SW103S	2	R-SA2	50-75	CHRYSTILE	POOR	B/C	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT ON FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S103G	ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S103H	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	5	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SOME OF THE ASBESTOS-CONTAINING INSULATION ON PIPE FITTINGS MAY HAVE BEEN REPLACED WITH NEW, NON-ASBESTOS INSULATION.		4
S103I	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	30	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SOME OF THE ASBESTOS-CONTAINING INSULATION ON PIPE FITTINGS MAY HAVE BEEN REPLACED WITH NEW, NON-ASBESTOS INSULATION.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	GLYCOL SUPPLY	GENERAL ROOM/CEILING SPACE	5	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	GLYCOL RETURN	GENERAL ROOM/CEILING SPACE	6	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HOT WATER RECIRCULATE	GENERAL ROOM/CEILING SPACE	24	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM - NEAR ENTRANCE TO ROOM S103I	5	R-SA1	50-75	CHRYSTILE	POOR	B/C	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S103J	CONTROL ROOM	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S103K	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	500	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SOME OF THE ASBESTOS-CONTAINING INSULATION ON PIPE FITTINGS MAY HAVE BEEN REPLACED WITH NEW, NON-ASBESTOS INSULATION.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	POOR	B/C	YES	FRIABLE	2 DAMAGED FITTINGS AND MOULD IMPACTED PIPE STRAIGHTS AND THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT ON FITTINGS SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	 	2
S103L	ELECTRICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S103M	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	20	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SOME OF THE ASBESTOS-CONTAINING INSULATION ON PIPE FITTINGS MAY HAVE BEEN REPLACED WITH NEW, NON-ASBESTOS INSULATION. SELECT FITTING REMOVED IN JULY 2019 ACCORDING TO UTSC NOTICE OF PROJECT.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES COLD WATER	GENERAL ROOM/CEILING SPACE	56	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	1 FITTING REMOVED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	GENERAL ROOM/CEILING SPACE	13	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DIESEL GENERATOR	GENERAL ROOM/CEILING SPACE	4	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		INSULATION MATERIAL ON GENERATOR PIPE	INSULATION COVER AND MASTIC	GENERAL ROOM/CEILING SPACE		26954-1A-C		ND			NO		SAMPLED BY OHE IN AUGUST 2021 (OHE PROJECT #26954). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		FIRESTOP AROUND PIPE PENETRATION		WALL									REMOVED IN 2022 (OHE PROJECT # 26697)		N/A
S103N	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S103O	ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S103P	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S103R	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S103S	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	50	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	ONE FITTING REPAIRED IN 2017 (MAPLE PROJECT #16643). SELECT FITTINGS REMOVED IN 2020 (MAPLE PROJECT (#18469). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	CONDENSATE	GENERAL ROOM/CEILING SPACE	12	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	LOW PRESSURE STEAM	GENERAL ROOM/CEILING SPACE	40	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	LOW PRESSURE STEAM	GENERAL ROOM	4	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	DAMAGED PIPE FITTINGS WERE REPAIRED BY HIGHPOINT FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HOT WATER HEAT SUPPLY	GENERAL ROOM/CEILING SPACE	6	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	CONDENSATE	GENERAL ROOM/CEILING SPACE	22	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
S103T	CORRIDOR & STAIR	DRYWALL JOINT COMPOUND		WALL		26954-2A-C		ND			NO		SAMPLED BY OHE IN AUGUST 2021 (OHE PROJECT #26954). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
	CORRIDOR & STAIR	CAULKING	WHITE	DOOR BETWEEN S114B / S113T		26954-3A-C		ND			NO		SAMPLED BY OHE IN AUGUST 2021 (OHE PROJECT #26954). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S103V	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	25-35	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SOME OF THE ASBESTOS-CONTAINING INSULATION ON PIPE FITTINGS MAY HAVE BEEN REPLACED WITH NEW, NON-ASBESTOS INSULATION.		4
S103W	STAIRCASE	NO SUSPECT ACM OBSERVED									NO				N/A
S105	CARPENTRY SHOP	BLACK MASTIC	BLACK MASTIC	FLOOR		16894 S01A-C	2	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	MATERIAL SAMPLED BY MAPLE (MAPLE PROJECT #16894). ACM FLOORING MASTIC REMOVED IN 2019 (MAPLE PROJECT #17660). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ROOM S107 - GENERAL ROOM	4	R-SA1	50-75	CHRYSTILE	GOOD	A/B	YES	FRIABLE			4
		CAULKING	OFF-WHITE	WALL - FORMER DOOR WAY		26255-1A, 26255-1B, 26255-1C	ND	ND			NO		SAMPLED BY OHE (PROJECT #26255) IN 2020.		N/A
S105A	ROOM	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S105B	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	IN ROOM	12	R-SA1	50-75	CHRYSTILE	GOOD	A/B	YES	FRIABLE	SOME OF THE ASBESTOS-CONTAINING INSULATION ON PIPE FITTINGS MAY HAVE BEEN REPLACED WITH NEW, NON-ASBESTOS INSULATION.		4
		PLASTER	WHITE & BEIGE PLASTER	WALL		26255-3A, 26255-3B, 26255-3C	ND	ND			NO		SAMPLED BY OHE (PROJECT #26255) IN 2020.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL - FORMER DOOR WAY		26255-2A, 26255-2B, 26255-2C	ND	ND			NO		SAMPLED BY OHE (PROJECT #26255) IN 2020.		N/A
		CAULKING	BLACK	DOORFRAME		26255-4A	2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY OHE (PROJECT #26255) IN 2020.		4
		VINYL SHEET FLOORING	BEIGE VINYL FLOORING AND BACKING MATERIAL	FLOOR		26255-5A, 26255-5B, 26255-5C	ND	ND			NO		SAMPLED BY OHE (PROJECT #26255) IN 2020.		N/A
		MASTIC	YELLOW	FLOOR - UNDER VINYL SHEET FLOORING		26255-6A, 26255-6B, 26255-6C	ND	ND			NO		SAMPLED BY OHE (PROJECT #26255) IN 2020.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S105K	CORRIDOR	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	64 SQ. FT.	R-SA11 & SA120-(E-F)-06		ND			NO		LIMITED VISIBILITY/ACCESS ABOVE THE CEILING		N/A
		BLACK MASTIC	BLACK MASTIC	WALL			8	CHRYSTILE			YES		REMOVED IN 2019 (MAPLE PROJECT #18149). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	25	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE - AT CORRIDOR 107K	5	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S106	CARPENTRY OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	16	R-SA1	50-75	CHRYSTILE	GOOD	A/B	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S107	CARPENTRY SHOP										NO		REFER TO S105		N/A
S107K	CORRIDOR - FABRICATION LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	5	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
S109	FABRICATION LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	24	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	ONE FITTING REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE	COUNTERTOP									REMOVED IN JAN 2022 ACCORDING TO UTSC NOTICE OF PROJECT. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S109A	FABRICATION LAB	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	400 SQ. FT.	SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ASBESTOS -CONTAINING VINYL FLOOR TILES WERE OBSERVED TO BE REMOVED DURING THE 2017 REASSESSMENT, HOWEVER RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING FLOOR TILE MASTIC MAY REMAIN BELOW NEW FLOORING.		4
S109B	TRADES WORKSHOP	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	20	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	3 FITTINGS AND 5 LIN. FT. REMOVED IN 2020 (OHE PROJECT #25966)		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
S109C	MACHINE SHOP/WELDING ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM AND CEILING	23	R-SA1	50-75	CHRYSTILE	GOOD	A/B	YES	FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		PLASTER	WHITE AND GREY PLASTER	WALL		26702-2A TO 26702-2C	ND	ND			ND		SAMPLED BY OHE IN MAY 2021 (OHE PROJECT #26702). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S109D	FABRICATION LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		NEW DRYWALL	LEADING TO LOCATION 109K	WALL							NO				N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S109E	FABRICATION LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S109F	ELECTRICAL SHOP	NO SUSPECT ACM OBSERVED									NO				N/A
S109G	PAINT ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S109K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	10	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
S109V	VESTIBULE FABRICATION LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S110	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL	360 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
S110A	STORAGE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	360 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	6	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
S110V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	4	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S111A	STORAGE	NO SUSPECT ACM OBSERVED									NO		ASBESTOS ABATEMENT INCLUDING REMOVAL OF ASBESTOS-CONTAINING PARGING CEMENT INSULATION ON A PIPE FITTING WAS COMPLETED BY TRI PHASE IN MARCH 2016.		N/A
S111B	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS		10	R-SA1	50-75	CHRYSTILE		A/C	YES	FRIABLE			4
S111C	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM AND CEILING	14	R-SA1	50-75	CHRYSTILE		A/C	YES	FRIABLE			4
S111K	CORRIDOR	GASKET	ROPE	AROUND HATCH ON DUCT			60	CHRYSTILE			YES	NON-FRIABLE	SAMPLED BY OHE (Project #26108) IN 2020. REMOVED IN 2020 (OHE Project #26108)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	6	R-SA1	50-75	CHRYSTILE		B	YES	FRIABLE			4
S112	CENTRAL STORES	DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	1 SQ. FT	R-SA1-A-07 & 18419 S03A & S03B	0.75	CHRYSTILE	FAIR	A	YES	NON-FRIABLE	DAMAGE TO EDGING. THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S112A	MAILROOM	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		17713 S01 & S02	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17713). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	250 SQ. FT.	SA2-A-07	1.5	CHRYSTILE	GOOD	A	YES	FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. OBSERVED TO BE REMOVED DURING THE 2021 REASSESSMENT, HOWEVER RESIDUAL AMOUNTS MAY REMAIN.		4
S113S	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S114	GAS CYLINDER STORAGE	CAULKING	GREY CAULKING	AT LOADING DOCK		16733 S01A-C & S001A-002C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16733) AND GOLDER IN 2021 (GOLDER PROJECT #21487831). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		FIBROUS MATERIAL	FIBROUS MATERIAL	AT LOADING DOCK		16733 S03A-C	75	CHRYSTILE	GOOD	B	YES	FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16733). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PLASTER	PLASTER	WALL		17713 S01A-02C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17713). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S114A	WALKWAY	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA1	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S114B	LOADING DOCK 7 TUNNEL	METAL CLADDING OVER PIPES AND FITTING INSULATION- APPEARS TO BE FIBERGLASS									NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE			4
		ACM PAPER WITHIN METAL WALL	PAPER	WALLS	UNKNOWN	16733-03A-C	70	CHRYSTILE	GOOD	C	YES	FRIABLE	WITHIN METAL WALL SEPARATING THE POWER PLANT FROM THE LOADING DOCK TUNNEL. SELECT SECTIONS REMOVED IN 2017 (MAPLE PROJECT #16733) AND IN 2021 (OHE PROJECT #26954). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT FITTINGS	FITTINGS	GENERAL ROOM	~10	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	TOO HIGH TO ACCESS, LIKELY PRESENT		4
		CAULKING	BLACK	DOOR BETWEEN S114B / S103T		26954-4A-C		ND			NO		SAMPLED BY OHE IN AUGUST 2021 (OHE PROJECT #26954). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S114D	GARAGE & STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S114E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S114F	LOADING DOCK WALKWAY RAMP	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S114G	LOADING DOCK WALKWAY RAMP	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S114H	MECHANICAL ROOM	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S114J	LOADING DOCK WALKWAY	NO SUSPECT ACM OBSERVED									NO				N/A
S114S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S115	ELEVATOR MACHINE ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE	3 REMOVED NEAR ENTRANCE IN 2009		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	AT RADIATOR	1	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE	AT RADIATOR		4
S115E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S115F	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S115K	CORRIDOR	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	232 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S116	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	GLYCOL LINES	GENERAL ROOM	3	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE	2 PARGING CEMENT FITTINGS REMOVED IN 2019 (MAPLE PROJECT #17677). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	SHAFT	30-35	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	LIMITED ACCESS TO SHAFT DUE TO HEIGHT RESTRICTIONS		4
S119	BOOKSTORE - STORAGE	VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR									REMOVED 2021 (OHE PROJECT # 26480)		N/A
		MASTIC	BLACK MASTIC	FLOOR									REMOVED 2021 (OHE PROJECT # 26480)		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	PRESENT IN BACK CORNER UNDER SHELIVING.									REMOVED 2021 (OHE PROJECT # 26480)		N/A
		NEW LAY-IN CEILING TILES		CEILING							NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES HOT WATER	GENERAL ROOM AND CEILING									REMOVED 2021 (OHE PROJECT # 26480)		N/A
S119A	GROUNDS LUNCHROOM	PLASTER	BEIGE	WALL		275402A-C	<0.5	TREMOLITE			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27540). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	220 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	C	YES	NON-FRIABLE			4
		BLACK MASTIC	BLACK MASTIC	FLOOR	400 SQ. FT.	18751-01A	3	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18751). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES HOT WATER	GENERAL ROOM AND CEILING	12	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
S120	CENTRAL STORES	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HOT WATER RETURN	GENERAL ROOM AND CEILING	20	R-SA1	50-75	CHRYSTILE	GOOD	A/B	YES	FRIABLE	IN AREA S120. SELECT FITTINGS REMOVED IN 2019 ACCORDING TO UTSC NOTICE OF PROJECTS. SELECT FITTINGS REMOVED IN 2020 (MAPLE PROJECT (#18695). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	HOT WATER SUPPLY	GENERAL ROOM AND CEILING	24	R-SA1	50-75	CHRYSTILE	GOOD	A/B	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	EYE WASH STATION	2						NO		2 PARGING CEMENT FITTINGS REMOVED IN 2019 (MAPLE PROJECT #18105). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	750 SQ. FT.	SA2-A-07	1.5	CHRYSTILE	GOOD	A	YES	FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. OBSERVED TO BE REMOVED DURING THE 2021 REASSESSMENT, HOWEVER RESIDUAL AMOUNTS MAY REMAIN.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY MAPLE AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S120A	CARETAKING STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S121	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING	20-25	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	SOME REMOVED JUNE 2014		4
S121K	CORRIDOR OUTSIDE S121	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	4	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S122	ELECTRICAL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S123	MECHANICAL ROOM	BLACK FIBER BOARD	FIBRE BOARD	DECK - EXPANSION JOINT		17005 S02A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17005). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S125E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S125K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING	20	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	ACCESS/VISIBILITY ABOVE THE CEILING TILES WAS LIMITED DUE TO DUCTS AND CABLES		4
		BLACK FELT INSULATION ON PIPE	PIPE INSULATION	CEILING		SA130-(A-B)-06		ND			NO				N/A
		2'x4' ACOUSTIC TILES	PINHOLES AND LONG FISSURES	CEILING		25995-5A, 25995-5B, 25995-5C		ND			NO		SAMPLED BY OHE (PROJECT 25995) IN 2020		N/A
		2'x4' ACOUSTIC TILES	PINHOLES AND SMALL FISSURES	CEILING		25955-6A, 25995-6B, 25995-6C, 25995-7A, 25995-7B, 25995-7C		ND			NO		SAMPLED BY OHE (PROJECT 25995) IN 2020		N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S125S	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S126	WOMEN'S WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING	6	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED VISIBILITY/ACCESS ABOVE THE DRYWALL CEILING		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		DRYWALL		CEILING	150 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
S126A	WOMEN'S WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED VISIBILITY/ACCESS ABOVE THE DRYWALL CEILING		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		DRYWALL		CEILING	150 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
S127	MEN'S WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	SELECT FITTINGS REMOVED IN JANUARY 2020 ACCORDING TO UTSC NOTICE OF PROJECT.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	BEHIND WALL	UNKNOWN	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED ACCESS AND VISIBILITY		4
		PLASTER	PLASTER	CEILING		27010-1A-C	ND	ND		A	NO		SAMPLED BY OHE (Project #27010) IN 2021.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	150 SQ. FT.	R-SA1-A-07	0.75	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
S127A	CLEANERS	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S127V	MEN'S WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	13	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S128	LECTURE HALL	NEW VINYL SHEET FLOORING									NO		ACM TILES AND MASTIC MAY BE PRESENT BELOW		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	500 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC.		4
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR - SPORADIC DAMAGE	8 SQ. FT	R-R-SA113-B-06 & R-SA88	<5	CHRYSTILE	POOR	A	YES	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	1500 SQ. FT.	R-SA13		ND			NO		ADDITIONAL SAMPLING IS RECOMMENDED- NO ACCESS ABOVE THE DRYWALL CEILING		N/A
		PLASTER	WHITE & GREY PLASTER	CEILING		25891-3A, 25891-3B, 25891-3C		ND			ND		SAMPLED BY OHE (Project #25891) IN 2020.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE- ABOVE DRYWALL	5	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		NO SUSPECT ACM OBSERVED									NO				N/A
S128A	CORRIDOR OUTSIDE S128	NO SUSPECT ACM OBSERVED									NO				N/A
S129	LECTURE HALL STORAGE ROOM	NEW VINYL SHEET FLOORING									NO		ACM TILES AND MASTIC MAY BE PRESENT BELOW		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	312 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	MAY BE PRESENT BELOW VINYL SHEET FLOORING. ACM DETECTED IN BOTH TILE AND MASTIC.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	20	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE			4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	312 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S130	STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S130A	STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S130K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S131	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
S132	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16553). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S132A	LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S132B	LINGUISTICS RESEARCH LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16553). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S132E	WAITING AREA	DRYWALL	DRYWALL JOINT COMPOUND	WALL	64 SQ. FT.	R-SA1-D-07	0.25	CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S132F	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	64 SQ. FT.	25622-022-24A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S132G	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	64 SQ. FT.	25622-022-22A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S132H	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE DRYWALL CEILING	4	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED ACCESS/VISIBILITY ABOVE THE CEILING		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING	64 SQ. FT.	25622-022-23A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S132V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S133	LAB	VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		CAULKING	GREY CAULKING	DOOR FRAME									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE MATERIAL	LAB BENCHES (COUNTERTOPS AND SINKS)									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE MATERIAL	SLOP SINK									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE MATERIAL	BEHIND WALL MOUNTED RADIATORS									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PLASTER	PLASTER	ABOVE DOOR		PLA01E	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		MILLBOARD	MILLBOARD	WALL CAVITIES									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		CAULKING	BROWN CAULKING	AROUND DOORS									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		CAULKING	LIGHT BROWN CAULKING	PERIMETER, BETWEEN WALL AND CEILING	40 LN. FT.	CLK04	4	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	BEHIND SIDE BENCH									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	UNDERNEATH LAB BENCHES									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION	DUCTWORK	BETWEEN CANVAS JACKET AND FIBERGLASS INSULATION									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
S133A	LAB	MILLBOARD	MILLBOARD	CEILING CAVITY									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		CAULKING	BROWN CAULKING	DOOR & JUNCTION OF BRICK AND CONCRETE DECK									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	TRENCHES AND BEHIND MILLWORK									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION	DUCTWORK	BETWEEN CANVAS JACKET AND FIBERGLASS INSULATION									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	ACM CEMENT BOARD	FUME HOODS									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	ACM CEMENT BOARD	CEILING SPACE ON WALL									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	ACM CEMENT BOARD	TABLES									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S134	LAB	CAULKING	GREY CAULKING	DOOR FRAME									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR, UNDERNEATH BENCHES									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		MASTIC	BLACK MASTIC	FLOOR, UNDER FLOOR TILES									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE, AT EYE WASH									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
	SHAFT	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	SHAFT #5	8	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	SHAFT CLEANED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S134V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		MASTIC	BLACK MASTIC	CONCRETE SEAM BETWEEN S134V & S142K	1 LN. FT.	CM01	10	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S135	LAB	VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		VINYL FLOOR TILES	9x9 DARK MAROON FLOOR TILE	FLOOR									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		MASTIC	BLACK/YELLOW MASTIC	FLOOR - UNDER FLOOR TILES									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PLASTER	PLASTER	ABOVE DOOR		PLA01F	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE MATERIAL	LAB BENCHES (COUNTERTOPS AND SINKS)									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE MATERIAL	SLOP BENCH									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE MATERIAL	BEHIND WALL MOUNTED RADIATORS									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	BEHIND SIDE BENCH									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	UNDERNEATH LAB BENCHES									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION	DUCTWORK	BETWEEN CANVAS JACKET AND FIBERGLASS INSULATION									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		CAULKING	BROWN CAULKING	DOOR									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		CAULKING	LIGHT BROWN CAULKING	PERIMETER, BETWEEN WALL AND CEILING	200 LN. FT.	CLK04	4	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S135A	LAB	TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE MATERIAL	FUME HOODS									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		TRANSITE™ ASBESTOS-CEMENT MATERIAL	TRANSITE MATERIAL	CEILING SPACE ON BEAM									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	GENERAL ROOM									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		CAULKING	BROWN CAULKING	DOOR & JUNCTION OF BRICK AND CONCRETE DECK									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		VINYL FLOOR TILES	9x9 DARK MAROON FLOOR TILE	FLOOR	20 SQ. FT.	VFT03A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		MASTIC	BLACK/YELLOW MASTIC	FLOOR - UNDER FLOOR TILES									REMOVED IN 2022 (GOLDER PROJECT 22543650). REFER TO PROJECT DCM2022-01		N/A
S137	WORKSHOP	DRYWALL	DRYWALL JOINT COMPOUND	ABOVE DOORWAY		17949 S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17949). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S138	FREEZER ROOM	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.4). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S138V	VESTIBULE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	100SQ FT	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	10	R-SA1	50-75	CHRYSTOTILE	GOOD	C	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S139	LAB	DRYWALL	DRYWALL (NEW - 2022)	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		ACOUSTIC TILES	CEILING TILES (NEW - 2022)	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	12X12 BROWN FLOOR TILE AND BLACK MASTIC	FLOOR									REMOVED IN 2021 (GOLDER PROJECT #21497546). REFER TO PROJECT DCM2020-19.		N/A
		TRANSITE ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS, BENCHTOPS, AND SINKS									MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE ASBESTOS CEMENT PANELLING	CEILING IN S139A									REMOVED IN 2021 (GOLDER PROJECT #21497546). REFER TO PROJECT DCM2020-19.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	TRANSITE ASBESTOS CEMENT PANELLING	CEILING IN S139A									REMOVED IN 2021 (GOLDER PROJECT #21497546). REFER TO PROJECT DCM2020-19.		N/A
		MILLBOARD	MILLBOARD	WALL BETWEEN S139 / S140									REMOVED IN 2021 (GOLDER PROJECT #21497546). REFER TO PROJECT DCM2020-19.		N/A
S139A	LAB	REFER TO S139											ALL ACM REMOVED IN 2021. REFER TO S139 FOR PROJECT DETAILS.		N/A
S139B	OPTICS ROOM	REFER TO S139											ALL ACM IN S139B (FORMERLY PART OF S139) WAS REMOVED IN 2021. REFER TO S139 FOR PROJECT DETAILS.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S139C	QUARANTINE	REFER TO S139											ALL ACM IN S139C (FORMERLY PART OF S139) WAS REMOVED IN 2021. REFER TO S139 FOR PROJECT DETAILS.		N/A
S140	LAB	ACOUSTIC TILES	CEILING TILES (NEW - 2022)	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	AROUND DOOR FRAME TO 140V		17782 S03A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17782). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		VINYL FLOOR TILES	9X9 RED FLOOR TILE AND BLACK MASTIC	FLOOR	440 SQ. FT.	R-SA113-B-06 & R-SA88	<5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RENOVATIONS IN JUNE 2011. RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC REMAIN UNDER BENCHES.		4
		TRANSITE™ ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS									REMOVED 2021 (GOLDER PROJECT 21497546). REFER TO PROJECT DCM2020-19.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE									REMOVED 2021 (GOLDER PROJECT 21497546). REFER TO PROJECT DCM2020-19.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM									REMOVED 2021 (GOLDER PROJECT 21497546). REFER TO PROJECT DCM2020-19.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		MILLBOARD	MILLBOARD	WALL BETWEEN S139 / S140									REMOVED IN 2021 (GOLDER PROJECT #21497546). REFER TO PROJECT DCM2020-19.		N/A
S140A	LAB SUPPORT	DRYWALL	DRYWALL JOINT COMPOUND	WALL		140A-DJC-02A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2021 (PROJECT 21464249(2000))		N/A
		MASTIC	BLACK MASTIC	CONCRETE WALL		140A-MAS-02A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2021 (PROJECT 21464249(2000))		N/A
S140V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE									REMOVED IN APRIL 2022 (SEE CURMANN REPORT #21045-1).		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING		17782 S02A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17782). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS		17782 S05A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17782). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S141	LAB	VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	400 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. OBSERVED TO BE REMOVED DURING THE 2021 REASSESSMENT, HOWEVER RESIDUAL AMOUNTS MAY REMAIN.. 400 SQ. FT. OF MASTIC REMAINS IN THE EAST SIDE OF THE ROOM.		4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER									REMOVED 2017 (GOLDER PROJECT 1670341)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM/UNDER SINK									REMOVED 2017 (GOLDER PROJECT 1670341)		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S141A	LAB SUPPORT	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS									REMOVED 2017 (GOLDER PROJECT 1670341)		N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	WALL WITHIN CEILING SPACE									REMOVED 2017 (GOLDER PROJECT 1670341)		N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR									REMOVED 2017 (GOLDER PROJECT 1670341)		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE COUNTERTOP	WEST SIDE OF ROOM							SUSPECT				4
S141B	LAB	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	120 SQ. FT.	R-SA45 & R-SA-123-(A-B)-06		ND			NO				N/A
		VINYL SHEET FLOORING	NEW	NEW 2009							NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	R-SA1-D-07	0.25	CHRYOTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
S142B	PSYCHOLOGY LAB - MEETING ROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-01A-E	ND				NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553)		N/A
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA45 & R-SA-123-(A-B)-06		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S142C	LAB	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	198 SQ. FT.	R-SA45 & R-SA-123-(A-B)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	75 SQ. FT.	R-SA1-D-07	0.25	CHRYOTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S142D	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	BACK OF ROOM - AT THE RADIATOR	6	R-SA1	50-75	CHRYOTILE	GOOD	A	YES	FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	142 SQ. FT.	25622-022-25A-C	1	CHRYOTILE	GOOD	A	YES	NON-FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	1 SQ. FT.	25622-022-25A-C	1	CHRYOTILE	FAIR	A	YES	NON-FRIABLE	REPAIR FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	280 SQ. FT.	R-SA123(A-B)-06		ND			NO				N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S142E	PSYCHOLOGY LAB - ROOM 1	VINYL FLOOR TILES	12x12 MUSTARD FLOOR TILE	FLOOR	119 SQ. FT.	R-SA40 & SA116-(A-B)-06	5	CHRYOTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED WITHIN MASTIC ONLY. VINYL FLOOR TILES OBSERVED TO BE REMOVED DURING THE 2021 REASSESSMENT, HOWEVER, MASTIC MAY BE PRESENT BELOW NEW VINYL SHEET FLOORING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-01A-E	ND				NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553)		N/A
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	119 SQ. FT.	R-SA45 & R-SA-123-(A-B)-06		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		MASTIC	BLACK	UNDER VINYL SHEET FLOORING		MAS-01A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553)		N/A
		MASTIC	YELLOW	BEHIND BASEBOARD		BBM-01C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553)		N/A
S142F	PSYCHOLOGY LAB - ROOM 2	NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC-01A-E	ND				NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553). NO ACCESS ABOVE CEILING.		N/A

Level of Accessibility


A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S142G	PSYCHOLOGY LAB - ROOM 3	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	UNKNOWN	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	NO HATCH TO GAIN ACCESS TO FITTINGS		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	~10	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	POSSIBLY STILL LOCATED ABOVE DRYWALL CEILING		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-01A-E	ND				NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553)		N/A
		MASTIC	YELLOW	BEHIND BASEBOARD		BBM-01B		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553)		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S142H	PSYCHOLOGY LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-01A-E	ND				NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553)		N/A
		MASTIC	YELLOW	BEHIND BASEBOARD		BBM-01A		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553)		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S142I	PSYCHOLOGY LAB - OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC-01A-E	ND				NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21497553). NO ACCESS ABOVE CEILING.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE THE CEILING	5	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED VISIBILITY/ACCESS ABOVE THE CEILING		4
S142J	LAB	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	198 SQ. FT.	R-SA45 & R-SA-123-(A-B)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	75 SQ. FT.	R-SA1-D-07	0.25	CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S142K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE THE CEILING	12			CHRYSTILE	GOOD	C	YES	FRIABLE			4
		MASTIC	ORANGE DUCT MASTIC	CEILING SPACE	UNKNOWN	SA133-(A-C)	7	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	ADDITIONAL SAMPLING RECOMMENDED THROUGHOUT S-WING		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S142S	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S142V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	12	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2018 (MAPLE PROJECT #16940). SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17005).		4
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA45 & R-SA-123-(A-B)-06		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S143	LECTURE HALL	VINYL FLOOR TILES	12x12 BROWN FLOOR TILE	FLOOR	1008 SQ. FT.	R-SA113-B-06 & R-SA88	<5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR	100 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR - SPORADIC DAMAGE	10 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	FAIR	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PLASTER	WHITE & GREY PLASTER	CEILING		25891-4A, 25891-4B, 25891-4C		ND			ND		SAMPLED BY OHE (Project #25891) IN 2020.		N/A
S143A	LECTURE HALL - HALLWAY	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING	9	R-SA1	35-50	CHRYSTILE	GOOD	B/C	YES	FRIABLE	REPAIRED IN 2014. ADJACENT TO S144 (AT THE END OF THE RAMP)		4
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR	1000 SQ. FT.	R-SA24	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ASBESTOS DETECTED WITHIN FLOOR TILE ONLY.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S144	LECTURE HALL - BACK ROOM	VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR	312 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	10	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE	LIMITED ACCESS TO FITTINGS DUE TO CONTENTS		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	312 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	13	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
S145	STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S145A	STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S145K	CORRIDOR	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA45 & R-SA123-(A-B)-06		ND			NO				N/A
S146	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	SUSPECTED ASBESTOS PARGING AT JOINTS	CEILING SPACE	3	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
S147	LIQUID NITROGEN STORAGE	PARGING ON MECHANICAL EQUIPMENT	PARGING CEMENT	GENERAL ROOM	50 SQ. FT.	SA-131-(A-C)-06	ND				NO		REPAIRED IN 2018 (MAPLE PROJECT #16940). SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17005). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		MASTIC	BLACK MASTIC	UNDER NEW FLOORING		17520 S01A	2	CHRYSTILE	GOOD	A	YES	FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17520). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		MECHANICAL INSULATION		CONDENSATE TANK		INS01A-C		ND			NO		SAMPLED BY GOLDER IN 2022 (GOLDER PROJECT 22532220)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM AND CEILING SPACE	20	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE	25 FITTINGS REMOVED IN 2018 (MAPLE PROJECT #17520). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S148	LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PIPE FITTINGS	FITTINGS										REMOVED BY ENVIROSAFE IN JUNE 2021 (GOLDER PROJECT 21470830)		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S148V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S149	LAB	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		GREY CAULKING	CAULKING	DOOR		17484 S01A-C	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17848). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		MASTIC	BLACK & YELLOW MASTIC	FLOOR BELOW VSF		17484 S02A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17848). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S149V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	2	R-SA1	50-75	CHRYSOTILE	POOR	C	YES	FRIABLE	PRESENT IN CEILING SPACE. THE MOULD IMPACTED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA45 & R-SA-123-(A-B)-06		ND			NO				N/A
S150	WAITING AREA	DRYWALL	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	R-SA52	0.25	CHRYSOTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MASTIC REMOVED IN 2018 (MAPLE PROJECT 16687)		N/A
S150A	PSYCHOLOGY	NEW VINYL SHEET FLOORING		FLOOR							NO				N/A
		CAULKING	GREY CAULKING	WALL	4 L. FT.	25622-022-26A-C	1	CHRYSOTILE	POOR	a	YES	NON-FRIABLE	SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). REMOVE DAMAGED MATERIALS FOLLOWING TYPE 1 ASBESTOS PROCEDURE, AS PRESCRIBED UNDER O.REG. 278/05.		2
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	302 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSOTILE	GOOD	A	YES	NON-FRIABLE	NOT FOUND DURING THE 2021 REASSESSMENT (COULD BE BELOW NEW VINYL SHEET FLOORING). ACM DETECTED IN BOTH TILE AND MASTIC		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	180 SQ. FT.	R-SA52	0.25	CHRYSOTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
S150B	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL AND CEILING	120 SQ. FT.	R-SA52	0.25	CHRYSOTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED. NO ACCESS ABOVE CEILING		4
S150C	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL AND CEILING	50 SQ. FT.	R-SA52	0.25	CHRYSOTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED. NO ACCESS ABOVE CEILING		4
S150D	LAB CONTROL ROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL AND CEILING	120 SQ. FT.	R-SA52	0.25	CHRYSOTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED. NO ACCESS ABOVE CEILING		4
		MASTIC	MASTIC	FLOOR							NO		MASTIC REMOVED IN 2018 (MAPLE PROJECT 16687)		N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions


ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S150E	ROOM	NEW VINYL SHEET FLOORING		FLOOR							NO				N/A
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	140 SQ. FT.	R-SA86	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	NOT FOUND DURING THE 2021 REASSESSMENT (COULD BE BELOW NEW VINYL SHEET FLOORING). ACM DETECTED IN BOTH TILE AND MASTIC		4
		1'x1' ACOUSTIC TILE	SMALL PINHOLES	WALL	56 SQ. FT.	SA51 & SA124-(A-C)-06		ND			NO				N/A
		1'x1' ACOUSTIC TILE	LARGE HOLES	WALL	21 SQ. FT.	SA53 & SA125-(A-C)-06		ND			NO				N/A
		1'x1' ACOUSTIC TILE	SMALL PINHOLES	CEILING	42 SQ. FT.	R-SA51 & R-SA124-(A-C)-06		ND			NO		NO ACCESS ABOVE THE CEILING - ASSUME ACM MAY BE PRESENT UNTIL PROVEN OTHERWISE		N/A
S150F	ROOM	1'x1' ACOUSTIC TILE	LARGE HOLES	WALL	133 SQ. FT.	R-SA53 & R-SA125-(A-C)-06		ND			NO				N/A
		1'x1' ACOUSTIC TILE	LARGE HOLES	CEILING	49 SQ. FT.	R-SA53 & R-SA125-(A-C)-06		ND			NO		NO ACCESS ABOVE THE CEILING - ASSUME ACM MAY BE PRESENT UNTIL PROVEN OTHERWISE		N/A
S150G	ROOM	1'x1' ACOUSTIC TILE	LARGE HOLES	WALL	133 SQ. FT.	R-SA53 & SA125-(A-C)-06		ND			NO				N/A
		1'x1' ACOUSTIC TILE	LARGE HOLES	CEILING	49 SQ. FT.	R-SA53 & R-SA125-(A-C)-06		ND			NO		NO ACCESS ABOVE THE CEILING - ASSUME ACM MAY BE PRESENT UNTIL PROVEN OTHERWISE		N/A
S150H	LAB SUPPORT	1'x1' ACOUSTIC TILE	LARGE HOLES	WALL	133 SQ. FT.	R-SA53 & SA125-(A-C)-06		ND			NO				N/A
		1'x1' ACOUSTIC TILE	LARGE HOLES	CEILING	49 SQ. FT.	R-SA53 & R-SA125-(A-C)-06		ND			NO		NO ACCESS ABOVE THE CEILING - ASSUME ACM MAY BE PRESENT UNTIL PROVEN OTHERWISE		N/A
S151	HEALTH & SOCIETY LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16574). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S151A	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16574). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S151B	HEALTH & SOCIETY LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16574). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S151C	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16574). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S152	LAB	VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	250 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH THE 9"X9" BROWN VINYL FLOOR TILES AND THE MASTIC.		4
		NEW LAY-IN CEILING TILES									NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND BULKHEAD	150 SQ. FT.	R-SA52	0.25	CHRYSTILE	GOOD	C	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS AND COUNTER TOPS	75 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	15	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE			4
S152A	BACK ROOM	VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	77 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	4	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE	FITTINGS NOT OBSERVED DURING THE CURRENT 2018 REASSESSMENT		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	77 SQ. FT.	R-SA52	0.25	CHRYSTILE	GOOD	C	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S152B	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	DOMESTIC WATER LINE ABOVE CEILING	7	R-SA1	50-75	CHRYSTILE	FAIR	C	YES	FRIABLE	UNJACKETED INSULATION ON DOMESTIC WATER LINE ABOVE CEILING. THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S152C	ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S152V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #18574). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S153	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT.	R-SA52	0.25	CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
		MILLBOARD	MILLBOARD	WALL CAVITY	6 SQ. FT	MB01	15	AMOSITE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		CAULKING	RED CAULKING	AROUND WALL/PIPE PENETRATIONS	10 LN. FT.	CLK02	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
S153A	LAB	MILLBOARD	MILLBOARD	CEILING CAVITY	5 SQ. FT	MB01	15	AMOSITE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		CAULKING	RED CAULKING	AROUND WALL/PIPE PENETRATIONS	5 LN. FT.	CLK02	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		CAULKING	BROWN CAULKING	RED BRICK/CONCRETE JUNCTION	10 LN. FT.	CLK05	4	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING ON WALL	CEILING SPACE	9 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE	1 SQ. FT WAS PREVIOUSLY REMOVED BY FERRO IN 2016. FOUR (4) TRANSITE PANELS AND PARGING CEMENT FROM UNDERSIDE OF FLOOR TRENCHES ASSOCIATED WITH SW240 AND SW242 WAS REMOVED BY ENVIROSAFE DURING JUNE 2020.		4
		MASTIC	BLACK AND YELLOW MASTIC	FLOOR		S02A-C	0.5	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18659). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		MASTIC	COLOURLESS	FLOOR		S01A-C	ND				NO		SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18659). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S155	HALLWAY	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	16	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
		CAULKING	BEIGE CAULKING	DOOR	3 L.FT.	CLK01A-C	0.5	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284). REMOVE ASBESTOS-CONTAINING CAULKING FOLLOWING TYPE 1 PROCEDURES PRESCRIBED IN O.REG 278/05.		2
		CAULKING	BEIGE CAULKING	DOOR	17 L.FT.	CLK01A-C	0.5	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		4
		PLASTER	PLASTER	ABOVE DOOR		PLA01C	ND	ND			NO		SAMPLED BY GOLDR IN 2022 (PROJECT 22521196-1000)		N/A
		MASTIC	BEIGE MASTIC	DUCT		DM01A-C		ND			NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
		CEILING TILES	2'X4' WITH PINHOLE PATTERN	CEILING		ACT01A-C		ND			NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
		CEILING TILES	2'X4' WITH SWIRL PINHOLE PATTERN	CEILING		CT02A-C		ND			NO		SAMPLED BY GOLDR IN 2022 (PROJECT 22521196-1000)		N/A
		MASTIC	BLACK MASTIC	UNDER VINYL SHEET FLOORING	250 SQ.FT.	MAS-01A-C	1	CHRYSTILE	GOOD	C	YES		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		4
		VINYL SHEET FLOORING	LIGHT BEIGE	FLOOR		VSF02A-C		ND			NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
		MASTIC	YELLOW	BEHIND BASEBOARD		BA01A-C		ND			NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	128 SQ. FT.	DJC01D		ND			NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
S155A	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	6	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01A-E					NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		MASTIC	BLACK MASTIC	UNDER VINYL SHEET FLOORING	250 SQ.FT.	MAS-01A-C	1	CHRYSTILE	GOOD	C	YES		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S155B	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	8	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01A-E					NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		MASTIC	BLACK MASTIC	UNDER VINYL SHEET FLOORING	250 SQ.FT.	MAS-01A-C	1	CHRYSTILE	GOOD	C	YES		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ADJACENT TO WALL-MOUNTED RADIATOR	2	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
S155C	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	3	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		ACOUSTIC TILES	UNKNOWN	CEILING	100 SQ. FT.	SA3-A-07		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01A-E					NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
		MASTIC	BLACK MASTIC	UNDER VINYL SHEET FLOORING	250 SQ.FT.	MAS-01A-C	1	CHRYSTILE	GOOD	C	YES		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S155D	KITCHENETTE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2		50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	80 SQ. FT.	DJC01A		ND			NO		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		N/A
		ACOUSTIC TILES	UNKNOWN	CEILING	30 SQ. FT.	R-SA3-A-07		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		MASTIC	BLACK MASTIC	UNDER VINYL SHEET FLOORING	250 SQ.FT.	MAS-01A-C	1	CHRYSTILE	GOOD	C	YES		SAMPLED BY GOLDR IN 2022 (GOLDR PROJECT 22525284)		4
S156K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	20-25	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		ACOUSTIC TILES	UNKNOWN	CEILING	570 SQ. FT.	R-SA3-A-07		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		RED FIRESTOP AND BLACK TAR ON DUCTS	FIRESTOP	BELOW FIBREGLASS ABOVE CEILING		16365-SO3	ND	ND			NO		SAMPLED BY MAPLE IN 2017. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CAULKING	RED CAULKING	DUCTWORK - ABOVE CEILING	15 LN. FT.	CLK02	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDR IN 2022 (PROJECT 22521196-1000)		4
S156S	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S156V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	25-30	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S158	LAB	DRYWALL	DRYWALL JOINT COMPOUND	CEILING (S158A)	100 SQ. FT.	R-SA52	0.25	CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED. NO ACCESS ABOVE DRYWALL CEILING IN BACK LAB AREA		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL SPACE/SHAFT	6	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	NO ACCESS		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S158V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES									ALL FITTINGS REMOVED IN MAY 2021 (GOLDR PROJECT 21467665).		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S159	LAB	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S159A	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S159B	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S161	LAB	NEW DRYWALL	12 X 12 WHITE STREAKS	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PLASTER	PLASTER	ABOVE DOOR		PLA01A	ND	ND			NO		SAMPLED BY GOLDR IN 2022 (PROJECT 22521196-1000)		N/A
		2'x4' ACOUSTIC TILES	PINHOLES	CEILING	570 SQ. FT.	R-SA56	ND	ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM/CEILING AT ENTRANCE TO ROOM 161	18	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE	LIMITED ACCESS DUE TO HEIGHT		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S161A	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM/CEILING	6	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		VINYL FLOOR TILES	VINYL FLOOR TILE	INSIDE FRIDGE AREA	100 SQ. FT.						SUSPECT		MAY BE PRESENT BENEATH NEW VINYL SHEET FLOORING.		4
		CAULKING	RED CAULKING	DUCTWORK	30 LN. FT.	CLK02	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDR IN 2022 (PROJECT 22521196-1000)		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility


A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions


ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S161B	LAB	2'x4' ACOUSTIC TILES	PINHOLES	CEILING	570 SQ. FT.	R-SA56		ND			NO				N/A
		NEW DRYWALL	12 X 12 WHITE STREAKS	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S161C	LAB	2'x4' ACOUSTIC TILES	PINHOLES	CEILING	570 SQ. FT.	R-SA56		ND			NO				N/A
		NEW DRYWALL	12 X 12 WHITE STREAKS	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S161D	LAB	2'x4' ACOUSTIC TILES	PINHOLES	CEILING	570 SQ. FT.	R-SA56		ND			NO				N/A
		NEW DRYWALL	12 X 12 WHITE STREAKS	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S161V	VESTIBULE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO				N/A
		2'x4' ACOUSTIC TILES	FISSURE AND PINHOLE	CEILING		CT01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		CAULKING	BEIGE CAULKING	DUCT/UAV BOX		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		CAULKING	RED CAULKING	DUCTWORK AROUND UAV BOXES - ABOVE CEILING	10 LN. FT.	CLK02	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
S162	LAB WAITING AREA	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		PLASTER	PLASTER	ABOVE DOOR		PLA01B	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		MASTIC	GREY MASTIC	DUCTWORK		DM01A-C		ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000) ALL ACM REMOVED IN NOVEMBER		N/A
S162A	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN NOVEMBER, 2017 (MAPLE PROJECT #16553). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S162B	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN NOVEMBER, 2017 (MAPLE PROJECT #16553). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S164	LAB	ACOUSTIC TILES	UNKNOWN	CEILING		R-SA3-A-07		ND			NO		ACM PIPE FITTINGS SUSPECTED PRESENT ABOVE CEILING TILES - LIMITED VIEW.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		CAULKING	DOOR CAULKING	DELAMINATED AT DOOR	15 L. FT.	SA134	>4	CHRYSTILE	POOR	A	YES	NON-FRIABLE	IT IS RECOMMENDED THAT ALL TAN CAULKING BE CONSIDERED ASBESTOS CONTAINING THROUGHOUT THE S-WING. THE DAMAGED ASBESTOS-CONTAINING CAULKING SHOULD BE REMOVED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S164A	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S164V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	1	R-SA1	50-75	CHRYSTILE	POOR	C	YES	FRIABLE	PRESENT IN CEILING SPACE. THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		2'x4' ACOUSTIC TILES	PINHOLES	CEILING	60 SQ. FT.	SA56		ND			NO				N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S165	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN NOVEMBER, 2017 (MAPLE PROJECT #16687). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S165A	LAB SUPPORT	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN NOVEMBER, 2017 (MAPLE PROJECT #16687). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S165B	MEETING ROOM	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN NOVEMBER, 2017 (MAPLE PROJECT #16687). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S166	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	20	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
S168A	ELECTRICAL	TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	WALL	10 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	R-SA52	0.25	CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S168S	STAIRWELL	TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	WALL AT DUCT PENETRATION	15 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S169	STORAGE ROOM	TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	COUNTER	25 SQ. FT				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S200	WOMEN'S CHANGE ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE IN VESTIBULE	1	R-SA1	35-50	CHRYSTILE	GOOD	C	YES	FRIABLE			4
S200A	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	3	R-SA1	35-50	CHRYSTILE	GOOD	C	YES	FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S200B	STORAGE	VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	200 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR AT DOOR THRESHOLD	5 SQ. FT	R-SA18	5	CHRYSTILE	POOR	A	YES	NON-FRIABLE	DAMAGED AT DOOR THRESHOLD. THE ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S200C	STORAGE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	R-SA52	0.25	CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
S200D	SPRINKLER ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM AND CEILING	8	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE			4
S200E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S200F	MAINTENANCE AREA	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	2 FITTINGS REMOVED IN 2018 (MAPLE PROJECT #17131). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		27844-3A-C, 27844-4A-C & 27844-5A-C	ND				NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27844). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S200G	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	7	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
S200H	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
S200I	STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S200IJ	STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S200K	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	14	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE	ONE FITTING REMOVED IN 2022 (OHE PROJECT #27844). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		27844-1A-C & 27844-2A-C	ND				NO		SAMPLED BY OHE IN 2022 (OHE PROJECT #27844). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S200L	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S200M	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S200N	STORAGE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	1000 SQ. FT.	R-SA52	0.25	CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	ADDITIONAL SAMPLING IS RECOMMENDED.		4
S200P	STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S200S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S201E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S201K	CORRIDOR	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		17335 S01A-C		ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17335). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		17335 S02A-C		ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17335). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		BROWN MASTIC	BULLETIN BOARD	SW MEETING AREA		16840 S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16840). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	25-35	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014. SELECT FITTINGS REMOVED IN OCTOBER 2019 ACCORDING TO UTSC NOTICE OF PROJECT.		4
S201S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	4	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S201V	CORRIDOR	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		17335 S01		ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17335). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		SMOOTH PLASTER	WHITE & GREY PLASTER	WALL		17335 S03A-C		ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17335). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	25-35	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014. FITTINGS WERE NOT OBSERVED DURING THE 2021 REASSESSMENT SURVEY, LIMITED ACCESS TO FITTINGS DUE TO CLOSED CEILING. PRESUMED TO BE PRESENT.		4
S202	ACADEMIC PRINTING AND PUBLISHING SERVICES	MASTIC		FLOOR UNDER NEW VINYL SHEET FLOORING					GOOD	C	SUSPECT	NON-FRIABLE	FLOORING INSTALLED IN 2009. MASTIC IS PRESUMED TO BE ACM		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	120 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		GREY COATING	GREY COATING	OVERTOP FIBREGLASS		17875 S01A-C		ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17875). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S202A	ACADEMIC PRINTING AND PUBLISHING SERVICES	MASTIC		FLOOR UNDER NEW VINYL SHEET FLOORING					GOOD	C	SUSPECT	NON-FRIABLE	FLOORING INSTALLED IN 2009. MASTIC IS PRESUMED TO BE ACM		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	120 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	NOT OBSERVED DURING THE 2021 REASSESSMENT.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	6	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	PRESENT AT DUCT RUN ON THE SOUTH SIDE. SELECT REPAIRS COMPLETED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S202B	ACADEMIC PRINTING AND PUBLISHING SERVICES	MASTIC		FLOOR UNDER NEW VINYL SHEET FLOORING					GOOD	C	SUSPECT	NON-FRIABLE	FLOORING INSTALLED IN 2009. MASTIC IS PRESUMED TO BE ACM		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	120 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	10	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	NOT FOUND DURING THE 2021 ASSESSMENT. MAY BE PRESENT ABOVE SOLID CEILING, NO HATCHES TO VIEW		4
S202C	ACADEMIC PRINTING AND PUBLISHING SERVICES	MASTIC		FLOOR UNDER NEW VINYL SHEET FLOORING					GOOD	C	SUSPECT	NON-FRIABLE	FLOORING INSTALLED IN 2009. MASTIC IS PRESUMED TO BE ACM		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	120 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S204	MAINTENANCE AREA	MASTIC		FLOOR UNDER NEW VINYL SHEET FLOORING					GOOD	C	SUSPECT	NON-FRIABLE	FLOORING INSTALLED IN 2009. MASTIC IS PRESUMED TO BE ACM		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-28A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S204A	MANAGER'S OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	10	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	240 SQ. FT.	R-SA89		ND			NO				N/A
S205A	MECHANICAL ROOM	REFER TO S103B AND VICINITY									SUSPECT		2ND FLOOR OF THE MECHANICAL ROOM - PLEASE REFER TO MECHANICAL ROOM INFO		N/A
S205B	MECHANICAL ROOM	REFER TO S103B AND VICINITY									SUSPECT		2ND FLOOR OF THE MECHANICAL ROOM - PLEASE REFER TO MECHANICAL ROOM INFO		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S205K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	UNKNOWN	27531-1A-C	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY OHE IN 2022 (OHE PROJECT 27531). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		SHEETING	BLACK/GREEN RUBBERY MATERIAL	CEILING		27531-2A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 27531). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	2	R-SA1	50-75	CHRYSTILE	POOR	C	YES	FRIABLE	MOULD IMPACTED FITTINGS SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05.		2
S205S	STAIRWELL	PLASTER	SMOOTH PLASTER	CEILING	UNKNOWN	16365-S02A-C	<0.5	TREMOLITE	GOOD	A	NO	FRIABLE	LOCATED OUTSIDE THE STAIRWELL AT LIGHT FIXTURE. SAMPLED BY MAPLE IN 2017. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S205V	MECHANICAL ROOM	REFER TO S103B AND VICINITY									SUSPECT		2ND FLOOR OF THE MECHANICAL ROOM - PLEASE REFER TO MECHANICAL ROOM INFO		N/A
S206	MEETING PLACE	NO SUSPECT ACM OBSERVED									NO				N/A
S206A	MEETING PLACE	NO SUSPECT ACM OBSERVED									NO				N/A
S206B	MEETING PLACE	NO SUSPECT ACM OBSERVED									NO				N/A
S206C	GALLERY 1265	NO SUSPECT ACM OBSERVED									NO				N/A
S206D	STARBUCKS	NO SUSPECT ACM OBSERVED									NO				N/A
S206E	STARBUCKS	NO SUSPECT ACM OBSERVED									NO				N/A
S206K	MEETING PLACE	NO SUSPECT ACM OBSERVED									NO				N/A
S206S	STAIRCASE	NO SUSPECT ACM OBSERVED									NO				N/A
S208	STORAGE	GREY VINYL SHEET FLOORING	BROWN MOSAIC SHEET FLOORING	FLOOR		R-SA-012 & R-SA-108(A-C)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	1	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN				GOOD	A	SUSPECT	NON-FRIABLE			4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S208A	BELL CANADA ROOM	GREY VINYL SHEET FLOORING	LIGHT BROWN MOSAIC- NEW	FLOOR		R-SA-012 & R-SA-108(A-C)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	1	R-SA1	50-75	CHRYSTILE	POOR	C	YES	FRIABLE	PRESENT IN CEILING SPACE. THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	SELECT FITTINGS REMOVED IN OCTOBER 2019 ACCORDING TO UTSC NOTICE OF PROJECT.		4
		ELECTRICAL WIRES AND CABLE SHEATHING	ELECTRICAL WIRES AND CABLE SHEATHING	GENERAL ROOM	UNKNOWN				GOOD	B	SUSPECT		ALL EQUIPMENT WAS LIVE- NO ACCESS- PRESUMED ACM UNTIL PROVEN OTHERWISE		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN				GOOD	A	SUSPECT	NON-FRIABLE			4
S208B	OFFICE	NEW LAY-IN CEILING TILES									NO			RENOVATED IN 2021 (NEW CEILING TILES INSTALLED).	N/A
S208C	BELL CANADA ROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN				GOOD	A	SUSPECT	NON-FRIABLE			4
S208V	BELL CANADA ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS										ONE FITTING REMOVED IN 2019 (MAPLE PROJECT (#18314). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN				GOOD	A	SUSPECT	NON-FRIABLE			4
S209	MEETING ROOM	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	400 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA89		ND			NO				N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S209E	ELEVATOR MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S209K	CORRIDOR	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	730 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	25-35	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014. FITTINGS WERE NOT OBSERVED DURING THE 2021 REASSESSMENT SURVEY, PRESUMED TO BE PRESENT.		4
S210E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S210K	CORRIDOR	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	730 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	25-35	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014. FIFTEEN FITTINGS REMOVED IN 2019 (MAPLE PROJECT #18314). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S210S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		GREY CAULKING AROUND DOOR GLASS PANELS	DOOR CAULKING	DOOR TO STAIRWELL	14 L. FT.	25622-022-1A-C	3	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		GREY CAULKING AROUND DOOR GLASS PANELS	DOOR CAULKING	DOOR TO STAIRWELL	1 L. FT.	25622-022-1A-C	3	CHRYSTILE	FAIR	A	YES	NON-FRIABLE	REMOVE DAMAGED MATERIALS FOLLOWING TYPE 1 ASBESTOS PROCEDURE, AS PRESCRIBED UNDER O.REG. 278/05. SAMPLED BY OHE (PROJECT #25622-022) IN 2022		2
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S211	ELECTRICAL	NO SUSPECT ACM OBSERVED									NO				N/A
S212	FACILITIES MANAGEMENT OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	520 SQ. FT.	S01A-E		ND			NO		SAMPLED BY MAPLE (PROJECT #18602) IN 2020		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		CARPET	CARPET	FLOOR	80 SQ. FT.						NO		FLOOR TILES MAY BE PRESENT UNDER THE CARPET		N/A
S212A	FACILITIES MANAGEMENT OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	360 SQ. FT.	S01A-E		ND			NO		SAMPLED BY MAPLE (PROJECT #18602) IN 2020		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	12x12 VINYL FLOOR TILE								NO		NEW. MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S212B	FACILITIES MANAGEMENT OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	360 SQ. FT.	S01A-E		ND			NO		SAMPLED BY MAPLE (PROJECT #18602) IN 2020		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	12x12 VINYL FLOOR TILE								NO		NEW. MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S212C	FACILITIES MANAGEMENT OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	360 SQ. FT.	S01A-E		ND			NO		SAMPLED BY MAPLE (PROJECT #18602) IN 2020		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	12x12 VINYL FLOOR TILE								NO		NEW. MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S213A	MEN'S CHANGE ROOM	MASTIC	YELLOW	FLOOR - UNDER CARPET		26181-3A, 26181-3B, 26181-3C		ND			ND		SAMPLED BY OHE (Project #26181) IN 2020.		N/A
		QUARRY TILES	GROUT	FLOOR		26181-2A, 26181-2B, 26181-2C		ND			ND		SAMPLED BY OHE (Project #26181) IN 2020.		N/A
		QUARRY TILES	MORTAR	FLOOR		26181-1A, 26181-1B, 26181-1C		ND			ND		SAMPLED BY OHE (Project #26181) IN 2020.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	5+	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED ACCESS TO FITTINGS DUE TO DUCTS. ONLY NOT INSULATED PIPING WAS OBSERVED DURING THE 2017 ASSESSMENT, PRESUMED TO BE PRESENT		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.	R-SA89		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S213B	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	4	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S213K	CORRIDOR	2'x4' ACOUSTIC TILES	LONG FISSURES AND PINHOLES	CEILING		25995-9A, 25995-9B, 25995-9C		ND			NO		SAMPLED BY OHE (PROJECT 25995) IN 2020.		N/A
S214	WOMEN'S WASHROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.	R-SA13		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	600 SQ. FT.	R-SA13		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	WALL SPACE	8	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	CEILING IS NOW DRYWALL- LIMITED ACCESS		4
S214V	VESTIBULE	2'x4' ACOUSTIC TILES	LONG FISSURES AND PINHOLES	CEILING		25995-8C		ND			NO		SAMPLED BY OHE (PROJECT 25995) IN 2020.		N/A
S215	JANITOR CLOSET	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	GENERAL ROOM	1	R-SA1	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	ACM MASTIC AND FLOOR TILE REMOVED IN 2018 (MAPLE PROJECT #16726). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		JANITOR CLOSET	BLACK MASTIC	FLOOR MASTIC									REMOVED IN FEBRUARY 2018 ACCORDING TO UTSC NOTICE OF PROJECT.		N/A
S216	MEN'S WASHROOM	DRYWALL	DRYWALL JOINT COMPOUND	CEILING		25622-022-29A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). ALSO SAMPLED BY MAPLE IN 2020 (OHE PROJECT 18764). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	WALL SPACE	MIN 2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	NUMBER OF PIPE FITTINGS IS UNDETERMINED. DRYWALL CEILING- COULD NOT ACCESS		4
S216V	VESTIBULE	2'x4' ACOUSTIC TILES	LONG FISSURES AND PINHOLES	CEILING		25995-8A, 25995-8B		ND			NO		SAMPLED BY OHE (PROJECT 25995) IN 2020.		N/A
S217	OFFICE & DUCT SHAFT	CARPET	9x9 RED FLOOR TILE								NO		ASBESTOS-CONTAINING VINYL FLOOR TILES REMOVED IN 2016. ASBESTOS-CONTAINING MASTIC MAY STILL BE PRESENT BENEATH THE CARPET.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S218	LECTURE HALL	VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR	600 SQ. FT.	R-SA15 & R-SA(103-107)-06		ND			NO				N/A
		VINYL FLOOR TILES	12x12 VINYL FLOOR TILE	FLOOR	1152 SQ. FT.	R-SA88 & SA113-B-06	<5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		PLASTER	WHITE PLASTER	CEILING		25897-1A, 25891-1B, 25891-1C		ND			ND		SAMPLED BY OHE (Project #25891) IN 2020.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S218A	LECTURE HALL - STORAGE	VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR	800 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM AND CEILING	~15	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE			4
		VINYL FLOOR TILES	9x9 BROWN FLOOR TILE	FLOOR - SPORADIC DAMAGE	8 SQ. FT.	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	POOR	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S218K	LECTURE HALL - HALLWAY	NO SUSPECT ACM OBSERVED									NO				N/A
S218S	STAIRCASE	NO SUSPECT ACM OBSERVED									NO				N/A
S219	OFFICE	VINYL SHEET FLOORING		NEW 2009							NO				N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	ABOVE DUCT	2 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA11 & SA120-(A-C)-06		ND			NO				N/A
S219A	OFFICE	VINYL SHEET FLOORING		NEW 2009							NO				N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	ABOVE DUCT	2 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA11 & SA120-(A-C)-06		ND			NO				N/A
S219B	OFFICE	VINYL SHEET FLOORING		NEW 2009							NO				N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	ABOVE DUCT	2 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA11 & SA120-(A-C)-06		ND			NO				N/A
S219C	OFFICE	VINYL SHEET FLOORING		NEW 2009							NO				N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	ABOVE DUCT	2 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA11 & SA120-(A-C)-06		ND			NO				N/A
S219D	OFFICE	VINYL SHEET FLOORING		NEW 2009							NO				N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	ABOVE DUCT	2 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING		R-SA11 & SA120-(A-C)-06		ND			NO				N/A
S219V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S220	OFFICE	VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	400 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR - SPORADIC DAMAGE	4 SQ. FT	R-SA18	5	CHRYSTILE	POOR	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	240 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S221	BIOARCHEOLOGY LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S221A	ANTHROPOLOGY RESEARCH LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S221E	MECHANICAL SHAFT	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S222	ANTHROPOLOGY LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S222A	LAB SUPPORT	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S222V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S223	PALEONTOLOGY LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S223A	MEETING ROOM	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S223B	PRIMATOLOGY LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16557). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S225	LAB SUPPORT	NEW LAY-IN CEILING TILES	2X4 CEILING TILE								NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	384 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RENOVATIONS IN MARCH 2011. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S225A	WASH STERILIZATION	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	1296 SQ. FT.	R-SA11		ND			NO		VERY LIMITED ACCESS AND VISIBILITY ABOVE THE CEILING TILES - ADDITIONAL SAMPLING IS RECOMMENDED		N/A
		ASBESTOS WOVEN MATERIAL	ASBESTOS WOVEN MATERIAL	OVENS	20 SQ. FT				GOOD	A	SUSPECT	FRIABLE	NO SAMPLE - PRESUMED ACM		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	GENERAL ROOM / CEILING SPACE	25-30	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	INSULATION ON THE CONDENSATE TANK WAS REMOVED IN 2022 (CURMANN PROJECT 22-0145)		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	PARGING CEMENT	GENERAL ROOM / CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	FAIR	A	YES	FRIABLE	MOULD IMPACTED FITTINGS SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05.		2
S225V	VESTIBULE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S226	MECHANICAL ROOM	TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	ABOVE CEILING - AROUND DUCT	30 SQ. FT.				GOOD	B	SUSPECT				4
S226A	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO		ACM MAY BE PRESENT WITH THE INTERNAL COMPONENTS OF THE TRANSFORMERS PRESENT WITHIN THE ROOM- PRESUME ACM ARE PRESENT UNTIL PROVEN OTHERWISE		N/A
S227A	CENTRE FOR THE NEUROBIOLOGY OF STRESS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS		18765A-01A-C, 18765A-02A-C		ND			NO		SAMPLED BY MAPLE (PROJECT #18765A) IN 2020		N/A
		CERAMIC TILE									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S227B	CENTRE FOR THE NEUROBIOLOGY OF STRESS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS		18765A-01A-C, 18765A-02A-C		ND			NO		SAMPLED BY MAPLE (PROJECT #18765A) IN 2020		N/A
		CERAMIC TILE									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S227C	CENTRE FOR THE NEUROBIOLOGY OF STRESS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS		18765A-01A-C, 18765A-02A-C		ND			NO		SAMPLED BY MAPLE (PROJECT #18765A) IN 2020		N/A
		CERAMIC TILE									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S228	CENTRE FOR THE NEUROBIOLOGY OF STRESS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	UNDER SINK	UNKNOWN	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	REMOVED WHERE VISIBLE, FITTINGS MAY BE BEHIND MILLWORK		4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	COUNTERS AND FUME HOOD	~150 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S228A	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		CERAMIC TILE									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S228E	SHAFT	NO SUSPECT ACM OBSERVED									NO				N/A
S228V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A
S229	CENTRE FOR THE NEUROBIOLOGY OF STRESS	TRANSITE™ ASBESTOS-CEMENT	LAB COUNTER	COUNTER	150 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	330 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. POSSIBLY STILL PRESENT BENEATH NEW VINYL SHEET FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	320 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	UNDER SINK	~5-10	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	REPAIRED IN 2014		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S229A	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL	320 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S229B	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL	320 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.





Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S229C	CENTRE FOR THE NEUROBIOLOGY OF STRESS	NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	320 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S229D	OFFICE	NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	320 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S230	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S230A	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S230B	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S231K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL CEILING SPACE	15	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	NOT OBSERVED DURING 2021 REASSESSMENT		4
		2'x4' ACOUSTIC TILES	LONG FISSURES AND PINHOLES	CEILING		25995-10A, 25995-10B, 25995-10C		ND			NO		SAMPLED BY OHE (PROJECT 25995) IN 2020.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL NEAR CEILING ACROSS FROM S229		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S231S	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL NEAR CEILING ACROSS FROM S229		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S231V	VESTIBULE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		SA3-A-07		ND			NO				N/A
		2'x4' ACOUSTIC TILES	PINHOLES AND SMALL FISSURES	CEILING		25995-7C		ND			NO		SAMPLED BY OHE (PROJECT 25995) IN 2020.		N/A
		2'x4' ACOUSTIC TILES	LONG FISSURES AND PINHOLES	CEILING		25995-11A, 25995-11B, 25995-11C		ND			NO		SAMPLED BY OHE (PROJECT 25995) IN 2020.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	4	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	1 FITTING REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S232	ELECTRICAL	SUSPECT ACM FITTING	FITTINGS	CEILING	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	WALL - CORNER OF ROOM	1 SQ. FT.	SA22	15-25	CROCIDLITE	GOOD	C	YES	NON-FRIABLE	ACM MAY BE PRESENT WITH THE INTERNAL COMPONENTS OF THE ELECTRICAL EQUIPMENT PRESENT WITHIN THE ROOM- PRESUME ACM ARE PRESENT UNTIL PROVEN OTHERWISE		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S233	LECTURE HALL	VINYL FLOOR TILES	12x12 VINYL FLOOR TILE	FLOOR	1250 SQ. FT.	R-SA113-B-06 & R-SA88	<5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR	825 SQ. FT.	R-SA12 & R-SA(103-105)-06		ND			NO				N/A
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR		R-SA24	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		WALL PANELS	PAPER INSULATION	WALL - BEHIND PANELS		25891-6A	70	CHRYSTILE	GOOD	C	YES	FRIABLE	SAMPLED BY OHE (Project #25891) IN 2020.		4
		WALL PANELS - PERIMETER WALL	PAPER INSULATION	WALL - BEHIND PANELS		27061-1A, 27061-1B, 27061-1C		ND			NO		SAMPLED BY OHE (Project #27061) IN 2021.		N/A
		WALL PANELS - PERIMETER WALL	TAR	WALL - BEHIND PANELS, UNDER FIBREGLOSS		27061-2A, 27061-2B, 27061-2C		ND			NO		SAMPLED BY OHE (Project #27061) IN 2021.		N/A
		PLASTER	WHITE & GREY PLASTER	CEILING		25891-2, 25891-2B, 25891-2C		ND			NO		SAMPLED BY OHE (Project #25891) IN 2020.		N/A
S233K	LECTURE HALL - HALLWAY	VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR	825 SQ. FT.	R-SA12 & R-SA(103-105)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S233A	LECTURE HALL - BACK ROOM	VINYL FLOOR TILES	12x12 BROWN FLOOR TILE	FLOOR	800 SQ. FT	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		VINYL FLOOR TILES	12x12 BROWN FLOOR TILE	FLOOR	2 SQ. FT	R-SA86 & R-SA112-A-06	<2	CHRYSTILE	FAIR	A	YES	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	 	2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	9	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES (2ND LEVEL)	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA1	50-75	CHRYSTILE	POOR	C	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. DEBRIS ON FLOOR SHOULD BE REMOVED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	 	2
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25891-5A	2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY OHE (Project #25891) IN 2020.		4
S233S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S234A	CENTRE FOR THE NEUROBIOLOGY OF STRESS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS		GENERAL ROOM	4		50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
S234B	CENTRE FOR THE NEUROBIOLOGY OF STRESS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	UNDER SINK							NO		SIX FITTINGS REMOVED IN 2019 (MAPLE PROJECT (#18235). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	UNKNOWN	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S234C	CENTRE FOR THE NEUROBIOLOGY OF STRESS	VINYL SHEET FLOORING	BROWN MOSAIC	FLOOR		R-SA12 & R-SA108(A-C)-06		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S234D	CENTRE FOR THE NEUROBIOLOGY OF STRESS	VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR		SA-(103-107)-06		ND			NO		NO ACCESS ABOVE THE CEILING		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S234E	CENTRE FOR THE NEUROBIOLOGY OF STRESS	VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR		R-SA(103-107)-06		ND			NO		NO ACCESS ABOVE THE CEILING		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S234F	CENTRE FOR THE NEUROBIOLOGY OF STRESS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	IN ROOM BELOW TABLE	4	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR		SA106-06		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S234G	BIOLOGY TEACHING PREP	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. LIMITED ACCESS ABOVE CEILING DUE TO DUCTS ABOVE THE CEILING.		N/A
S234H	BIOLOGY TEACHING PREP	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. LIMITED ACCESS ABOVE CEILING DUE TO DUCTS ABOVE THE CEILING.		N/A
S234V	CENTRE FOR THE NEUROBIOLOGY OF STRESS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S235A	CENTRE FOR THE NEUROBIOLOGY OF STRESS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	BEHIND SINK	UNKNOWN	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE			4
		PARGING CEMENT INSULATION	INSULATION	BELOW SINK	2 SQ. FT	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	COUNTERS	100 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-2A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (PROJECT 25622-022)		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	BULKHEAD		DJC-02A-C	ND	ND			NO		SAMPLED IN 2021 BY GOLDER (PROJECT 21481817(1000))		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S235B	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S235C	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S235D	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S235E	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions


ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S235F	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S235G	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL		26835-1A-C			ND		NO		MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS. SAMPLED BY OHE IN AUGUST 2021 (OHE PROJECT #26835). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S236	CENTRE FOR THE NEUROBIOLOGY OF STRESS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	UNDER SINK							NO		REMOVED IN 2020 (MAPLE PROJECT (#18470). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	VERTICAL BRICK CHASES	16						SUSPECT		ALL ACCESSIBLE FITTINGS REMOVED IN 2022 (GOLDER PROJECT 21507943). ASBESTOS-CONTAINING PARGING CEMENT MAY STILL BE PRESENT IN PIPE SHAFT AND BEHIND MILLWORK.		4
		TRANSITE™ ASBESTOS-CEMENT	ASBESTOS CEMENT	COUNTERS AND FUME HOOD							NO		REMOVED IN 2020 (MAPLE PROJECT (#18470). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	ACM TILES AND MASTIC ALSO PRESENT UNDER CERAMIC FLOOR							NO		REMOVED IN 2020 (MAPLE PROJECT (#18470). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-3A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022)		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S236A	CENTRE FOR THE NEUROBIOLOGY OF STRESS	DRYWALL	DRYWALL JOINT COMPOUND	WALL		18010 S04A-C & DJC03A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT 18010) AND BY GOLDER IN 2022 (GOLDER PROJECT 22521196-1000 .		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S236E	SHAFT	NO SUSPECT ACM OBSERVED									NO				N/A
S236V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE			ND	ND			NO		REMOVED IN 2022 (GOLDER PROJECT 21507943).		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		PLA-A-C	ND	ND			NO		SAMPLED BY GOLDER (PROJECT #21507943) IN 2022.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S237	BIOLOGICAL SCIENCES TEACHING PREP	TRANSITE™ ASBESTOS-CEMENT	COUNTER AND FUME HOOD	GENERAL ROOM	200 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE			4
		TRANSITE™ ASBESTOS CEMENT	COUNTER AND FUME HOOD	GENERAL ROOM	10 SQ. FT	R-SA22	15-25	CROCIDOLITE	POOR	A	YES	NON-FRIABLE	MOULD IMPACTED AND WATER STAINED. REMOVE AND REPLACE THE DAMAGED TRANSITE PANEL FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES	FITTINGS												N/A
		PLASTER	PLASTER	ABOVE DOOR		PLA01D	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		MILLBOARD	MILLBOARD	UPPER WALL CAVITIES	2 SQ. FT.	MB01	15	AMOSITE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		CAULKING	RED CAULKING	CEILING/PIPE PENETRATIONS	7 LN. FT.	CLK02	1	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		CAULKING	LIGHT BROWN CAULKING	PERIMETER, BETWEEN WALL AND CEILING	50 LN. FT.	CLK04	4	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		VINYL SHEET FLOORING	PINK	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		MASTIC	BLACK MASTIC	UNDER VINYL FLOORING	750 SQ. FT.	VSF01A-C	2	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		ADHESIVE	BASEBOARD ADHESIVE	VINYL BASEBOARD			ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	UNDER LAB BENCHES	200 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	C	YES	NON-FRIABLE			4
		VINYL SHEET FLOORING	BROWN MOSAIC	FLOOR	825 SQ. FT.	R-SA12 & R-SA108-(A-C)-06	ND	ND			NO				N/A
S238	LAB MANAGER OFFICE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06	ND	ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	AROUND DOOR		DJC02A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	BEHIND SIDE BENCH				CHRYSTILE	GOOD	C	YES	FRIABLE			4
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	UNDER LAB BENCHES	50 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	C	YES	NON-FRIABLE			4
		VINYL SHEET FLOORING	GREEN-YELLOW	FLOOR		VSF02A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	CEILING - BY DUCTS	15 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	LAB COUNTERS	25 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S239	LIFE SCIENCES	VINYL SHEET FLOORING	BROWN MOSAIC	FLOOR	825 SQ. FT.	R-SA-012 & R-SA-108(A-C)-06		ND			NO				N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	350 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO		WITHIN S239		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	150 SQ. FT..				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	GENERAL	25 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S239A	LIFE SCIENCES	VINYL SHEET FLOORING	BROWN MOSAIC	FLOOR	825 SQ. FT.	R-SA-012 & R-SA-108(A-C)-06		ND			NO				N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	350 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO		WITHIN S239		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	150 SQ. FT..				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	GENERAL	25 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S239V	VESTIBULE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S240	LAB	DRYWALL (NEW - 2022)	DRYWALL JOINT COMPOUND	WALLS									MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
		VINYL FLOOR TILES	9X9 RED FLOOR TILES AND BLACK MASTIC	FLOOR									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		TRANSITE ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS, BENCHTOPS, AND SINKS									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		CAULKING AROUND DOOR FRAMES	TAN CAULKING										REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS										REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		MILLBOARD	MILLBOARD										REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
S241	LAB	ACOUSTIC TILES	CEILING TILES (NEW - 2022)	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING									CEILING AND 3 WALL PARTITIONS REMOVED IN 2021 (GOLDER 21467665).		N/A
		VINYL FLOOR TILES	9X9 RED FLOOR TILE AND BLACK MASTIC	FLOOR									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		TRANSITE ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS, BENCHTOPS, AND SINKS									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		CAULKING AROUND DOOR FRAMES	TAN CAULKING	DOORS	3 DOORS								REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		MILLBOARD	MILLBOARD	WALLS BETWEEN S240/S241 AND S241/S242									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
S241 E	SHAFT	BLACK MASTIC	BLACK MASTIC	WALL MASTIC		17594 S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17594). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		GREY CAULKING	GREY CAULKING	DUCT MASTIC		17594 S02A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17594). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S241V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	4 PARGING CEMENT FITTINGS REMOVED IN 2019 (MAPLE PROJECT #17648). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY. 1 PARGING CEMENT FITTING WAS REMOVED BY ENVIROSAFE IN JUNE 2020.		4
		CAULKING		AROUND DOOR FRAMES									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S242	LAB	DRYWALL (NEW - 2022)	DRYWALL JOINT COMPOUND	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
		VINYL FLOOR TILES	9X9 RED FLOOR TILE AND BLACK MASTIC	FLOOR									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		TRANSITE ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS, BENCHTOPS, AND SINKS									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		CAULKING AROUND DOOR FRAMES	TAN CAULKING	DOORS	2 DOORS								REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
		MILLBOARD	MILLBOARD	WALL BETWEEN S241 / S242									REMOVED IN 2021 (GOLDER PROJECT #21467665).		N/A
S244	VACANT ROOM	VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	150 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. NEW VINYL SHEET FLOORING OBSERVED. MAY BE PRESENT BENEATH NEW VINYL SHEET FLOORING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC04A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		CAULKING	BEIGE CAULKING	DOOR FRAME	2 L.FT.	25622-022-4A-C	2	CHRYSTILE	POOR	A	YES	NON-FRIABLE	SAMPLED BY OHE IN 2022 (PROJECT 25622-022). REMOVE FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		MASTIC	MASTIC	FLOOR							YES		REMOVED ON AUGUST 2019 ACCORDING TO UTSC NOTICE OF PROJECT.		N/A
S244A	VACANT ROOM	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	50 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER	12 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S244B	LINGUISTICS LAB	VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	150 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. NEW VINYL SHEET FLOORING OBSERVED. MAY BE PRESENT BENEATH NEW VINYL SHEET FLOORING.		4
		ACOUSTIC TILES	2'x4' LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06	ND	ND			NO				N/A
		MASTIC	MASTIC	FLOOR							YES		REMOVED ON AUGUST 2019 ACCORDING TO UTSC NOTICE OF PROJECT.		N/A
S245K	CORRIDOR	ACOUSTIC TILES	2'x4' LENGTH-WISE FISSURE	CEILING		R-SA11, R-SA120-(A-F)-06 & ACT-01A-C	ND	ND			NO		SAMPLED IN 2021 BY GOLDER (PROJECT 21481817(1000))		N/A
		CEILING TILES	2'X4' TEXTURE PINHOLE	CEILING		AT-02A-C	ND	ND			NO		SAMPLED IN 2021 BY GOLDER (PROJECT 21481817(1000))		N/A
		PLASTER	PLASTER SKIM	UNDERSIDE OF CEILING TRENCH COVER		PL-01A-C	ND	ND			NO		SAMPLED IN 2021 BY GOLDER (PROJECT 21481817(1000))		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	4	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	ACCESSIBLE PARGING CEMENT FITTINGS REMOVED IN 2019 (MAPLE PROJECT #17648) AND IN 2022 (GOLDER PROJECT 21507943). INACCESSIBLE PARGING CEMENT REMAINS IN THE CEILING SPACE.		4
S245S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S245V	VESTIBULE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO		2 PARGING CEMENT FITTINGS REMOVED IN 2019 (MAPLE PROJECT #17648). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PLASTER	PLASTER	ABOVE DOOR		PLA01G	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
S246	SEM BIOLOGICAL SCIENCES	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S246A	SEM BIOLOGICAL SCIENCES	PLASTER	PLASTER	CEILING							NO				N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	LAB COUNTERS	5 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S247	BIOLOGY OFFICE	TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	LAB COUNTERS	10 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		2'x4' ACOUSTIC TILES	DRYWALL	CEILING							NO				N/A
S247A	CLEANERS & SHAFT	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	PIPE SHAFT	6 TO 10	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	WALL AT CEILING - BACK OF ROOM	2 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE	SOME OF THIS MATERIAL WAS REMOVED AND REPLACED BY FERRO CANADA INC. ON NOVEMBER 22, 2010.		4
		MASTIC	BROWN MASTIC	WALLS	10 SQ. FT.				GOOD	A	SUSPECT		SUSPECT MATERIAL		4
		WALL CAVITY BOARD		UPPER WALL			ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		PLASTER	PLASTER	ABOVE DOOR		PLA01H	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S247V	VESTIBULE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S248	LAB	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER									REMOVED IN 2020 (OHE PROJECT #25924)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS										REMOVED IN 2020 (OHE PROJECT #25924)		N/A
		NEW VINYL SHEET FLOORING									NO		REMOVED IN 2020 (OHE PROJECT #25924)		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S249	LAB	VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR									REMOVED IN 2020 (OHE PROJECT #25924)		N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER									REMOVED IN 2020 (OHE PROJECT #25924)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES									REMOVED IN 2020 (OHE PROJECT #25924)		N/A
S249E	SHAFT	CONCEALED ACM MAY BE PRESENT									SUSPECT				4
S249V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES									REMOVED IN 2020 (OHE PROJECT #25924)		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S250	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING - BACK OF ROOM									REMOVED IN 2020 (OHE PROJECT #25924)		N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER									REMOVED IN 2020 (OHE PROJECT #25924)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS										REMOVED IN 2020 (OHE PROJECT #25924)		N/A
S251	TRANSFORMER ROOM	TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	WALL	20 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		ELECTRICAL EQUIPMENT	ELECTRICAL EQUIPMENT	ELECTRICAL EQUIPMENT	300 SQ. FT.				GOOD	B	SUSPECT		ACM MAY BE PRESENT WITHIN THE INTERNAL COMPONENTS OF THE TRANSFORMERS PRESENT WITHIN THE ROOM- PRESUME ACM IS PRESENT UNTIL PROVEN OTHERWISE		4
		PLASTER	PLASTER	ABOVE DOOR		PLA01I	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		MILLBOARD	LIGHT GREY MILLBOARD	UPPER WALL CAVITIES	8 SQ. FT.	MB02	8 & 8	CHRYSTILE & CROCIDOLITE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		CAULKING	GREY CAULKING	AROUND MILLBOARD IN CEILING SPACE	20 LN. FT.	CLK03A-C	2	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	S251 - ABOVE DOORS	35 SQ. FT.	01-F	ND	ND			NO		SAMPLE LOCATION. SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S251A	TRANSFORMER ROOM	ELECTRICAL EQUIPMENT	ELECTRICAL EQUIPMENT	ELECTRICAL EQUIPMENT	300 SQ. FT.				GOOD	B	SUSPECT		ACM MAY BE PRESENT WITHIN THE INTERNAL COMPONENTS OF THE TRANSFORMERS PRESENT WITHIN THE ROOM- PRESUME ACM IS PRESENT UNTIL PROVEN OTHERWISE		4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	CEILING	40 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	SUSPECT MATERIAL		4
S252	BIOLOGY TEACHING PREP	TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	WALL AT DUCT PENETRATION	15 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		MILLBOARD	MILLBOARD	WALL CAVITIES	8 SQ. FT.	MB02	8 & 8	CHRYSTILE & CROCIDOLITE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		CAULKING	GREY CAULKING	AROUND MILLBOARD IN CEILING SPACE	20 LN. FT.	CLK03	2	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S252V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	3	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PLASTER	PLASTER	ABOVE DOOR		PLA01J	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.

B - Accessible only to maintenance staff and exposed to view without moving a building compound.

C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 - Perform asbestos removal/repair for compliance with the regulations.

3 - Type 2 asbestos procedures required to enter area.

4 - Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.



Definitions

ACM - Asbestos-Containing Materials

SA - Sample representative

R-SA - Sample referenced to a visually similar homogeneous sample material.




ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S253	BIOLOGICAL SCIENCES PREP ROOM	VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	340 SQ. FT.	R-SA18 & VFT04A-C	2-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR - SPORADIC DAMAGE	6 SQ. FT.	R-SA18 & VFT04A-C	2-5	CHRYSTILE	POOR	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		MASTIC	BLACK MASTIC	FLOOR - UNDER FLOOR TILES	340 SQ. FT.	VFT04A-C	3	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	2 SQ.FT.	DJC05 & 25622-022-5A-C	1	CHRYSTILE	FAIR	A	YES	NON-FRIABLE	REPAIR FOLLOWING TYPE 1 ASBESTOS PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.	DJC05 & 25622-022-5A-C	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER (PROJECT 22521196-1000) & OHE (PROJECT 25622-022) IN 2022		4
		MILLBOARD	MILLBOARD	WALL CAVITIES	8 SQ. FT.	MB02	8 & 8	CHRYSTILE & CROCIDOLITE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		CAULKING	GREY CAULKING	AROUND MILLBOARD IN CEILING SPACE	20 LN. FT.	CLK03	2	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	AT WALL ABOVE CEILING TILES	3 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	C	YES	NON-FRIABLE			4
S253A	DARK ROOM	VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	180 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	120 SQ. FT.	DJC05	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2022 (PROJECT 22521196-1000)		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S253B	DARK ROOM	VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	180 SQ. FT.	R-SA18	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC		4
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	FLOOR	1 SQ. FT.	R-SA18	5	CHRYSTILE	FAIR	A	YES	NON-FRIABLE	ACM DETECTED IN BOTH TILE AND MASTIC. THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. LIMITED ACCESS DUE TO ROOM BEING USED AS STORAGE.		2
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	5 SQ. FT.	25622-022-5A-C	1	CHRYSTILE	POOR	A	YES	NON-FRIABLE	SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.	DJC05 & 25622-022-5A-C	1	CHRYSTILE	YES	A	YES	NON-FRIABLE	SAMPLED BY GOLDER (PROJECT 22521196-1000) & OHE (PROJECT 25622-022) IN 2022		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S254A	TELECOM ROOM	DRYWALL	DRYWALL JOINT COMPOUND (BEIGE)	WALL	7 SQ. FT.	25622-022-7A-C	1	CHRYSTILE	POOR	A	YES	NON-FRIABLE	SAMPLED BY OHE IN 2022 (OHE PROJECT #25622-022). DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05.		2
		DRYWALL	DRYWALL JOINT COMPOUND (BEIGE)	WALL	250 SQ. FT.	25622-022-7A-C	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY OHE IN 2022 (OHE PROEJCT #25622-022).		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GROUND LEVEL	1	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE	LOCATED IN CORNER OF ROOM AT GROUND LEVEL		4
S254E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S254S	STAIRWELL	TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	WALL AT CEILING	3 SQ. FT	R-SA22	15-25	CROCIDLITE	GOOD	C	YES	NON-FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S255	LAUNDRY ROOM	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S255A	SPRINKLER VALVE ROOM	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S255V	VESTIBULE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S256E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				4
S256K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.						NO		SAMPLED BY OHE IN 2022 (OHE PROJECT NO. 25622-026). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S257	DRESSING ROOM	DRYWALL	DRYWALL JOINT COMPOUND	BULKHEAD	UNKNOWN				GOOD	A	SUSPECT	NON-FRIABLE			4
		VINYL SHEET FLOORING	NEW SHEET FLOORING (2009)	FLOOR	121 SQ. FT.						SUSPECT	NON-FRIABLE	MASTIC UNDER THE NEW SHEET FLOORING IS PRESUMED TO BE ACM.		4
S257A	MEN'S WASHROOM	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.	25622-022-9A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT NO. 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S259	DRESSING ROOM	DRYWALL	DRYWALL JOINT COMPOUND	BULKHEAD					GOOD	A	SUSPECT	NON-FRIABLE			4
		VINYL FLOOR TILES	9x9 RED FLOOR TILES	NEW - 2009	161 SQ. FT.	R-SA18	5	CHRYSTOTILE	GOOD	A	YES	NON-FRIABLE	MASTIC IS PRESUMED TO BE ACM. NO ACCESS ABOVE THE CEILING		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S259A	WOMEN'S WASHROOM	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S260	2ND LEVEL STUDIO	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S260A	RENOVATED ROOMS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S260B	THEATRE & CONTROL BOOTH	DRYWALL	DRYWALL JOINT COMPOUND	WALL	2000 SQ. FT.	25622-022-31A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		VINYL FLOOR TILES	12x12 BLACK VINYL FLOOR TILE	FLOOR - CONTROL BOOTH	150 SQ.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL SPACE	9	R-SA1	50-75	CHRYSTOTILE	GOOD	A	YES	FRIABLE			4
S260C	RENOVATED ROOMS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S260F	RENOVATED ROOMS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S260K	RENOVATED ROOMS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S260S	RENOVATED ROOMS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S260E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S261	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S261S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S262	STORAGE	TRANSITE™ ASBESTOS-CEMENT	2X4 ASBESTOS WALL TILES WITH HOLES	WALL	100 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.	25622-022-32A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S262A	SHOWER	TRANSITE™ ASBESTOS-CEMENT	2X4 ASBESTOS WALL TILES WITH HOLES	WALL	100 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S262B	GREEN ROOM	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	50 SQ. FT.	25622-022-33A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S300	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	PARTITION WALL AT RECEPTION DESK		17982-01 S01 & DJC01G-I		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17982-01) AND BY GOLDER IN 2021 (21502859)		N/A
		LAY-IN CEILING TILES	TEXTURED PINHOLE	CEILING		AT01A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		YELLOW MASTIC	MASTIC	BELOW VINYL SHEET FLOORING		17982-01 S02		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17982-01). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		ADHESIVE	OFF-WHITE	BASEBOARD		ADH01A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S300A	HALLWAY	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01E		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S300B	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01A, B		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		CAULKING	COLOURLESS	WINDOW		CLK01A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		CAULKING	BLACK	WINDOW		CLK02A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		CAULKING	BLACK	WINDOW (EXTERIOR)		CLK04A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		ADHESIVE	BROWN	CARPET		ADH02A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
S300C	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01C, D		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		VINYL SHEET FLOORING	GREY	FLOOR		VSF01B		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		MASTIC	YELLOW	BELOW VINYL SHEET FLOORING		VSF01B		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
S300D	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	NORTH WALL		17982 S01A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17982). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S300E	KITCHENETTE	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01F		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		CAULKING	CLEAR	FLOOR		CLK03A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		VINYL SHEET FLOORING	GREY	FLOOR		VSF01C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		MASTIC	YELLOW	BELOW VINYL SHEET FLOORING		VSF01C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
S300F	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01K		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		VINYL SHEET FLOORING	GREY	FLOOR		VSF01A		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		MASTIC	YELLOW	BELOW VINYL SHEET FLOORING		VSF01A		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
		ADHESIVE	BROWN	BELOW VINYL SHEET FLOORING		ADH03A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21502859)		N/A
S300K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL	20 SQ. FT.	25622-022-34A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	1000 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED ACCESS ABOVE CEILING.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S300L	ELEVATOR ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S300V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO		WOOD PANEL CEILING - NO ACCESS ABOVE		N/A
S301A	WASHROOM	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	10 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED ACCESS ABOVE CEILING. SUSPECT ACM PIPE FITTING INSULATION WITHIN CEILING SPACE AND WALL CAVITY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE- MIDDLE OF THE ROOM	1	R-SA1	50-75	CHRYSTOLE	GOOD	A	YES	FRIABLE	TWO FITTINGS REMOVED IN 2019 (MAPLE PROJECT (#18314). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S301S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S301V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO		NO ACCESS ABOVE THE CEILING		N/A
S302	DESIGN AND CONSTRUCTION MANAGEMENT	DRYWALL (NEW - 2020)	DRYWALL JOINT COMPOUND	WALLS AND CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		CARPET AND VINYL SHEETING FLOORING	BELOW CARPET AND VSF	FLOOR							NO		ALL PRE-EXISTING FLOOR MATERIALS (E.G. MASTIC) WERE SAMPLED BY MAPLE IN 2019 (PROJECT #17989-01) AND FOUND TO BE NON-ASBESTOS. REFER TO PROJECT DCM2019-03.		N/A
		DARK BROWN MASTIC	WALL MASTIC	EAST AND WEST WALLS	18237S01A-C		ND	ND			NO		SAMPLED BY MAPLE IN 2019 (PROJECT #18237).		N/A
		LIGHT BROWN MASTIC	CEILING MASTIC	CEILING	18237S02A-C		ND	ND			NO		SAMPLED BY MAPLE IN 2019 (PROJECT #18237).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS									REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO PROJECT DCM2019-03.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	PERIMETER RADIATOR UNITS									REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO PROJECT DCM2019-03.		N/A
		CAULKING	RED CAULKING ON FAN COILS	PERIMETER RADIATOR UNITS									REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO PROJECT DCM2019-03.		N/A
S302A	DESIGN AND CONSTRUCTION MANAGEMENT	REFER TO S302											ALL ACM REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO S302 FOR PROJECT DETAILS.		N/A
S302B	DESIGN AND CONSTRUCTION MANAGEMENT	REFER TO S302											ALL ACM REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO S302 FOR PROJECT DETAILS.		N/A
S302C	DESIGN AND CONSTRUCTION MANAGEMENT	REFER TO S302											ALL ACM REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO S302 FOR PROJECT DETAILS.		N/A
S302D	DESIGN AND CONSTRUCTION MANAGEMENT	REFER TO S302											ALL ACM REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO S302 FOR PROJECT DETAILS.		N/A
S302E	DESIGN AND CONSTRUCTION MANAGEMENT	REFER TO S302											ALL ACM REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO S302 FOR PROJECT DETAILS.		N/A
S302F	DESIGN AND CONSTRUCTION MANAGEMENT	REFER TO S302											ALL ACM REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO S302 FOR PROJECT DETAILS.		N/A
S302G	DESIGN AND CONSTRUCTION MANAGEMENT	REFER TO S302											ALL ACM REMOVED IN 2019 (MAPLE PROJECT #18222). REFER TO S302 FOR PROJECT DETAILS.		N/A
S302K	DESIGN AND CONSTRUCTION MANAGEMENT	DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING	100 SQ. FT.	17973 S03E	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		VINYL SHEET FLOORING	WOOD PATTERN	FLOOR	152 SQ. FT.						NO		RECENTLY INSTALLED		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S302V	DESIGN AND CONSTRUCTION MANAGEMENT	DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		17973 S03B		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		GREY LEVELLING COMPOUND	BELOW CARPET	FLOOR		17973 S02A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		YELLOW MASTIC	BELOW CARPET	FLOOR		17973 S02A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S303	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND					SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	UNKNOWN				GOOD		PRESUMED	NON-FRIABLE	PRESUMED ACM. ASBESTOS-CONTAINING PARGING CMNT INSULATION MAY ALSO BE PRESENT ON PIPE FITTINGS WITHIN RADIATOR UNITS.		4
		BLACK TAR	BLACK TAR ON FIBREGLOSS INSULATION	PERIMETER RADIATOR UNITS		TAR01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
S303A	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
S303B	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	UNKNOWN				GOOD		PRESUMED	NON-FRIABLE	PRESUMED ACM. ASBESTOS-CONTAINING PARGING CMNT INSULATION MAY ALSO BE PRESENT ON PIPE FITTINGS WITHIN RADIATOR UNITS.		4
		BLACK TAR	BLACK TAR ON FIBREGLOSS INSULATION	PERIMETER RADIATOR UNITS		TAR01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S303C	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	UNKNOWN				GOOD		PRESUMED	NON-FRIABLE	PRESUMED ACM. ASBESTOS-CONTAINING PARGING CMENT INSULATION MAY ALSO BE PRESENT ON PIPE FITTINGS WITHIN RADIATOR UNITS.		4
		BLACK TAR	BLACK TAR ON FIBREGLASS INSULATION	PERIMETER RADIATOR UNITS		TAR01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
S303D	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	UNKNOWN				GOOD		PRESUMED	NON-FRIABLE	PRESUMED ACM. ASBESTOS-CONTAINING PARGING CMENT INSULATION MAY ALSO BE PRESENT ON PIPE FITTINGS WITHIN RADIATOR UNITS.		4
		BLACK TAR	BLACK TAR ON FIBREGLASS INSULATION	PERIMETER RADIATOR UNITS		TAR01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
S303E	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
S303G	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	UNKNOWN				GOOD		PRESUMED	NON-FRIABLE	PRESUMED ACM. ASBESTOS-CONTAINING PARGING CMENT INSULATION MAY ALSO BE PRESENT ON PIPE FITTINGS WITHIN RADIATOR UNITS.		4
		BLACK TAR	BLACK TAR ON FIBREGLASS INSULATION	PERIMETER RADIATOR UNITS		TAR01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S303H	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	UNKNOWN				GOOD		PRESUMED	NON-FRIABLE	PRESUMED ACM. ASBESTOS-CONTAINING PARGING CMENT INSULATION MAY ALSO BE PRESENT ON PIPE FITTINGS WITHIN RADIATOR UNITS.		4
		BLACK TAR	BLACK TAR ON FIBREGLASS INSULATION	PERIMETER RADIATOR UNITS		TAR01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
S303I	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	UNKNOWN				GOOD		PRESUMED	NON-FRIABLE	PRESUMED ACM. ASBESTOS-CONTAINING PARGING CMENT INSULATION MAY ALSO BE PRESENT ON PIPE FITTINGS WITHIN RADIATOR UNITS.		4
		BLACK TAR	BLACK TAR ON FIBREGLASS INSULATION	PERIMETER RADIATOR UNITS		TAR01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
S303J	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		TRANSITE ASBESTOS CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	UNKNOWN				GOOD		PRESUMED	NON-FRIABLE	PRESUMED ACM. ASBESTOS-CONTAINING PARGING CMENT INSULATION MAY ALSO BE PRESENT ON PIPE FITTINGS WITHIN RADIATOR UNITS.		4
		BLACK TAR	BLACK TAR ON FIBREGLASS INSULATION	PERIMETER RADIATOR UNITS		TAR01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
S303K	CORRIDOR	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC02A-C	ND	ND			NO		SAMPLED BY GOLDER (PROJECT #22532220)		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S303L	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S303M	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010 S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
S303V	FACILITIES MANAGEMENT OFFICES	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING AND MASTIC	FLOOR		VSF01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		DJC01A-H, 18010S01-S03	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		ADHESIVE	BEIGE ON ADHESIVE ON VINYL BASEBOARDS	BASEBOARDS		ADH01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
		CAULKING	YELLOW CAULKING AROUND DRYWALL SEAMS	ABOVE CEILING TILES		CLK01A-C	ND	ND			NO		SAMPLED BY GOLDER IN 2022 (PROJECT #22532220) AND MAPLE IN 2019 (PROJECT #18010).		N/A
S303X	DESIGN AND CONSTRUCTION MANAGEMENT	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	1200 SQ. FT.	26012-1A, 26012-1B, 26012-1C		ND			NO		SAMPLED BY OHE (PROJECT #26012) IN 2020.		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-	PERIMETER RADIATOR UNITS									REMOVED IN AUGUST 2019		N/A
		LEVELLING COMPOUND	GREY, CEMENTITIOUS	FLOOR		26257-1A, 26257-1B, 26257-1C		ND			NO		SAMPLED BY OHE (PROJECT #26257) IN 2020.		N/A
		CERAMIC TILES	MORTAR	FLOOR		26257-2A, 26257-2B, 26257-2C		ND			NO		SAMPLED BY OHE (PROJECT #26257) IN 2020.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S304A	CAMPUS SAFETY	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	COLUMN & WALL		25875-4B & 25875-4D		ND			NO		SAMPLED BY OHE (Project #25875) IN 2020		N/A
		QUARRY TILES	GROUT	FLOOR		25951-1C, 26167-3A, 26167-3B		ND			NO		SAMPLED BY OHE (Project #25951 & 26167) IN 2020.		N/A
		QUARRY TILES	MORTAR	FLOOR		25951-2C, 26167-6A, 26167-6B		ND			NO		SAMPLED BY OHE (Project #25951 & 26167) IN 2020.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	450 SQ. FT.	25951-3A, 25951-3B, 25951-3C		ND			NO		SAMPLED BY OHE (Project #25951) IN 2020.		N/A
S304G	CAMPUS SAFETY	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25875-2A-C		ND			NO		SAMPLED BY OHE (PROJECT #25875) IN 2020.		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	ROOM S304G - PERIMETER RADIATOR UNIT	25 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S304H	CAMPUS SAFETY	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25875-4A-E		ND			NO		SAMPLED BY OHE (PROJECT #25875) IN 2020.		N/A
S304I	CAMPUS SAFETY	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25875-3A-C					NO		SAMPLED BY OHE (PROJECT #25875) IN 2020.		N/A
S304J	CAMPUS SAFETY	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		QUARRY TILES	GROUT	FLOOR		25951-1A, 25951-1B, 26167-1A, 26167-1B, 26167-2A, 26167-2B		ND			NO		SAMPLED BY OHE (PROJECT #25951 & 26167) IN 2020.		N/A
		QUARRY TILES	MORTAR	FLOOR		25951-2A, 25951-2B, 26167-4A, 26167-4B, 26167-5A, 26167-5B		ND			NO		SAMPLED BY OHE (PROJECT #25951 & 26167) IN 2020.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	BULKHEAD		25875-1A, 25875-1B, 25875-1C		ND			NO		SAMPLED BY OHE (Project #25875) IN 2020		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25875-2A, 25875-2C, 25875-4A		ND			NO		SAMPLED BY OHE (Project #25875) IN 2020		N/A
S304K	CORRIDOR (OUTSIDE CAMPUS SAFETY)	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		18660 S01A-C		ND			NO		SAMPLED BY MAPLE (PROJECT #18660) IN 2020.		N/A
S304L	CAMPUS SAFETY	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25875-3A-C		ND			NO		SAMPLED BY OHE (PROJECT #25875) IN 2020.		4
S304M	ELECTRICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S304N	CAMPUS SAFETY	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25875-4A-E					NO		SAMPLED BY OHE (PROJECT #25785) IN 2020.		4
S304P	ELEVATOR	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S304S	STAIRS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	450 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	NOT OBSERVED DURING 2021 REASSESSMENT		4
		1'x1' ACOUSTIC TILE	PINHOLES AND FISSURES	CEILING		26133-2A-C		ND			NO		SAMPLED BY OHE (PROJECT #26133) IN 2020. NO ACCESS ABOVE THE CEILING.		N/A
S304T	CAMPUS SAFETY	DRYWALL	DRYWALL JOINT COMPOUND	WALL		25875-4A-E		ND			NO		SAMPLED BY OHE (PROJECT #25875) IN 2020		N/A
S304V	KEYBOX / ELEVATOR 3 ACCESS	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		SUSPENDED CEILING TILES	1' X 1'	CEILING		26133-1A-C		ND			NO		SAMPLED BY OHE (PROJECT #26133) IN 2020.		N/A
S305E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S305K	CORRIDOR	SUSPENDED CEILING TILES	1' X 1'	CEILING		26133-2A-C		ND			NO		SAMPLED BY OHE (Project #26133) IN 2020.		N/A
		CAULKING	BROWN & OFF-WHITE	WINDOW - EXTERIOR		26261-1A-C, 26261-2A-C		ND			NO		SAMPLED BY OHE (Project #26197) IN 2020.		N/A
		CAULKING	BROWN	WINDOW - INTERIOR		26197-1A-C		ND			NO		SAMPLED BY OHE (Project #26197) IN 2020.		N/A
S305S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S306	WOMEN'S WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	WALL SPACE	8	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	NO ACCESS BEHIND WALL		4
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	250 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S307	JANITOR CLOSET	NO SUSPECT ACM OBSERVED									NO				N/A
	SHAFT	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	SHAFT	15 TO 20	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
S308	MEN'S WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	WALL SPACE	10 TO 15	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	250 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S309	LECTURE HALL	REFER TO 218											REFER TO THE RESPECTIVE AREA ON 2ND FLOOR		N/A
S309A	LECTURAL HALL - STORAGE	REFER TO 218A											REFER TO THE RESPECTIVE AREA ON 2ND FLOOR		N/A
S309S	STAIRCASE	REFER TO 218S											REFER TO THE RESPECTIVE AREA ON 2ND FLOOR		N/A
S310	SERVER ROOM & SHAFT	NO SUSPECT ACM OBSERVED									NO		LIMITED ACCESS TO SHAFT		N/A
S311	CLASSROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	PIPE TRENCHES	UNKNOWN						SUSPECT		ROOM WAS RENOVATED -2009 - ACM SUSPECTED TO BE PRESENT IN PIPE TRENCHES		4
		NEW DRYWALL	DRYWALL JOINT COMPOUND	WALLS							NO				N/A
		BLACK & YELLOW MASTIC	FLOOR MASTIC	FLOOR							NO		REMOVED IN JULY 2020 (MAPLE PROJECT #17971). REFER TO PROJECT DCM2019-05.		N/A
		BLACK MASTIC/TAR	ON SOUTH WALL	ABOVE CEILING TILES		17971 S04A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17971). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S312	CULINARIA	NO SUSPECT ACM OBSERVED									NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
S312A	CULINARIA	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2018 (MAPLE PROJECT #17273). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S312V	VESTIBULE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR TO ROOM S311		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. ROOM WAS REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
S313	CULINARIA	NO SUSPECT ACM OBSERVED									NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
S315K	CORRIDOR	SUSPENDE CEILING TILES	1' X 1'	CEILING - WALKWAY ABOVE S317 DOOR							NO		CEILING TILES ARE VISUALLY SIMILAR TO S305K.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING - ABOVE WOOD PANELS	UNKNOWN				UNKNOWN		YES	FRIABLE	NO ACCESS ABOVE WOOD PANEL CEILING. ACM PIPE FITTING INSULATION LIKELY PRESENT THROUGHOUT THE CORRIDOR.		4
S315S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S316	PSYCHOLOGY TEACHING LAB	VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR									REMOVED IN 2021 (GOLDER PROJECT 21497509)		N/A
		NEW VINYL SHEET FLOORING											MASTIC REMOVED IN 2021 (GOLDER PROJECT 21497509)		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S316A	COMPUTER LAB	VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR									REMOVED IN 2021 (GOLDER PROJECT 21497509)		N/A
		NEW VINYL SHEET FLOORING											MASTIC REMOVED IN 2021 (GOLDER PROJECT 21497509)		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR TO ROOM S316C		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S316B	COMPUTER LAB	VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR									REMOVED IN 2021 (GOLDER PROJECT 21497509)		N/A
		NEW VINYL SHEET FLOORING											MASTIC REMOVED IN 2021 (GOLDER PROJECT 21497509)		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR TO ROOM S316C		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S316C	LAB	BLACK MASTIC	FLOOR MASTIC	FLOOR UNDER MILLWORK				CHRYSTILE	GOOD	A	YES	NON-FRIABLE	REMOVED IN 2021 (GOLDER PROJECT 21497509) WITH THE EXCEPTION OF UNDER MILLWORK		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES	FITTINGS												4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	LAB COUNTERS	150 SQ. FT				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S317	LAB	DRYWALL (NEW - 2022)	DRYWALL JOINT COMPOUND	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBETOS		N/A
		ACOUSTIC TILES	CEILING TILES (NEW - 2022)	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBETOS		N/A
		VINYL FLOOR TILES	9X9 RED FLOOR TILE AND BLACK MASTIC	FLOOR									REMOVED IN 2021 (GOLDER PROJECT #21497509). REFER TO PROJECT DCM2020-24.		N/A
		TRANSITE ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS, BENCHTOPS, AND SINKS									REMOVED IN 2021 (GOLDER PROJECT #21497509). REFER TO PROJECT DCM2020-24.		N/A
		CAULKING AROUND DOOR FRAMES	TAN CAULKING	DOORS	2 DOORS								CAULKING REMOVED FROM 2 DOORS BETWEEN S317V / S317 AND S317 / 317C IN 2021 (GOLDER PROJECT #21497509). REFER TO PROJECT DCM2020-24.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM									REMOVED IN 2021 (GOLDER PROJECT #21497509). REFER TO PROJECT DCM2020-24.		N/A
S317C	LAB	REFER TO S317											ALL ACM REMOVED IN 2021 (GOLDER PROJECT #21497509). REFER TO S317 FOR PROJECT DETAILS.		N/A
S318A	EMBODIED SOCIAL COGNITION LAB	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER	10 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S318B	EMBODIED SOCIAL COGNITION LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S318C	EMBODIED SOCIAL COGNITION LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S318D	EMBODIED SOCIAL COGNITION LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S318E	EMBODIED SOCIAL COGNITION LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S318K	EMBODIED SOCIAL COGNITION LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S319	LECTURE HALL	REFER TO S233											REFER TO THE RESPECTIVE AREA ON 2ND FLOOR: S233		N/A
S319A	LECTURE HALL - BACK ROOM	REFER TO S233A											REFER TO THE RESPECTIVE AREA ON 2ND FLOOR: S233A		N/A
S319S	STAIRCASE	REFER TO S233S											REFER TO THE RESPECTIVE AREA ON 2ND FLOOR: S233S		N/A
S320	ACCESS HATCH	NO SUSPECT ACM OBSERVED									NO				N/A
	ELECTRICAL ROOM	ELECTRICAL WIRES AND CABLE SHEATHING	ELECTRICAL WIRES AND CABLE SHEATHING	GENERAL ROOM							NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S321	BIOLOGY TEACHING LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	TRENCHES	2				GOOD	C	YES	FRIABLE	MOST FITTINGS WERE REMOVED IN 2022 (GOLDER PROJECT #21507943). 1 PIPE FITTING REMAINS IN EACH TRENCH IN THIS ROOM.		4
		DRYWALL (NEW - 2022)	DRYWALL JOINT COMPOUND	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBETOS		N/A
		VINYL FLOOR TILES	9X9 RED FLOOR TILE AND BLACK MASTIC	FLOOR									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
		TRANSITE ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS, BENCHTOPS, AND SINKS									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
		CAULKING AROUND DOOR FRAMES	GREY CAULKING	DOORS									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
		MILLBOARD	MILLBOARD	WALL BETWEEN S321 / S322									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
S322	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	PIPE SHAFTS	UNKNOWN				GOOD	C	YES	FRIABLE	MOST FITTINGS WERE REMOVED IN 2022 (GOLDER PROJECT #21507943). ACM FITTINGS ARE STILL PRESENT IN PIPE SHAFTS ADJACENT TO S321 AND S323.		4
		DRYWALL (NEW - 2022)	DRYWALL JOINT COMPOUND	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		ACOUSTIC TILES	CEILING TILES (NEW - 2022)	CEILING							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	9X9 RED FLOOR TILE AND BLACK MASTIC	FLOOR									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
		TRANSITE ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS, BENCHTOPS, AND SINKS									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
		CAULKING AROUND DOOR FRAMES	GREY CAULKING	DOORS									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
		MILLBOARD	MILLBOARD	WALL BETWEEN S321 / S322									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
S322E	MECHANICAL SHAFT	LIMITED VIEW									SUSPECT		NO ACCESS TO SHAFT DUE TO CONTENTS BLOCKING ACCESS DOOR		4
S322V	VESTIBULE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S323	BIOLOGY TEACHING LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	TRENCHES	2				GOOD	C	YES	FRIABLE	MOST FITTINGS WERE REMOVED IN 2022 (GOLDER PROJECT #21507943). 1 PIPE FITTING REMAINS IN EACH TRENCH IN THIS ROOM.		4
		DRYWALL (NEW - 2022)	DRYWALL JOINT COMPOUND	WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
		VINYL FLOOR TILES	9X9 RED FLOOR TILE AND BLACK MASTIC	FLOOR									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
		TRANSITE ASBESTOS CEMENT	BLACK TRANSITE MATERIAL	FUME HOODS, BENCHTOPS AND SINKS									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
		CAULKING AROUND DOOR FRAMES	GREY CAULKING	DOORS									REMOVED IN 2022 (GOLDER PROJECT #21507943).		N/A
S325K	CORRIDOR	SUSPENDE CEILING TILES	1' X 1'	CEILING - WALKWAY ABOVE S327V DOOR		26133-2A-C		ND			NO		CEILING TILES ARE VISUALLY SIMILAR TO S305K.		N/A
		MORTAR	WHITE & GREY	CERAMIC TILES		MTR-01 (A-C)		ND			NO		SAMPLED BY GOLDER IN FEB 2022 (GOLDER PROJECT 21498224)		N/A
		GROUT		CERAMIC TILES		GRT-01(A-C)		ND			NO		SAMPLED BY GOLDER IN FEB 2022 (GOLDER PROJECT 21498224)		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING - ABOVE WOOD PANELS	UNKNOWN				UNKNOWN	C	YES	FRIABLE	NO ACCESS ABOVE WOOD PANEL CEILING. ACM PIPE FITTING INSULATION LIKELY PRESENT THROUGHOUT THE CORRIDOR.		4
S325S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S325V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S326	RESEARCH LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR	530 SQ. FT.	R-SA24	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	NEW VINYL SHEET FLOORING WAS OBSERVED. ASBESTOS-CONTAINING VINYL FLOOR TILE MASTIC IS LIKELY STILL PRESENT.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS AND IN PIPE TRENCHES													4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER	72 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM. REMOVED DURING 2012 RENOVATIONS.		4
S327	RESEARCH LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR	300 SQ. FT.	R-SA24	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	NEW VINYL SHEET FLOORING WAS OBSERVED. ASBESTOS-CONTAINING VINYL FLOOR TILE MASTIC IS LIKELY STILL PRESENT.		4
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS AND IN PIPE TRENCHES													4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER	108 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM. REMOVED DURING 2012 RENOVATIONS.		4
S327A	RESEARCH LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S327E	MECHANICAL SHAFT	NO SUSPECT ACM OBSERVED									NO		LIMITED VIEW		N/A
S327V	VESTIBULE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S328	RESEARCH LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR	1000 SQ. FT.	R-SA24	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	NEW VINYL SHEET FLOORING WAS OBSERVED. ASBESTOS-CONTAINING VINYL FLOOR TILE MASTIC IS LIKELY STILL PRESENT.		4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	FUME HOOD AND COUNTER	600 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS AND IN PIPE TRENCHES													N/A
		VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR	900 SQ. FT.	R-SA15 & R-SA(103-107)-06		ND			NO		NEW SHEET FLOORING OBSERVED		N/A
S328A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR	1000 SQ. FT.	R-SA24	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	BARE BASE RENOVATIONS IN PROGRESS DURING 2012 ACM CONDITION ASSESSMENT. NEW VINYL SHEET FLOORING WAS OBSERVED. ASBESTOS-CONTAINING VINYL FLOOR TILE MASTIC IS LIKELY STILL PRESENT.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		VINYL SHEET FLOORING	BROWN SPECKLED SHEET FLOORING	FLOOR	900 SQ. FT.	R-SA15 & R-SA(103-107)-06		ND			NO		NEW SHEET FLOORING OBSERVED		N/A
S330	LAB	BLACK AND YELLOW MASTIC	FLOOR MASTIC	FLOOR UNDER VSF	UNKNOWN	18826-S03A-C	1	CHRYSTILE	GOOD	B	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (PROJECT #18826). ACM MASTIC REMAINS UNDER SHEET FLOORING FOLLOWING 2010 AND 2021 RENOVATIONS.		4
		CAULKING AROUND DOOR FRAMES	GREY CAULKING	DOOR		18826-S03A-C	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (PROJECT #18826).		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS		18826-S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2020 (PROJECT #18826).		N/A
		PLASTER	LIGHT GREY, TEXTURED PLASTER	WALLS - ABOVE DOOR		18826-S02A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2020 (PROJECT #18826).		N/A
		CAULKING	TAN CAULKING	CEILING ON DUCTWORK		18826-S05A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2020 (PROJECT #18826).		N/A
S331	LAB	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER	108 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S331A	LAB	FLOORING MATERIAL	FLOOR MASTIC	FLOOR	UNKNOWN				GOOD	C	YES	NON-FRIABLE	ACM MASTIC IS PRESENT UNDER NON-ASBESTOS FLOORING MATERIAL		4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions


ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S331E	MECHANICAL SHAFT	NO SUSPECT ACM OBSERVED									NO		LIMITED VIEW		N/A
S331V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A
S332	LAB	BLACK AND YELLOW MASTIC	FLOOR MASTIC	FLOOR UNDER VSF	UNKNOWN				GOOD	B	PRESUMED	NON-FRIABLE	SAMPLED IN ADJACENT LAB S330 BY MAPLE IN 2020 (PROJECT #18826). ALTHOUGH SPACE WAS RENOVATED IN 2010, ACM MASTIC IS PRESUMED UNDER SHEET FLOORING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.	25622-022-39A-C	ND	ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S333A	FRUIT FLY STORAGE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S333S	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	35 SQ. FT.	01-E	ND	ND			NO		SAMPLE LOCATION. SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S333V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A
S334	THEATRE ENTRANCE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT.	R-SA1-E-07		ND			NO		AREA RECENTLY RENOVATED		N/A
S335	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	330 SQ. FT.	R-SA1-E-07		ND			NO		AREA RECENTLY RENOVATED		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	860 SQ. FT.	SA5(A-E)-08		ND			NO		AREA RECENTLY RENOVATED		N/A
S335E	ELEVATOR	VINYL FLOOR TILES	9x9 ORANGE FLOOR TILE	FLOOR	30 SQ. FT.	R-SA20	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN TILE ONLY. A DIFFERENT COLOUR VINYL FLOOR TILES WAS OBSERVED DURING THE 2021 REASSESSMENT.		4
S335K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S336	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S336S	STAIRCASE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S338	WOMEN'S WASHROOMS	DRYWALL	DRYWALL JOINT COMPOUND	WALL/CEILING	300 SQ. FT.	R-SA1-E-07		ND			NO		AREA RECENTLY RENOVATED		N/A
S338E	ELEVATOR ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S338F	STORAGE	NO SUSPECT ACM OBSERVED									NO				N/A
S339	SINGLE USER WASHROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL/CEILING	370 SQ. FT.	R-SA1-E-07		ND			NO		AREA RECENTLY RENOVATED		N/A
S340	MEN'S WASHROOMS	DRYWALL	DRYWALL JOINT COMPOUND	WALL/CEILING	370 SQ. FT.	R-SA1-E-07		ND			NO		AREA RECENTLY RENOVATED		N/A
S340K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL	370 SQ. FT.	R-SA101		ND			NO		AREA RECENTLY RENOVATED		N/A
S340V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A
S343V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A
S344K	VESTIBULE	VINYL SHEET FLOORING		NEW - 2009							NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND		280 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S344V	VESTIBULE	VINYL SHEET FLOORING		NEW - 2009							NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND		280 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S345	DRESSING ROOM	VINYL SHEET FLOORING		NEW - 2009							NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND		300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S345	MECHANICAL SHAFT	NO SUSPECT ACM OBSERVED									NO		LIMITED ACCESS TO SHAFT		N/A
S345A	MECHANICAL ROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		VINYL FLOOR TILES	12x12 DARK BEIGE FLOOR TILES	FLOOR	40 SQ. FT.	SA118-(A-C)-06		ND			NO				N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S345B	STORAGE	VINYL FLOOR TILES	12x12 DARK BEIGE FLOOR TILES	FLOOR	40 SQ. FT.	SA118-(A-C)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND		20 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S345C	STORAGE	VINYL FLOOR TILES	12x12 DARK BEIGE FLOOR TILES	FLOOR	40 SQ. FT.	SA118-(A-C)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	FLOOR	20 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S347	JANITOR CLOSET	NO SUSPECT ACM OBSERVED									NO				N/A
S401S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING	1	R-SA1	50-75	CHRYSTILE	POOR	C	YES	FRIABLE	PRESENT IN CEILING SPACE. THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S402	SINGLE USER WASHROOM	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	20 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED VIEW ABOVE CEILING. SUSPECT ACM PIPE FITTING INSULATION WITHIN CEILING SPACE AND WALL CAVITY.		4
S403	CONFERENCE ROOM	1'x1' ACOUSTIC TILE	UNKNOWN	CEILING		R-SA121-(A-E)-06		ND			NO		NO ACCESS ABOVE CEILING TILES AND WOOD PANELS		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING	1	17403 S01	50	CHRYSTILE	GOOD	C	YES	FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17403). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	900 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED VIEW ABOVE CEILING. SUSPECT ACM PIPE FITTING INSULATION WITHIN CEILING SPACE AND WALL CAVITY.		4
S404A	STORAGE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED VIEW ABOVE CEILING. SUSPECT ACM PIPE FITTING INSULATION WITHIN CEILING SPACE AND WALL CAVITY.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S404B	ELEVATOR	VINYL FLOOR TILES	2'X2' NEW TILE								NO				N/A
S404E	ELEVATOR	NO ACCESS									SUSPECT				4
S404K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED VIEW ABOVE CEILING. NO ACCESS ABOVE WOOD PANEL CEILING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S405	OFFICE	NO SUSPECT ACM OBSERVED									NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S405K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2018 (MAPLE PROJECT #17403). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S406	OFFICE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	NORTHEAST CORNER - WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S407	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED VIEW ABOVE CEILING. NO ACCESS ABOVE WOOD PANEL CEILING.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S407A	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED VIEW ABOVE CEILING. NO ACCESS ABOVE WOOD PANEL CEILING.		4
S407B	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED VIEW ABOVE CEILING. NO ACCESS ABOVE WOOD PANEL CEILING.		4
S407C	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	600 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. LIMITED VIEW ABOVE CEILING. NO ACCESS ABOVE WOOD PANEL CEILING.		4
S408	OFFICE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE INSIDE DOOR SEPARATING ROOMS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS ROOM 408A	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S408A	OFFICE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE INSIDE DOOR SEPARATING ROOMS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS ROOM 408A	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S409	OFFICE	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.5). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S409A	CONTROL ROOM	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.5). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S409B	PSYCHOLOGY LAB 1	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.5). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S409C	KITCHEN	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.5). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S409D	TOILET	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.5). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S409E	CONTROL ROOM	BRICK MORTAR	MORTAR	ADJACENT TO DOOR		16849 S01A-C	ND	ND			NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.5). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S409F	PSYCHOLOGY ROOM 2	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.5). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S409G	PSYCHOLOGY ROOM 3	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.5). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S410	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S410A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S410B	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S410C	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S410K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S410L	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S410M	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S410N	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S411	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S411A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	100 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S411B	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		CARPET									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S411C	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S412	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S412A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S413	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S413A	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	100 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S413B	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S414	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S414A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S414B	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S414C	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S414D	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S414E	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S414F	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S414K	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S415	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	100 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S415A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	75 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S416	FILE ROOM	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	75 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S416A	ELECTRICAL CLOSET	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S416B	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S417	ICE MACHINE ROOM	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		INSTALLED IN 2009 - MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S417K	CORRIDOR	VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	800 SQ. FT.	R-SA28	1-5	CHRYSTOTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN THE MASTIC ONLY - NO ACCESS ABOVE THE WOOD PANEL CEILING		4
S418	OFFICE	ELECTRICAL WIRES AND CABLE SHEATHING	ELECTRICAL WIRES AND CABLE SHEATHING	GENERAL ROOM							NO		ALL EQUIPMENT WAS LIVE- NO ACCESS- PRESUMED ACM PRESENT UNTIL PROVEN OTHERWISE		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	1000 SQ. FT.			ND			NO		DRYWALL CEILING INSTALLED IN 2007, NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
S418A	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	1000 SQ. FT.			ND			NO		DRYWALL CEILING INSTALLED IN 2007, NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
S418B	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	1000 SQ. FT.			ND			NO		DRYWALL CEILING INSTALLED IN 2007, NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
S418C	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	1000 SQ. FT.			ND			NO		DRYWALL CEILING INSTALLED IN 2007, NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A
S418D	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	1000 SQ. FT.			ND			NO		DRYWALL CEILING INSTALLED IN 2007, NOT SUSPECTED TO CONTAIN ASBESTOS.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S418K	CORRIDOR	DRYWALL		WALLS	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S419	ELECTRICAL	NO SUSPECT ACM OBSERVED									NO				N/A
S419E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S419K	CORRIDOR	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS ACROSS FROM ROOM S418	35 SQ. FT.				GOOD	C	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S419S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO		ACM BY FERRO CANADA INC. ON NOVEMBER 22, 2010		N/A
S420	WOMEN'S WASHROOM	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16714). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S420A	MAIL + PHOTOCOPY ROOM	NEW LAY-IN CEILING TILES									NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE		R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	160 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S420B	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	160 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S420K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	THROUGHOUT CEILING	25 TO 35	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED VIEW ABOVE CEILING.		4
		NEW LAY-IN CEILING TILES		CEILING - NEAR WASHROOMS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	2000 SQ. FT.	SA28 & SA109-(A-E)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
S421	MEN'S WASHROOM & JANITOR CLOSET	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	6 TO 10	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	THREE ARE PRESENT WITHIN THE CLEANERS CLOSET		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S421A	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
S421B	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
S421C	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		GREY FIBROUS MATERIAL	GREY FIBROUS MATERIAL	METAL DUCT, T-BAR AND T-BAR SUPPORT		17950 S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17950). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S421D	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
S421E	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
S421F	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
S421G	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
S421H	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
S421K	BIOLOGICAL SCIENCES	NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S422	LAB	ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES									SUSPECT				N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		BLACK COUNTERTOPS	BLACK COUNTERTOPS	GENERAL ROOM		18403 S01A-C	ND	ND					SAMPLED BY MAPLE IN 2019 (PROJECT #18403).		N/A
S422A	LAB	VINYL SHEET FLOORING		NEW - 2009							NO				N/A
S422E	MECHANICAL SHAFT (#5)	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	100	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE	REPAIRED IN 2014		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	11	R-SA1	50-75	CHRYSTILE	GOOD	A/C	YES	FRIABLE	SELECT FITTINGS REMOVED IN 2018 (MAPLE PROJECT #17272). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	AT RIGHT SIDE OF SHAFT IN THE CORNER ADJACENT TO THE WALL ON THE DOOR SIDE, APPROXIMATELY 10 FEET UP	1	R-SA1	50-75	CHRYSTILE	FAIR	C	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT ON FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	IN THE BACK LEFT CORNER AT THE METAL GRATE (FLOOR LEVEL) AT LADDER. DEBRIS ALSO PRESENT IN THE WALL CAVITY	1	R-SA1	50-75	CHRYSTILE	FAIR	C	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT ON FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S422V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.2). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S423	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.2). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S425K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	>100	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S425S	STAIRWELL	TRANSITE™ ASBESTOS-CEMENT									NO		ITEM WAS REMOVED AND REPLACED BY FERRO CANADA INC. IN NOVEMBER 22, 2010		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S426	LAB	VINYL SHEET FLOORING		NEW - 2009							NO				N/A
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES									SUSPECT		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
S426A	LAB	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S426E	MECHANICAL SHAFT	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	56	R-SA1	50-75	CHRYSTOTILE	GOOD	A/C	YES	FRIABLE	SELECT FITTINGS REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.1) AND 2018 (MAPLE PROJECT #17272). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S426V	VESTIBULE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S427	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.1). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S427A	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S427B	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S427C	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S427D	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S427E	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S427F	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S427G	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S427H	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S427J	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16687, SIF 9.1). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S427K	PSYCHOLOGY OFFICES	NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S428	LAB	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
S428A	LAB	NEW LAY-IN CEILING TILES	PAINTED TEXTURE COAT OVER PLASTER								NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S428B	LAB	NEW LAY-IN CEILING TILES	PAINTED TEXTURE COAT OVER PLASTER								NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S428C	LAB	NEW LAY-IN CEILING TILES	PAINTED TEXTURE COAT OVER PLASTER								NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S428E	MECHANICAL SHAFT (#5)	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	40	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED ACCESS TO THE SHAFT. 6 FITTINGS REMOVED IN 2019 (MAPLE PROJECT #18025). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S428V	VESTIBULE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
S429	LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S429A	LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S429B	LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
S431K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	THROUGHOUT CEILING	25	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	LIMITED VIEW ABOVE CEILING.		4
		VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	2000 SQ. FT.	SA28 & SA109-(A-E)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
S431S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S432	LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
S432A	LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S432B	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01A-C	ND	ND					SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		WALL BOARD	WALL BOARD	WALL - BEHIND DRYWALL		WB01A-C	ND	ND					SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL ADHESIVE	YELLOW ADHESIVE	WALL - BETWEEN DRYWALL AND WALL BOARD		ADH01A-C	ND	ND					SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
S432C	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC02A-C	ND	ND					SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		WALL BOARD	WALL BOARD	WALL - BEHIND DRYWALL		WB01A-C	ND	ND					SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		DRYWALL ADHESIVE	YELLOW ADHESIVE	WALL - BETWEEN DRYWALL AND WALL BOARD		ADH01A-C	ND	ND					SAMPLED BY GOLDER IN 2022 (PROJECT #22532220).		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
S432E	MECHANICAL SHAFT	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	30	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE	LIMITED ACCESS TO THE SHAFT. SOME ASBESTOS-INSULATED PIPE FITTINGS HAVE BEEN REMOVED AND REPLACED WITH FIBERGLASS INSULATION.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM							NO		REMOVED IN 2021 (MAPLE PROJECT 19345)		N/A
S432V	VESTIBULE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	TEE OUTSIDE THE SHAFT							NO		REMOVED IN 2021 (MAPLE PROJECT 19345)		N/A
S433	LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW DRYWALL									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL IS NOT SUSPECTED TO CONTAIN ASBESTOS. AREA WAS RECENTLY RENOVATED.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S435	LAB	FLOOR TILES									NO		THE ASBESTOS-CONTAINING VINYL FLOOR TILES WERE REMOVED AS PART OF RENOVATIONS IN AUGUST 2011.		N/A
		CAULKING	GREY CAULKING	DOOR		S02 (A-C)	2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18754). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		DRYWALL	DRYWALL JOINT COMPOUND	BULKHEAD		S03 (A-C)	ND	ND			NO		SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18754). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PLASTER	PLASTER	WALL - ABOVE DOOR AND ENTRANCE		S04 (A-C)	ND	ND			NO		SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18754). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		FIRESTOP	GREY CAULKING	TOP OF WALL		S05 (A-C)	0.5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18754). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
		FLOOR MASTIC	GREY MASTIC	FLOOR UNDER VSF		S01 (A-C)	ND	ND			NO		SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18754). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		FLOOR MASTIC	BROWN AND YELLOW MASTIC	FLOOR UNDER VSF		S06 (A-C)	0.5	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	PARTIALLY REMOVED IN 2020 (OHE PROJECT #25955). SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18754).		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS									SUSPECT	FRIABLE	ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES		4
S435E	MECHANICAL SHAFT	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	DOMESTIC LINES	GENERAL ROOM	50 TO 60	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
S435V	VESTIBULE	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
S436	LAB	NO SUSPECT ACM OBSERVED									NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES									SUSPECT	FRIABLE			4
S436C	LAB	NO SUSPECT ACM OBSERVED									NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES									SUSPECT	FRIABLE			4
S436K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S436V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S437A	STORAGE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	12 SQ. FT.	01-D	ND	ND			NO		SAMPLE LOCATION. SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S437S	STAIRWELL	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	WALL - ABOVE ELECTRICAL CONDUIT	10 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	B	YES	NON-FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT. AREA WAS RECENTLY RENOVATED.		N/A
S438K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S439	MECHANICAL/STORAGE	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		NO SUSPECT ACM OBSERVED									NO				N/A
S440S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S442	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.	25622-022-40A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S442A	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S444	CONTROL BOOTH	SEE S260B													4
S444K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND		500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S500A	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S500B	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S500K	CORRIDOR	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	250 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO		NO ACCESS ABOVE THE WOOD PANEL CEILING		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	10 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		DRYWALL	DRYWALL JOINT COMPOUND	FLOOR AND WALL		25622-022-10A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
S502	WASHROOM	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	1500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S503	COMPUTER LAB	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	1000 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RENOVATIONS IN 2012. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	18041 S01A		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18041). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S503A	CLEANERS	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2018 (MAPLE PROJECT #17367). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S503B	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	162 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ASBESTOS-CONTAINING VFTs WERE REPORTEDLY REMOVED IN 2010. NEW VINYL SHEET FLOORING WAS OVERLAIN ON TOP OF THE REMAINING ASBESTOS-CONTAINING VINYL FLOOR TILE MASTIC.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	20 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	45 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S503C	OFFICE	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	20 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	45 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. NO ACCESS ABOVE CEILING TILES AND WOOD PANEL		4
S503G	CLEANERS	SMOOTH PLASTER	SMOOTH PLASTER	CEILING		16617-S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (PROJECT #16617). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S503K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	18041 S01B		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18041). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S504A	LAB	VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	188 SQ. FT.	R-SA28 & R-SA109-(A-E)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS							NO		REMOVED IN 2019 (MAPLE PROJECT #17666). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	340 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S504B	LAB	VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	188 SQ. FT.	R-SA28 & R-SA109-(A-E)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	140 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	340 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S504C	OFFICE	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2013.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	100 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S504D	OFFICE	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2013.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS							NO		REMOVED IN 2019 (MAPLE PROJECT #17666). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S504E	OFFICE	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2013.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	100 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	500 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S504K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	18041 S01C,D		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18041). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S505A	LAB STORAGE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS							NO		REMOVED IN 2019 (MAPLE PROJECT #17666). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S505B	LAB	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	80 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		1'x1' ACOUSTIC TILE	UNKNOWN	CEILING		R-SA121-(A-E)-06		ND			NO		NO ACCESS ABOVE CEILING TILES AND WOOD PANEL		N/A
S505C	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	100 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	REMOVED IN 2019 ACCORDING TO UTSC NOTICE OF PROJECT. ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	432 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	NOT OBSERVED DURING 2021 REASSESSMENT.		4
S505D	PHYSICS LAB	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS							NO		REMOVED IN 2019 (MAPLE PROJECT #17666). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	1200 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
S505E	PHYSICS LAB	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	1200 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		1'x1' ACOUSTIC TILE	UNKNOWN	CEILING	UNKNOWN	R-SA121-(A-E)-06		ND			NO		NO ACCESS ABOVE CEILING TILES AND WOOD PANEL		N/A
S505F	PHYSICS LAB	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	1200 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS							NO		REMOVED IN 2019 (MAPLE PROJECT #17666). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		1'x1' ACOUSTIC TILE	UNKNOWN	CEILING	UNKNOWN	R-SA121-(A-E)-06		ND			NO		NO ACCESS ABOVE CEILING TILES AND WOOD PANEL		N/A
S506	CLASSROOM, OFFICE & VESTIBULE	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	1200 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	45 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S506B	PHYSICS LAB	VINYL SHEET FLOORING	BEIGE MOSAIC SHEET FLOORING	FLOOR	340 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		VINYL SHEET FLOORING	MASTIC	FLOOR			3	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM PRESENT IN MASTIC ONLY		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	520 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		1'x1' ACOUSTIC TILE	UNKNOWN	CEILING	90 SQ. FT.	R-SA53		ND			NO		STAINING WAS OBSERVED ON CEILING TILES (NO ACCESS ABOVE) ADDITIONAL SAMPLING IS RECOMMENDED		N/A
S506C	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S506D	OFFICE	VINYL SHEET FLOORING	BEIGE MOSAIC SHEET FLOORING	FLOOR	340 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		VINYL FLOOR TILES	BLACK MASTIC	FLOOR	1200 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	520 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		1'x1' ACOUSTIC TILE	UNKNOWN	CEILING	90 SQ. FT.	R-SA53		ND			NO		STAINING WAS OBSERVED ON CEILING TILES (NO ACCESS ABOVE) ADDITIONAL SAMPLING IS RECOMMENDED		N/A
		CAULKING	RED CAULKING	ON DUCTWORK		S10A-C	1	CHRYSTILE	GOOD	C	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18565). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		MASTIC	MASTIC	BELOW VINYL SHEET FLOORING		S08A-C	2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18565). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S506E	OFFICE	VINYL SHEET FLOORING	BEIGE MOSAIC SHEET FLOORING	FLOOR	340 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		VINYL FLOOR TILES	BLACK MASTIC	FLOOR	1200 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	520 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		1'x1' ACOUSTIC TILE	UNKNOWN	CEILING	90 SQ. FT.	R-SA53		ND			NO		STAINING WAS OBSERVED ON CEILING TILES (NO ACCESS ABOVE) ADDITIONAL SAMPLING IS RECOMMENDED		N/A
S506F	SEMINAR ROOM	VINYL FLOOR TILES	BLACK MASTIC	FLOOR	1200 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		1'x1' ACOUSTIC TILE	UNKNOWN	CEILING	72 SQ. FT.	R-SA53		ND			NO		NO ACCESS ABOVE CEILING TILES - ADDITIONAL SAMPLING IS RECOMMENDED		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-11A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions


ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S506G	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	168 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		VINYL FLOOR TILES	BLACK MASTIC	FLOOR	1200 SQ. FT.	R-SA32	5	CHRYOTILE	GOOD	A	YES	NON-FRIABLE	RESIDUAL ACM MASTIC MAY BE PRESENT BELOW NEW NON-ASBESTOS FLOORING. FLOOR RENOVATED IN 2010.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	100 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		NEW DRYWALL		RENOVATED WALL	65 SQ. FT.						NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S506H	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		MASTIC	MASTIC	BELOW VINYL SHEET FLOORING			2	CHRYOTILE	GOOD				SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18565). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	100 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		NEW VINYL SHEET FLOORING		FLOOR	200 SQ. FT.	R-SA32	5	CHRYOTILE	GOOD	A	NO	NON-FRIABLE	ASBESTOS-CONTAINING VFTs WERE REMOVED IN 2010. NEW VINYL SHEET FLOORING WAS OVERLAIN ON TOP OF THE REMAINING ASBESTOS-CONTAINING VINYL FLOOR TILE MASTIC.		N/A
S506I	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-12A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S506K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL	347 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.NO ACCESS ABOVE WOOD PANEL CEILING.		4
		NEW VINYL SHEET FLOORING		FLOOR	1500 SQ. FT.	R-SA43A	5	CHRYOTILE	GOOD	A	YES	NON-FRIABLE	ASBESTOS-CONTAINING VFTs WERE REMOVED IN 2010. NEW VINYL SHEET FLOORING WAS OVERLAIN ON TOP OF THE REMAINING ASBESTOS-CONTAINING VINYL FLOOR TILE MASTIC.		4
S506L	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL		18041 S01E		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18041). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S506S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S507A	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	200 SQ. FT.	R-SA43A	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RENOVATIONS IN JULY 2013. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING. ASBESTOS-CONTAINING DRYWALL WALL SECTIONS MAY ALSO BE REMAINING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-13A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
S507B	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	200 SQ. FT.	R-SA43A	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RENOVATIONS IN JULY 2013. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING. ASBESTOS-CONTAINING DRYWALL WALL SECTIONS MAY ALSO BE REMAINING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	208 SQ. FT.	R-SA1-F-07	0.5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	<1 SQ. FT.	R-SA1-F-07	0.5	CHRYSTILE	FAIR	A	YES	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	150 SQ. FT.	R-SA43A	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED WITHIN TILE AND MASTIC		2

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S507C	SERVER ROOM	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	10 SQ. FT.	R-SA43A	5	CHRYSTILE	POOR	A	YES	NON-FRIABLE	ACM DETECTED WITHIN TILE AND MASTIC. THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS DRYWALL	FITTINGS	GENERAL ROOM	1	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
			DRYWALL JOINT COMPOUND	WALL	120 SQ. FT.	R-SA1-F-07	0.5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
S508A	CONFERENCE ROOM, UPPER LEVEL OF S403	1'x1' ACOUSTIC TILE	UNKNOWN	CEILING	150 SQ. FT.	R-SA121-(A-E)-06	ND	ND			NO		NO ACCESS ABOVE CEILING TILES AND WOOD PANELLING		N/A
S508K	CORRIDOR	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	500 SQ. FT.	R-SA43A	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RENOVATIONS IN JULY 2013. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING. ASBESTOS-CONTAINING DRYWALL WALL SECTIONS MAY ALSO BE REMAINING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-14A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
S509	ELECTRICAL ROOM	NO SUSPECT ACM OBSERVED									NO				N/A
S509K	CORRIDOR	VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	144 SQ. FT.	SA28 & SA109-(A-E)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		GREY FIBROUS MATERIAL	FIBROUS MATERIAL	AT ELEVATOR IN LIGHT FIXTURE		16961 S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16961). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-15A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
S509E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S510S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S511	OFFICE	VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	165 SQ. FT.	R-SA28 & R-SA109-(A-E)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		2'x4' ACOUSTIC TILES	RANDOM PINHOLES	CEILING	90 SQ. FT.	R-SA35 & R-SA122-(A-F)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS							NO		REMOVED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	110 SQ. FT.	R-SA1-F-07	0.5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	<1 SQ. FT.	R-SA1-F-07	0.5	CHRYSTILE	FAIR	A	YES	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S511A	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	70 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	TILES PREVIOUSLY REMOVED. ASSUME MASTIC IS ASBESTOS - CONTAINING AND STILL PRESENT BENEATH THE VINYL SHEET FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		ACOUSTIC TILES	UNKNOWN	CEILING	70 SQ. FT.	R-SA28 & R-SA109-(A-D)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	90 SQ. FT.	SA1-F-07	0.5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
S512	LAB	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	98 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RENOVATIONS IN APRIL 2012. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING.		4
		ACOUSTIC TILES	UNKNOWN	CEILING	98 SQ. FT.	R-SA28 & R-SA109-(A-D)-06		ND			NO				N/A
S513	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	0 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	TILES PREVIOUSLY REMOVED. ASSUME MASTIC IS ASBESTOS - CONTAINING AND STILL PRESENT BENEATH THE VINYL SHEET FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		ACOUSTIC TILES	UNKNOWN	CEILING	228 SQ. FT.	R-SA28 & R-SA109-(A-D)-06		ND			NO				N/A
S513A	OFFICE	2'x4' ACOUSTIC TILES	PINHOLES	CEILING	200 SQ. FT.	R-SA56		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	75 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
S514	OFFICE	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	36 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	36 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S515	OFFICE	2'x4' ACOUSTIC TILES	RANDOM PINHOLES	CEILING	228 SQ. FT.	R-SA35 & R-SA122-(A-F)-06		ND			NO				N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S515A	OFFICE	VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	150 SQ. FT.	R-SA28 & R-SA109-(A-D)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		TRANSITE™ ASBESTOS-CEMENT	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	COUNTERS									REMOVED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS									REMOVED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S516	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	160 SQ. FT.	R-SA43A	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S517	OFFICE	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	200 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	300 SQ. FT.	R-SA43A		CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	TILES PREVIOUSLY REMOVED. ACM DETECTED IN MASTIC ONLY. ASBESTOS-CONTAINING MASTIC IS LIKELY STILL PRESENT BENEATH THE SHEET FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S517A	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	150 SQ. FT.	R-SA43A		CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	TILES PREVIOUSLY REMOVED. ACM DETECTED IN MASTIC ONLY. ASBESTOS-CONTAINING MASTIC IS LIKELY STILL PRESENT BENEATH THE SHEET FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS									REMOVED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	IN RADIATOR BOX									REMOVED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S518	DARKROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	UNDER SINK	4	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE	REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S519S	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S519K	CORRIDOR	2'x4' ACOUSTIC TILES	RANDOM PINHOLES	CEILING	2,500 SQ. FT.	R-SA35 & R-SA122-(A-F)-06		ND			NO				N/A
S520A	PRINTER ROOM	2'x4' ACOUSTIC TILES	RANDOM PINHOLES	CEILING		R-SA35 & R-SA122-(A-F)-06		ND					CEILING CONSISTS OF WOOD PANELS AND CEILING TILES. NO ACCESS ABOVE WOOD PANEL CEILING.		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	38 SQ. FT.	R-SA34A	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	TILES PREVIOUSLY REMOVED. ASSUME MASTIC IS ASBESTOS - CONTAINING AND STILL PRESENT BENEATH THE VINYL SHEET FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	72 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S520B	MAIL ROOM	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	38 SQ. FT.	SA43A	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	TILES PREVIOUSLY REMOVED. ASSUME MASTIC IS ASBESTOS - CONTAINING AND STILL PRESENT BENEATH THE VINYL SHEET FLOORING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING	150 SQ. FT.	SA1-G-07	0.25	CHRYSTILE	GOOD	A	SUSPECT	NON-FRIABLE	NO ACCESS ABOVE CEILING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		WOOD PANELS	WOOD	CEILING	27 SQ. FT.						NO		CEILING CONSISTS OF WOOD PANELS AND DRYWALL. NO ACCESS ABOVE CEILING.		N/A
S521	OFFICE	2'x4' ACOUSTIC TILES	RANDOM PINHOLES	CEILING	244 SQ. FT.	R-SA35 & R-SA122-(A-F)-06		ND			NO		NO ACCESS ABOVE THE WOOD PANEL CEILING		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S521A	OFFICE	VINYL SHEET FLOORING	BEIGE SHEET FLOORING	FLOOR	140 SQ. FT.	R-SA110-D-02	2	CHRYSTILE	GOOD	A	YES	FRIABLE	VINYL SHEET FLOORING WAS REMOVED. ACM DETECTED IN MASTIC ONLY.		4
S521B	OFFICE	VINYL SHEET FLOORING	BEIGE SHEET FLOORING	FLOOR	140 SQ. FT.	R-SA110-D-02	2	CHRYSTILE	GOOD	A	YES	FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO		MECHANICAL PIPES UNINSULATED ABOVE CEILING - ADDITIONAL SAMPLING IS RECOMMENDED		N/A
S521C	OFFICE	VINYL SHEET FLOORING	BEIGE SHEET FLOORING	FLOOR	140 SQ. FT.	R-SA110-D-02	2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	200 SQ. FT.	R-SA43A	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED. ACM DETECTED IN MASTIC ONLY.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS	50 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S521D	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	80 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED. ACM DETECTED IN MASTIC ONLY.		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	16 SQ. FT.	SA35 & R-SA122-(A-F)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	25 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		2'x4' ACOUSTIC TILES	RANDOM PINHOLES	CEILING	40 SQ. FT.	R-SA35 & R-SA122-(A-F)-06		ND			NO				N/A
S521K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S522	WOMEN'S WASHROOM	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	80 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	LIMITED ACCESS ABOVE THE DRYWALL CEILING		4
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	2 SQ. FT.	R-SA32	5	CHRYSTILE	POOR	A	YES	NON-FRIABLE	THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES AND MASTIC SHOULD BE REMOVED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S522A	WOMEN'S WASHROOM	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	80 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	NOT OBSERVED DURING 2021 REASSESSMENT.		4
S523A	CLEANERS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE			4
S523B	MEN'S WASHROOM	NO SUSPECT ACM OBSERVED									NO		NO ACCESS ABOVE SOLID CEILING		N/A
S523V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A
S524	INFANT FEEDING ROOM	CAULKING	DOOR CAULKING	DOOR BETWEEN SW524 and SW254V									REMOVED FEB 2021 (GOLDER PROJECT 21445408)		N/A
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING - VESTIBULE	64 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S524A	STUDENT LOUNGE	NO SUSPECT ACM OBSERVED									NO				N/A
S524V	VESTIBULE	NO SUSPECT ACM OBSERVED									NO				N/A
		CAULKING	RED-BROWN CAULKING	CEILING SPACE - ON MECHANICAL EQUIPMENT									REMOVED IN 2021 (GOLDER PROJECT #21445408). REFER TO PROJECT DCM2019-23.		N/A
		MASTIC	MASTIC	BELOW VINYL SHEET FLOORING		CHRYSTILE	3	CHRYSTILE	GOOD		YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18568). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S525	OFFICE	NEW VINYL SHEET FLOORING	NEW - 2009								NO				N/A
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	244 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S525A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50SQ.FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S526	OFFICE	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	244 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S526A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50SQ.FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S527	LAB	VINYL SHEET FLOORING	GREY SPECKLED SHEET FLOORING	FLOOR	672 SQ. FT.	R-SA36		ND			NO				N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	FUME HOOD	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM. INCLUDES SHELVING UNITS BENEATH THE FUME HOODS.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S527A	CIRCUITS LAB	VINYL SHEET FLOORING	GREY SPECKLED SHEET FLOORING	FLOOR	672 SQ. FT.	R-SA36		ND			NO				N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S528	LAB	NEW DRYWALL	RANDOM PIN HOLES AND FISSURE	CEILING							NO		INSTALLED IN 2009		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S528V	VESTIBULE	PLASTER	ABOVE DOOR	ABOVE DOOR	16 SQ. FT.	SA128-(A-B)-06		ND			NO				N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	56 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		VINYL SHEET FLOORING	BEIGE SHEET FLOORING	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
S529	LAB	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	FUME HOOD	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S531	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	264 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RECENT RENOVATIONS. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50SQ.FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S531A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S532	OFFICE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	244 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S532A	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50SQ.FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S533	OFFICE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	244 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO		TRANSITE FUME HOOD AND PC FITTINGS REMOVED IN 2019 (MAPLE PROJECT #17990). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	25 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	VINYL SHEET FLOORING WAS OBSERVED DURING THE 2021 REASSESSMENT. ASBESTOS-CONTAINING FLOOR TILES MAY BE PRESENT BENEATH THE SHEET FLOORING.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.


Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S533A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50SQ.FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S534	OFFICE	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16763). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S534A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING. ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S535	OFFICE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	244 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S535A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING. ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S536	LAB	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER									ALL ACM REMOVED MAY 2022 (MAPLE PROJECT 20252).		N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	FUME HOOD									ALL ACM REMOVED MAY 2022 (MAPLE PROJECT 20252).		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS										ALL ACM REMOVED MAY 2022 (MAPLE PROJECT 20252).		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS									ALL ACM REMOVED MAY 2022 (MAPLE PROJECT 20252).		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR - LOCATED BENEATH VINYL SHEET FLOORING - NORTHEAST CORNER OF ROOM									ALL ACM REMOVED MAY 2022 (MAPLE PROJECT 20252).		N/A
		VINYL SHEET FLOORING	GREEN SPECKLE SHEET FLOORING (COATING)	FLOOR									ALL ACM REMOVED MAY 2022 (MAPLE PROJECT 20252).		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR									ALL ACM REMOVED MAY 2022 (MAPLE PROJECT 20252).		N/A
S536A / S536B	LAB	REFER TO S536											REFER TO S536 FOR PROJECT DETAILS.		N/A
S537	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED MAY 2022 (MAPLE PROJECT 20252).		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR - LOCATED BENEATH VINYL SHEET FLOORING - NORTHEAST CORNER OF ROOM									DURING ABATEMENT, FLOOR TILES AND MASTIC WERE FOUND UNDERNEATH METAL FLOORING AND SUBSEQUENTLY ABATED UNDER MAPLE PROJECT 20252.		N/A
S537V	VESTIBULE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	48 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		2'x4' ACOUSTIC TILES	RANDOM PINHOLES	CEILING	48 SQ. FT.	R-SA35 & R-SA122-(A-F)-06		ND			NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S538	LAB	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	600 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RECENT RENOVATIONS IN 2010. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING.		4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER	150 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES									SUSPECT				4
S538A	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	100 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S538B	OFFICE	NO SUSPECT ACM OBSERVED									NO		NO ACCESS ABOVE WOOD PANEL CEILING		N/A
S539	WALK-IN FRIDGE/AUTOCLAVE	NEW LAY-IN CEILING TILES									NO				N/A
S539K	CORRIDOR	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE AT STAIRWELL S539S	8	R-SA42	15	CHRYSTILE	GOOD	A	YES	FRIABLE	AT STAIRWELL S539S. REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S539S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	8	R-SA42	15	CHRYSTILE	POOR	A	YES	FRIABLE	THE DAMAGED (MOULD IMPACTED) ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S540	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE										REMOVED IN 2021 (OHE PROJECT 26355)		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S540A	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE										REMOVED IN 2021 (OHE PROJECT 26355)		N/A
		VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR		R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING. ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S541	OFFICE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	120 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING. ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE								NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	25 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S541A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
		NEW DRYWALL	DRYWALL JOINT COMPOUND	WALL	25 SQ. FT.						NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
		2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	64 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
S541B	OFFICE	VINYL FLOOR TILES									NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	50 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING. ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	120 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO		ROOMS RECENTLY RENOVATED- ALL ACM REMOVED		N/A
S542	OFFICE/LAB	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S542A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT		PERIMETER RADIATOR UNITS	60 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	SUSPECT ACM		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S543	LAB	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	FUME HOOD									REMOVED IN MAY 2022 (MAPLE PROJECT 20252)		N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER									NOT OBSERVED DURING THE 2022 REASSESSMENT		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR									REMOVED IN MAY 2022 (MAPLE PROJECT 20252)		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS										REMOVED IN MAY 2022 (MAPLE PROJECT 20252)		N/A
		MASTIC		FLOOR									REMOVED IN MAY 2022 (MAPLE PROJECT 20252)		N/A
		CAULKING AROUND DOOR FRAMES	BEIGE CAULKING	DOORS	2 DOORS	CLK-01A-C	3	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY GOLDER IN 2021 (PROJECT #21498224).		4
S543A	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS									REMOVED IN MAY 2022 (MAPLE PROJECT 20252).		4
		VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
S544	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS								NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE								NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL								NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S544A	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS								NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE								NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S544B	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS								NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE								NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED BACK TO		N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL								NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED BACK TO BARE-BASE.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S545	WALK-IN FRIDGE	FLEX CONNECTOR ON DUCT	ACM WOVEN MATERIAL	DUCT CONNECTOR	2 SQ. FT				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
S545V	VESTIBULE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S546	LAB	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER	144 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S548	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	NA	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		1'x1' ACOUSTIC TILE	SMALL PINHOLES	CEILING	220 SQ. FT.	R-SA51		ND			NO				N/A
S548A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S549	OFFICE	TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	FUME HOOD							NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED.		N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER							NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED.		N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR							NO		PREVIOUSLY REMOVED. ROOM REPORTEDLY RENOVATED.		N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	244 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S549A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING		4
S550	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S550A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S551	OFFICE	1'x1' ACOUSTIC TILE	SMALL PINHOLES	CEILING	16 SQ. FT.	R-SA51		ND			NO				N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	204 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		2'x4' ACOUSTIC TILES	RANDOM PINHOLES	CEILING	24 SQ. FT.	R-SA35 & R-SA122-(A-F)-06		ND			NO				N/A
S551A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
S552	OFFICE	NEW LAY-IN CEILING TILES									NO		AREA RECENTLY RENOVATED - 2009		N/A
		VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
S552A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S553	LAB	VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	936 SQ. FT.	R-SA28 & R-SA109-(A-E)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	COUNTER	100 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	PRESUMED ACM		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		CAULKING	DOOR CAULKING	DOOR CAULKING			1	CHRYSTILE	GOOD		YES		SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18566). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		BLACK MASTIC	FLOOR MASTIC	FLOOR UNDER VSF		18566 S04A-C	1	CHRYSTILE	GOOD	B	YES		SAMPLED BY MAPLE IN 2020 (PROJECT #18566). DURING 2020 LAB RENOVATION, FLOOR MASTIC WAS REMOVED IN S553A AND S553B SUBROOMS ONLY.		4
		ALL ACCESSIBLE FITTINGS AND ELBOW HAVE BEEN REMOVED BUT MAY STILL BE PRESENT BEHIND COUNTERS UNDER SINKS AND IN PIPE TRENCHES									SUSPECT				N/A
S553A	LAB	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		MASTIC	BLACK MASTIC	FLOOR BELOW VINYL SHEET FLOORING									REMOVED IN MAY 2020 ACCORDING TO UTSC NOTICE OF PROJECT. REFER TO PROJECT DCM2019-27.		N/A
S553B	LAB	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		MASTIC	BLACK MASTIC	FLOOR BELOW VINYL SHEET FLOORING									REMOVED IN MAY 2020 ACCORDING TO UTSC NOTICE OF PROJECT. REFER TO PROJECT DCM2019-27.		N/A
S554	WALK-IN FRIDGE	NO SUSPECT ACM OBSERVED									NO				N/A
S554V	VESTIBULE	VINYL SHEET FLOORING	ORANGE/PINK SPECKLED SHEET FLOORING	FLOOR	96 SQ. FT.	R-SA28 & R-SA109-(A-E)-06	1-5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	96 SQ. FT.	R-SA11, & R-SA120-(A-F)-06 R-SA51		ND			NO				N/A
S555	PSYCHOLOGY RESEARCH LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.	25622-022-16A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
		FLOOR MASTIC	MASTIC	UNDER FLOORING					GOOD	C	SUSPECT	NON-FRIABLE	ASBESTOS-CONTAINING MASTIC IS PRESUMED TO BE PRESENT UNDER THE FLOORING		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)		ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S555A	LAB SUPPORT	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-01A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21466439)		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)		ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		CAULKING	WHITE	AROUND ELECTRICAL BOXES		CLK-01A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21466439)		N/A
		BLACK MASTIC	FLOOR MASTIC	FLOOR UNDER VSF									REMOVED IN 2018 (MAPLE PROJECT #16687).		N/A
S555B	RIG ROOM	MASTIC		FLOOR									MASTIC REMOVED JULY 2021 ACCORDING TO UTSC NOTICE OF PROJECT		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-02A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21466439)		N/A
S556K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES - THROUGHOUT THE CORRIDOR	10	R-SA42	15	CHRYSTILE	GOOD	C	YES	FRIABLE	AT STAIRWELL S556S. REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA11, & R-SA120-(A-F)-06 R-SA51		ND			NO				N/A
S556S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING	3	R-SA42	15	CHRYSTILE	GOOD	C	YES	FRIABLE			4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S557	LAB	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	244 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S557A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S558	OFFICE	NEW LAY-IN CEILING TILES	GREY SPECKLED SHEET FLOORING								NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S558A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S559	OFFICE	NO SUSPECT ACM OBSERVED									NO				N/A
S559A	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S560	OFFICE	NO SUSPECT ACM OBSERVED									NO				N/A
560A	OFFICE	TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S561	WAITING AREA	NO SUSPECT ACM OBSERVED									NO				N/A
S561A	PSYCHOLOGY LAB 1	MASTIC		FLOOR					GOOD		YES	NON-FRIABLE			4
S561B	PSYCHOLOGY LAB 2	MASTIC		FLOOR					GOOD		YES	NON-FRIABLE			4
S561C	LAB SUPPORT	REFER TO S555B													N/A
S561D	RIG ROOM	REFER TO S555B													N/A
S561E	PSYCHOLOGY LAB 4	MASTIC		FLOOR			<5	CHRYSTILE	GOOD		YES	NON-FRIABLE			4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-02A-C		ND			NO		SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT 21466439)		N/A
S561F	PSYCHOLOGY LAB 5	MASTIC		FLOOR					GOOD		YES	NON-FRIABLE			4
S561G	PSYCHOLOGY LAB 6	MASTIC		FLOOR					GOOD		YES	NON-FRIABLE			4
S561H	PSYCHOLOGY LAB 8	MASTIC		FLOOR					GOOD		YES	NON-FRIABLE			4
S562	OFFICE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	96 SQ. FT.	R-SA45 & R-SA120-(A-F)-06		ND			NO				N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	50 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	THESE TILES WERE REMOVED AND REPLACED WITH NON-ASBESTOS FLOORING AS PART OF RENOVATIONS IN AUGUST 2011. HOWEVER, RESIDUAL AMOUNTS OF ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NON-ASBESTOS FLOORING.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S562V	VESTIBULE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	4	R-SA42	15	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	96 SQ. FT.	R-SA45		ND			NO				N/A
S563	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S563A	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ROOM S563A - AT NORTH WALL	4	R-SA42	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE	AT GROUND LEVEL		4
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S563B	OFFICE	NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S563C	OFFICE	NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S564	OFFICE	NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S564A	OFFICE	NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE ABOVE DOOR	4	R-SA42	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING		4
S565	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	200 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	VINYL FLOOR TILES AND BLACK FLOOR MASTIC REMOVED IN 2019 (MAPLE PROJECT #18439). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	180	R-SA11 & R-SA120-(A-F)-06		ND			NO		TRANSITE COUNTERTOP AND PANELS REMOVED IN 2019 (MAPLE PROJECT #17990). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S565A	OFFICE	BLACK & YELLOW MASTIC	FLOOR MASTIC	FLOOR UNDER VSF									REMOVED IN 2019 (MAPLE PROJECT #18439).		N/A
		VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING		4
S566	OFFICE	BLACK & YELLOW MASTIC	FLOOR MASTIC	FLOOR UNDER VSF									REMOVED IN 2019 (MAPLE PROJECT #18439).		N/A
		2'x4' ACOUSTIC TILES	PINHOLES	CEILING	64 SQ. FT.	R-SA56		ND			NO		ADDITIONAL SAMPLING IS RECOMMENDED		N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	180	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S566	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS										SELECT FITTINGS REMOVED IN 2019 (MAPLE PROJECT #18453). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S566A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S567	OFFICE	2'x4' ACOUSTIC TILES	UNKNOWN	CEILING	212	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
S567A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S567B	OFFICE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	140 SQ. FT.	R-SA45 & R-SA120-(A-F)-06		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	25622-022-17A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
		VINYL SHEET FLOORING	NEW - 2009	NEW - 2009							NO				N/A
S568A	IT ROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	WALL PANEL	6 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE	OBSERVED AT APPROXIMATELY 10 FOOT HEIGHT, AT THE ENTRANCE.		4
S568S	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S569	OFFICE	2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING	244 SQ. FT.	R-SA11 & R-SA120-(A-F)-06		ND			NO				N/A
		VINYL SHEET FLOORING	NEW - 2009	NEW - 2009							NO				N/A
S569A	OFFICE	VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	NEW - 2009							NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S570E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S571	STORAGE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions


ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S572	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	25622-022-18A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
		VINYL SHEET FLOORING	SHEET FLOORING (LIGHT BROWN MOSAIC)	FLOOR	120 SQ. FT.	R-SA34 & R-SA108-(A-C)-06		ND			NO				N/A
		TRANSITE ASBESTOS-CEMENT PANEL	TRANSITE(TM) ASBESTOS-CEMENT PANELLING	PERIMETER RADIATOR UNITS	35 SQ. FT.				GOOD	B	SUSPECT	NON-FRIABLE	MATERIAL IS PRESUMED TO BE IN MOST PERIMETER ROOMS THROUGHOUT BUILDING (REMOVED FROM SELECT AREAS IN 2009). ASBESTOS-CONTAINING PIPE ELBOW AND FITTING INSULATION MAY ALSO BE PRESENT WITHIN THE PERIMETER RADIATOR SYSTEM.		4
S572K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-022-19A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
		SUSPENDED CEILING TILES	2" X 4', LONG FISSURES AND PINHOLES	CEILING		26347-1A-C & 26347-2A-C		ND			NO				N/A
		SUSPENDED CEILING TILES	2" X 4', SMALL FISSURES AND PINHOLES	CEILING		26347-3A-C		ND			NO				N/A
S600A	ELEVATOR	VINYL SHEET FLOORING		FLOOR	100 SQ. FT						NO				N/A
S600B	ELEVATOR	VINYL SHEET FLOORING	DIAMOND (CHECKER) SHEET FLOORING	FLOOR	100 SQ. FT	SA111-(A-B)-06		ND			NO				N/A
S601	WASHROOM	NEW VINYL SHEET FLOORING	BEIGE/BBLUE SPECKLED SHEET FLOORING - NEW								NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING & WALL	100 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	DRYWALL BULKHEAD (EXIT STAIR) REMOVED IN 2019		4
		PARGING CEMENT	FITTINGS	MECHANICAL SHAFT							NO		1 PARGING CEMENT FITTING REMOVED FROM SHAFT IN 2019 (MAPLE PROJECT#18105). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S601S	STAIRWELL	DRYWALL	DRYWALL JOINT COMPOUND	CEILING & WALL	100 SQ. FT.	17553 S01B	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17553). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		DRYWALL	DRYWALL JOINT COMPOUND	BULKHEAD	50 SQ. FT.						NO		REMOVED IN 2018 (MAPLE PROJECT #17553). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		GREY DOOR CAULKING	GREY CAULKING	DOOR	UNKNOWN	17553 S02A	2	CHRYSTILE	GOOD	A	NO	NON-FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17553). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.



Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S611	AHU - 6TH FLOOR	INSULATION MATERIAL	PAPER MATERIAL AND TAR	GENERAL ROOM		26924-1A-C, 2A-C, 3A-C, 4A-C, 5A-C & 6A-C		ND			NO		SAMPLED BY OHE IN AUGUST 2021 (OHE PROJECT #26924). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	PARGING CEMENT	GENERAL ROOM	1	R-SA60	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SELECT FITTINGS REPAIRED IN 2019 (MAPLE PROJECT #17758). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	STORM SEWER	GENERAL ROOM	300	R-SA60	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SELECT FITTINGS, STRAIGHTS AND GASKETS REMOVED IN 2018 DURING RENOVATIONS (MAPLE PROJECT #16728, SIF 12-13). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	300	R-SA60	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	FITTINGS ASSOCIATED WITH AHU 16 REMOVED IN DEC 2017 (MAPLE PROJECT #16893). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	WATER SOFTENER	GENERAL ROOM	300	R-SA60	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	FITTINGS ASSOCIATED WITH WATER SOFTENER REMOVED IN 2018 (MAPLE PROJECT #16728)		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	12	R-SA60	50-75	CHRYSTILE	GOOD	B/C	YES	FRIABLE	SELECT FITTINGS REMOVED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ACROSS FROM AC09 AT THE VERY END OF THE MECHANICAL ROOM ABOVE DUCTWORK	2	R-SA60	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REMOVED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S611	AHU - 6TH FLOOR	PARGING CEMENT INSULATION AIR HANDLING UNIT 13	PARGING CEMENT	BODY OF AIR HANDING UNIT							NO		MATERIAL REMOVED IN 2018 (MAPLE PROJECT #16728). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION AIR HANDLING UNIT 14	PARGING CEMENT	BODY OF AIR HANDING UNITS							NO		MATERIAL REMOVED IN 2018 (MAPLE PROJECT #16728). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		MECHANICAL GASKETS	WOVEN GASKETS	ASSOCIATED WITH AIR HANDLING UNITS							NO		ITEM REMOVED IN 2018 (MAPLE PROJECT #16728). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR TO ROOM S612B	250 SQ. FT.	SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		17594 S03A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17594). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		GREY FIRE STOP ON FLOOR	FIRESTOP	FLOOR		17594 S04A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17594). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ON WALL NEAR AIR HANDLING UNIT #11	2	R-SA60	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ON WALL COLUMN, NEAR DOOR TO SW612	1	R-SA60	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.



Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S611	AHU - 6TH FLOOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ON WALL COLUMN, NEAR AC #7	1	R-SA60	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	NEAR DOOR TO SW612A	1	R-SA60	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S611	AHU - 6TH FLOOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	NEAR AC #8	3	R-SA60	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	NEAR AC #10	1	R-SA60	50-75	CHRYSTILE	POOR	B	YES	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT INSULATION SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
		BLACK FIRESTOP ON FLOOR	FIRESTOP	FLOOR		17594 S05A	0.5	CHRYSTILE	GOOD	B	YES	FRIABLE	SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17594). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		GREY FIRESTOP	FIRESTOP	WALL AT AC10		17758 S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17758). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S611	AHU - 6TH FLOOR	TRANSITE™ ASBESTOS-CEMENT	WALL PANELS	GENERAL ROOM	200 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	B/C	YES	NON-FRIABLE	SELECT PANELS REMOVED IN 2017 (MAPLE PROJECT #16728, SIF 12-13). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		DUCT GASKET	DUCT GASKET	AC10			1	CHRYSTILE	GOOD		YES		SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #17433-1). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S612	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	6	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S612A	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	3	R-SA1	50-75	CHRYSTILE	GOOD	B	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S612B	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S612C	STAIRWELL	PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR	250 SQ. FT.	SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S613S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	3	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		TRANSITE™ ASBESTOS-CEMENT	BLACK TRANSITE MATERIAL	NORTH AND SOUTH WALLS - PIPE/WALL PENETRATIONS	25 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR	35 SQ. FT.	01-B	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S624	LAB	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	300 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS IN JANUARY AND FEBRUARY 2011. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		DRYWALL		WALL	100 SQ. FT.	SA-34	1.9	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLES COLLECTED IN APRIL, 2015.		4
		2'x4' ACOUSTIC TILES	NEW	CEILING							NO		LIMITED VISIBILITY ABOVE CEILING TILES DUE TO DUCTS - NO SUSPECT ACM OBSERVED		N/A
S624A	MAIL ROOM	DRYWALL		INTERIOR & EXTERIOR WALL	350 SQ. FT	SA-34 to SA 35	1.6-1.9	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLES COLLECTED IN APRIL, 2015.		4
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	250 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	PRESUME THE MASTIC IS ALSO ASBESTOS-CONTAINING.		4
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	5 SQ. FT.	R-SA32	5	CHRYSTILE	POOR	A	YES	NON-FRIABLE	PRESUME THE MASTIC IS ALSO ASBESTOS-CONTAINING. THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES SHOULD BE REMOVED AND REPLACED FOLLOWING TYPE 1 OR 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.		2
S624B	LAB	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	300 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS IN JANUARY AND FEBRUARY 2011. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		2'x4' ACOUSTIC TILES	NEW	CEILING							NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING & WALL	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S624C	LAB	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	300 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS IN JANUARY AND FEBRUARY 2011. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		2'x4' ACOUSTIC TILES	NEW	CEILING							NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING & WALL	300 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S624D	LAB	VINYL SHEET FLOORING	LIGHT BEIGE SHEET FLOORING	FLOOR	50 SQ. FT.	R-SA110-D-06	2	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	ACM DETECTED IN MASTIC ONLY		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	200 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S624E	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL	150 SQ. FT.	25622-022-20A-C		ND			NO		SAMPLED BY OHE IN 2022 (OHE PROJECT 25622-022). MATERIAL WAS FOUND NOT TO CONTAIN ASBESTOS.		4
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS IN JANUARY AND FEBRUARY 2011. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		2'x4' ACOUSTIC TILES	NEW	CEILING							NO				N/A
S624F	ELEVATOR CORRIDOR	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS IN JANUARY AND FEBRUARY 2011. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S625	LAB	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	300 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS FROM JANUARY TO FEBRUARY 2012. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL		WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S625A	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	10 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS FROM JANUARY TO FEBRUARY 2012. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS		27221-1A-C	ND	ND			NO		SAMPLED BY OHE (Project #27221) IN 2021.		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S625B	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	300 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS FROM JANUARY TO FEBRUARY 2012. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL		WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S625K	CORRIDOR	DRYWALL		WALL	100 SQ. FT.	SA-34	1.9	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLES COLLECTED IN APRIL, 2015.		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	5 SQ. FT.	SA-34	1.9	CHRYSTILE	POOR	A	YES	NON-FRIABLE	DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05.		2
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S625V	VESTIBULE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	10SQ.FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS FROM JANUARY TO FEBRUARY 2012. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW DRYWALL		WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S626	OFFICE	DRYWALL		WALL	100 SQ. FT.	R-SA-34	1.9	CHRYSTILE	GOOD	A	YES	NON-FRIABLE			4
		NEW DRYWALL		WALL AND BULKHEAD							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S626A	OFFICE	NEW DRYWALL		WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S627	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS FROM JANUARY TO FEBRUARY 2012. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		NEW DRYWALL		WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S627A	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	150 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS FROM JANUARY TO FEBRUARY 2012. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		NEW DRYWALL		WALLS							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		NEW LAY-IN CEILING TILES									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
S627K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017		N/A
S628	LAB	NO SUSPECT ACM OBSERVED									NO		2012 BARE BASE RENOVATIONS COMPLETED. HOWEVER, NO ACCESS ABOVE WOOD PANELING.		N/A
S628A	LAB	NO SUSPECT ACM OBSERVED									NO		2012 BARE BASE RENOVATIONS COMPLETED. HOWEVER, NO ACCESS ABOVE WOOD PANELING.		N/A
S628B	LAB	NO SUSPECT ACM OBSERVED									NO		2012 BARE BASE RENOVATIONS COMPLETED. HOWEVER, NO ACCESS ABOVE WOOD PANELING.		N/A
S628C	LAB	NO SUSPECT ACM OBSERVED									NO		2012 BARE BASE RENOVATIONS COMPLETED. HOWEVER, NO ACCESS ABOVE WOOD PANELING.		N/A
S628D	LAB	NO SUSPECT ACM OBSERVED									NO		2012 BARE BASE RENOVATIONS COMPLETED. HOWEVER, NO ACCESS ABOVE WOOD PANELING.		N/A
S628E	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL		26348-1A-C & 26348-4A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26348). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S628K	LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL		26348-2A-C & 26348-3A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26348). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S628V	LAB	NO SUSPECT ACM OBSERVED									NO		2012 BARE BASE RENOVATIONS COMPLETED. HOWEVER, NO ACCESS ABOVE WOOD PANELING.		N/A
S630 (PREVIOUSLY S627B)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S631 (PREVIOUSLY S630A)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S632 (PREVIOUSLY S627B & S627C)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S632K (PREVIOUSLY S627C)	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S634 (PREVIOUSLY S629)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S636 (PREVIOUSLY S629)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S637 (PREVIOUSLY S630A)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S638 (PREVIOUSLY S631A)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S639 (PREVIOUSLY S630B)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S640 (PREVIOUSLY S631)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S640A (PREVIOUSLY S631)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S641 (PREVIOUSLY S632A)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S642 (PREVIOUSLY S632 & S634)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S642K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S643 (PREVIOUSLY S633 & S633A)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S644 (PREVIOUSLY S636)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S644A (PREVIOUSLY S636)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S645 (PREVIOUSLY S637 & S639)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S646 (PREVIOUSLY S638)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S646A (PREVIOUSLY S638)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S647 (PREVIOUSLY S639A)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S648 (PREVIOUSLY S640 & S641)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S648A (PREVIOUSLY S640 & S641)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S649 (PREVIOUSLY S643)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S650 (PREVIOUSLY S642)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S651 (PREVIOUSLY S643)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S651A (PREVIOUSLY S649)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S652 (PREVIOUSLY S644 & S645)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S655K (PREVIOUSLY S607K)	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S652S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO				N/A
S660 (PREVIOUSLY S464 & S647A)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S662 (PREVIOUSLY S647)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S664 (PREVIOUSLY S648)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S668 (PREVIOUSLY S650 & S651)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S669 (PREVIOUSLY S649B)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S669A (PREVIOUSLY S649A)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S699B (PREVIOUSLY S649B)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S699C (PREVIOUSLY S653)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S670 (PREVIOUSLY S652)	LAB	NO SUSPECT ACM OBSERVED									NO				N/A
S675 (PREVIOUSLY S609A)	OFFICE	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	75 SQ. FT.	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	PRESUME THE MASTIC IS ALSO ASBESTOS-CONTAINING. THE DAMAGED ASBESTOS-CONTAINING VINYL FLOOR TILES REMOVED FOLLOWING TYPE 1 OPERATION PROCEDURES (CURMANN CONTRACTING LTD. REPORT DATED JANUARY 7, 2022). MASTIC IS STILL PRESENT. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE		R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE			4
		2'x4' ACOUSTIC TILES	PINHOLES	CEILING		R-SA122-(A-F)		ND			NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	45 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE ELECTRICAL CLOSET DOOR	10 SQ. FT.	01-A	ND	ND			NO		SAMPLE LOCATION. SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S675A (PREVIOUSLY S609)	ELECTRICAL CLOSET	2'x4' ACOUSTIC TILES	PINHOLES	CEILING		R-SA122-(A-F)		ND			NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE IN ELECTRICAL CLOSET	15	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	REPAIRED IN 2014		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	45 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE ELECTRICAL CLOSET DOOR	10 SQ. FT.	01-A	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S675E (PREVIOUSLY S609E)	ELEVATOR	NEW VINYL SHEET FLOORING									NO				N/A
S676K (PREVIOUSLY S608 AND S613K)	CORRIDOR	2'x4' ACOUSTIC TILES	PINHOLES	CEILING		R-SA122-(A-F)-06		ND			NO		LOCATION PREVIOUSLY S613K		N/A
		2'x4' ACOUSTIC TILES	LENGTH-WISE FISSURE	CEILING		R-SA-11	ND	ND			NO				N/A
		VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	NEW - 2009							NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING TILES	2	R-SA1	50-75	CHRYSTILE	GOOD	C	YES	FRIABLE	AT DOOR TO S680-692		4
		FLOOR MASTIC	YELLOW AND GREY	FLOOR - DOORWAY THRESHOLD				ND			NO		SAMPLED IN 2022 BY OHE IN 2022 (OHE PROJECT #27349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		LEVELLING COMPOUND	GREY	FLOOR - DOORWAY THRESHOLD				ND			NO		SAMPLED IN 2022 BY OHE IN 2022 (OHE PROJECT #27349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	45 SQ. FT.				GOOD	A	SUSPECT	NON-FRIABLE	MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY OTHERS AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED.		4
S676S	STAIRWELL	NO SUSPECT ACM OBSERVED									NO		LOCATION PREVIOUSLY S610S		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.


Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S680K (PREVIOUSLY S614K)	CORRIDOR	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S681 (PREVIOUSLY S615)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S682 (PREVIOUSLY S616)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S683 (PREVIOUSLY S617)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S685 (PREVIOUSLY S618)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S686 (PREVIOUSLY S619)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S687 (PREVIOUSLY S620)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S688 (PREVIOUSLY S619A)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S689 (PREVIOUSLY S621)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S690 (PREVIOUSLY S621)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S691 (PREVIOUSLY S621)	LAB	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN 2017 (MAPLE PROJECT #16617, SIF 2.0). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S692 (PREVIOUSLY S621)	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING	2				GOOD	B	SUSPECT	FRIABLE			4
S692K (PREVIOUSLY S621A)	VESTIBULE	TEXTURED PLASTER	TEXTURED PLASTER	ABOVE DOOR TO SW622B		16892 S01A-C	ND	ND			NO		MATERIAL SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #16892). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		NEW VINYL SHEET FLOORING									NO		MATERIAL NOT SUSPECTED TO CONTAIN ASBESTOS		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.



Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S700K	CORRIDOR	VINYL FLOOR TILES	9x9 YELLOW FLOOR TILE	FLOOR	400 SQ. FT	R-SA32	5	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	FLOOR TILES WERE REMOVED DURING RENOVATIONS IN FEBRUARY 2011. HOWEVER, RESIDUAL AMOUNTS OF THE ASBESTOS-CONTAINING MASTIC MAY REMAIN BENEATH THE NEW, NON-ASBESTOS FLOORING.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE									ALL PARGING CEMENT PIPE FITTINGS REMOVED IN 2022 (OHE PROJECT 28213)		N/A
S701S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	8	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
	GREENHOUSE	CAULKING	GREY CAULKING	WINDOW CAULKING ON EXTERIOR		18348 S04A-C	1	CHRYSTILE	GOOD	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18348). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S702A	GREENHOUSE	CAULKING	OFF-WHITE CAULKING	DOOR CAULKING	3 L. FT.	25622-21A-C	1	CHRYSTILE	POOR	A	YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18348) AND OHE IN 2022 (OHE PROJECT #25622-022). REMOVE ASBESTOS CONTAINING CAULKING FOLLOWING TYPE 1 ASBESTOS PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05.		2
		CAULKING	OFF-WHITE CAULKING	DOOR CAULKING			1	CHRYSTILE	GOOD		YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18348) AND OHE IN 2022 (OHE PROJECT #25622-022). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S702B	GREENHOUSE	CAULKING	OFF-WHITE CAULKING	DOOR CAULKING	15 L. FT.		1	CHRYSTILE	GOOD		YES	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18348). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		CAULKING	OFF-WHITE CAULKING	DOOR CAULKING	5 L. FT.		1	CHRYSTILE	POOR	A	YES	NON-FRIABLE	REMOVE ASBESTOS CONTAINING CAULKING FOLLOWING TYPE 1 ASBESTOS PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05.		2
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
		TRANSITE™ ASBESTOS CEMENT	WALL	WALL	50	R-SA22	15-25	CROCIDOLITE	POOR	A	YES	NON-FRIABLE	DURING 2022 REASSESSMENT, TRANSITE ASBESTOS-CEMENT WAS OBSERVED ON THE PERIMETER WALLS OF THE GREENHOUSE. REMOVE FOLLOWING TYPE 1 ASBESTOS PROCEDURES AS PRESCRIBED UNDER O.REG. 278/05		2
		TRANSITE™ ASBESTOS-CEMENT	WALL	WALL	100	R-SA22	15-25	CROCIDOLITE	GOOD	A	NO	NON-FRIABLE			N/A
S702C	GREENHOUSE	TRANSITE™ ASBESTOS-CEMENT	WALL	WALL AND TABLES	30 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE			4
		CEMENT PANEL	PLATFORM	NORTH SIDE OF DOOR LEADING TO S702D				ND			NO		SAMPLED BY OHE IN 2023 (PROJECT 28528).		N/A
		CAULKING	GREY	WEST OVERHANG, NORTH SIDE OF DOOR LEADING TO S702D				ND			NO		SAMPLED BY OHE IN 2023 (PROJECT 28528).		N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS		UNKNOWN		50-75	CHRYSTILE			YES		ONE FITTING REMOVED IN 2020 (MAPLE PROJECT (#18695). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		BLACK MASTIC	WALL	BEHIND TRANSITE PANELS	UNKNOWN	18098 S03A-C		ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S702D	GREENHOUSE	TRANSITE™ ASBESTOS-CEMENT	WALL	WALL AND TABLES	400 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	A	YES	NON-FRIABLE	SELECT TRANSITE BOARDS FROM WALLS AND TABLES REMOVED IN 2020 (MAPLE PROJECT (#18695). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS				50-75	CHRYSTILE			YES		ONE FITTING REMOVED IN 2020 (MAPLE PROJECT (#18695). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		CAULKING	OFF-WHITE CAULKING	FLOOR CAULKING		S02A-C	3	CHRYSTILE			YES		SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18348). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
S702V	ELEVATOR LOBBY	CAULKING	OFF-WHITE CAULKING	DOOR CAULKING			1	CHRYSTILE			YES		SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18348). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	30 SQ. FT.	01-C	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S703	ELECTRICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	6	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S703A	ELECTRICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	8	R-SA1	50-75	CHRYSTILE	GOOD	A	YES	FRIABLE			4
		PAINTED TEXTURE COAT OVER PLASTER	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR		SA 01 (A-G)	ND	ND			NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE BUILDING DURING THE 2016 REASSESSMENT.		N/A
S703E	ELEVATOR	NO SUSPECT ACM OBSERVED									NO				N/A
S705	LABS	NO SUSPECT ACM OBSERVED									NO				N/A
S705K	CORRIDOR	NO SUSPECT ACM OBSERVED									NO				N/A
S706	LABS	NO SUSPECT ACM OBSERVED									NO				N/A
S707	LABS	NO SUSPECT ACM OBSERVED									NO				N/A
S708	LABS	NO SUSPECT ACM OBSERVED									NO				N/A
S709	LABS	NO SUSPECT ACM OBSERVED									NO				N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 – Perform asbestos removal/repair for compliance with the regulations.
3 – Type 2 asbestos procedures required to enter area.
4 – Regular inspection/surveillance of ACM for compliance with the regulations.
N/A – Not applicable.

Definitions
ACM – Asbestos-Containing Materials
SA – Sample representative
R-SA – Sample referenced to a visually similar homogeneous sample material.
ND – None detected

Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Type	Condition	Accessibility	ACM (Yes, No, Suspect)	Friability	Comments	Photographs	Action Required
S710	LABS	DRYWALL	DRYWALL JOINT COMPOUND	BULKHEAD AT GROUND LEVEL		17781 S01A-C	ND	ND			NO		SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17781). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		VINYL SHEET FLOORING	GREY WITH MOSAIC PATTERN	FLOOR		26349-1A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		MASTIC	BELOW VINYL SHEET FLOORING	FLOOR		26349-1A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CEMENTITIOUS CAULKING MATERIAL, GREY	UNDER VINYL SHEET FLOORING, CONCRETE FLOOR	FLOOR		26349-2A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		TAR MATERIAL	UNDER VINYL SHEET FLOORING, CONCRETE FLOOR	FLOOR		26349-3A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		PAPER MATERIAL	UNDER THE CONCRETE FLOOR	FLOOR		26349-4A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CEMENTITIOUS MATERIAL, LIGHT BROWN AND GREY	IN THE CONCRETE FLOOR	FLOOR		26349-5A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CEMENTITIOUS MATERIAL, DARK GREY	ON THE CONCRETE FLOOR	FLOOR		26349-6A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CEMENTITIOUS MATERIAL, LIGHT GREY	ON THE CONCRETE FLOOR	FLOOR		26349-6A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
		CEMENTITIOUS MATERIAL, GREY	IN THE CONCRETE FLOOR	FLOOR		26349-7A-C	ND	ND			NO		SAMPLED BY OHE IN 2021 (OHE PROJECT #26349). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.		N/A
S711	LABS	NO SUSPECT ACM OBSERVED									NO				N/A
S712	LABS	NO SUSPECT ACM OBSERVED									NO				N/A
S713	LABS	NO SUSPECT ACM OBSERVED									NO				N/A
S714	HOT WATER TANK ROOM	NO SUSPECT ACM OBSERVED									NO		ALL ACM REMOVED IN FEB 2015		N/A

Level of Accessibility
A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required
1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions
ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected