

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|--------------------------------|-----------------------------------|--|-------------------|----------------------|----------------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| ALL | ALL AREAS | GREY INSULATION MATERIAL | INSULATION MATERIAL WITHIN CAVITY DOOR | DOOR | UNKNOWN | A01a | 50 | CHRYSOTILE | YES | GOOD | B | FRIABLE | SAMPLED IN BV306 DOOR BY WSP (PROJECT #23595185), AND PRESUMED TO BE PRESENT IN OTHER DOORS THROUGHOUT THE BUILDING. ADDITIONAL SAMPLING IS RECOMMENDED PRIOR TO REMOVAL OR REPAIRS. | 4 |
| B1.1 ROOF | ROOF | CAULKING | BROWN CAULKING | COPPER ROOF | | 29265-1A-C | | ND | NO | | | | SAMPLED BY OHE IN 2023 (PROJECT #29265). | N/A |
| | | CAULKING | OFF-WHITE CAULKING | COPPER ROOF | | 29265-1A-C | | ND | NO | | | | SAMPLED BY OHE IN 2023 (PROJECT #29265). | N/A |
| | | CAULKING | GREY CAULKING | COPPER ROOF | | 29265-2A-C | | ND | NO | | | | SAMPLED BY OHE IN 2023 (PROJECT #29265). | N/A |
| B100T | STEAM TUNNEL | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B200 | MEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | | SA-1A-G | | ND | NO | | | | SAMPLED BY GOLDER IN 2021 (PROJECT #21460953-1000). ROOM WAS RENOVATED IN 2008. REFER TO PROJECT DCM2008-11. | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | SA-2A-C | | ND | NO | | | | SAMPLED BY GOLDER IN 2021 (PROJECT #21460953-1000). ROOM WAS RENOVATED IN 2008. REFER TO PROJECT DCM2008-11. | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | | N/A |
| B202 | CLEANER | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 3 | R-SA69 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | LIMITED ACCESS ABOVE CEILING | 4 |
| B202A | ELECTRICAL | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B203 | SINGLE USER WASHROOM | FIRESTOP | PIPE JOINT | CEILING SPACE | 4 | R-SA76 | 5 | AMOSITE | YES | GOOD | C | FRIABLE | | 4 |
| | | CERAMIC FLOOR TILES | | | | | | | NO | | | | | N/A |
| B204 | MEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 25622-024-1A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (PROJECT #25622-024). | N/A |
| | | CERAMIC FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B205E | ELEVATOR | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B206 | TIM HORTON'S | PARGING CEMENT ON PIPE FITTINGS | BLUE ENCAPSULATED | CEILING SPACE | 19 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | LIMITED ACCESS ABOVE CEILING | 4 |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | VINYL SHEET FLOORING | TAN SHEET FLOORING | FLOOR | -- | 20909 S01A-C | ND | ND | NO | -- | -- | -- | SAMPLED BY MAPLE IN 2023 (PROJECT #20909). | N/A |
| | | VINYL SHEET FLOORING | BEIGE SHEET FLOORING | FLOOR | -- | 20909 S02A-C | ND | ND | NO | -- | -- | -- | SAMPLED BY MAPLE IN 2023 (PROJECT #20909). | N/A |
| | | FLOOR MASTIC | COLOURLESS MASTIC | FLOOR UNDER VSF | -- | 20909 S01A-C, S02A-C | ND | ND | NO | -- | -- | -- | SAMPLED BY MAPLE IN 2023 (PROJECT #20909). | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS AND CEILING | | S03A-C | ND | ND | NO | -- | -- | -- | SAMPLED BY MAPLE IN 2023 (PROJECT #20909). | N/A |
| B206A | TIM HORTON'S KITCHEN | MORTAR AND MASTIC ON CERAMIC TILE | WHITE MORTAR AND YELLOW MASTIC ON CERAMIC TILE | WALLS | | S04A-C | | ND | NO | -- | -- | -- | SAMPLED BY MAPLE IN 2023 (PROJECT #20909). | N/A |
| | | NEW DRYWALL CEILING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS AND CEILING | | S03A-C | ND | ND | NO | -- | -- | -- | SAMPLED BY MAPLE IN 2023 (PROJECT #20909). | N/A |
| B206B | ELECTRICAL / ELEVATOR 9 ACCESS | PARGING CEMENT ON PIPE FITTINGS | BLUE ENCAPSULATED | CEILING SPACE | 2 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | VERY LIMITED ACCESS ABOVE CEILING DURING ASSESSMENT | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 800 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | NEW DRYWALL CEILING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 7 SQ. FT. | R-SA66 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B207A | KITCHEN STORAGE / PREP | NEW DRYWALL CEILING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 8 L. FT. + 7 SQ. FT. | 18765B-20 & 18765-24 | 1 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 800 SQ. FT. | 18765B-20 & 18765-24 | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2020 (PROJECT #18765B). | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | BLUE ENCAPSULATED | CEILING SPACE | 1 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | VERY LIMITED ACCESS ABOVE CEILING DURING ASSESSMENT | 4 |
| B210L | STORAGE | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | N/A | |
| B210S | STAIRCASE | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | N/A | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|------------------|---------------------------------|--------------------------|-----------------------------------|------------|-----------------------|-------|------------|------------------------|-----------|---------------|-------------|--|--|
| B220 | WOMEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 18765 S01A-C, SA-4A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2020 (PROJECT #18765) ALSO SAMPLED BY GOLDER IN 2021 (PROJECT #21460953). THE ROOM WAS RENOVATED IN 2008. REFER TO PROJECT DCM2008-11. | N/A |
| | | NEW DRYWALL CEILING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | NEW CERAMIC FLOOR TILES | | | | | | | | NO | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B220E | ELEVATOR | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B220K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM AND CEILING SPACE | 45 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | MANY HAVE BEEN REPAIRED TO FG & PVC, 2 REPAIRED IN 2018 (MAPLE PROJECT #16940) | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL, EXTERIOR OF B200 | | SA 3A-C | | ND | NO | | | | SAMPLED BY GOLDER IN 2021 (PROJECT #21460953-1000). | N/A |
| | | FIRESTOP | PIPE JOINT | GENERAL ROOM AND CEILING SPACE | | R-SA76 | 5 | AMOSITE | YES | GOOD | A | FRIABLE | | 4 |
| B222 | STORAGE ROOM | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 10 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 |
| B224S | STAIRWELL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 9 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 1 | R-SA60 | 50-75 | CHRYSOTILE | YES | POOR | A | FRIABLE | THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B230 | LOCKER AREA | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 10 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 1 | R-SA60 | 50-75 | CHRYSOTILE | YES | POOR | A | FRIABLE | THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | VINYL FLOOR TILES | 12 X 12 GREEN FLOOR TILE | FLOOR BELOW VSF AND UNDER LOCKERS | UNKNOWN | | | | | NO | GOOD | C | NON-FRIABLE | PRESUMED ACM TILES AND MASTIC MAY BE PRESENT BENEATH VINYL SHEET FLOORING AND UNDER LOCKERS. |
| B230K | CORRIDOR | VINYL FLOOR TILES | 12 X 12 GREEN FLOOR TILE | FLOOR BELOW VSF AND UNDER LOCKERS | UNKNOWN | | | | NO | GOOD | C | NON-FRIABLE | PRESUMED ACM TILES AND MASTIC MAY BE PRESENT BENEATH VINYL SHEET FLOORING AND UNDER LOCKERS. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | BULKHEAD | UNKNOWN | S01A | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18264). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 32 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | FOUR FITTINGS REMOVED IN 2020 (OHE REPORT #26206) | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 3 | R-SA60 | 50-75 | CHRYSOTILE | YES | POOR | A | FRIABLE | WATER STAINED AND VISUALLY IDENTIFIED MOULD GROWTH. THE DAMAGED ASBESTOS-CONTAINING PARGING CEMENT FITTING SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B230S | STAIRWELL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 5 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 400 SQ. FT | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B240E | ELEVATOR | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | N/A | |
| B240K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING | 35-40 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|------------------|---------------------------------|------------------------|--------------|----------------------|-----------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B242 | VESTIBULE | LEVELLING COMPOUND | BELOW CARPET | FLOOR | | 17973 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | BLACK FOAM | BELOW CARPET | FLOOR | | 17973 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | BROWN MASTIC | BASEBOARDS | WALL | | 17973 S03A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | SOUTH WALL | 50 SQ. FT. | 17973 S01A | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 4 L. FT. + 2 SQ. FT. | 17973 S01A | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B242A | STORAGE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 6 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |
| | | LEVELLING COMPOUND | BELOW CARPET | FLOOR | | 17973 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | BLACK FOAM | BELOW CARPET | FLOOR | | 17973 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 150 SQ. FT. | 17973 S01A | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 2 SQ. FT. | 17973 S01A | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B246 | ELECTRICAL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 150 SQ. FT. | R-SA17 (A-C)-08 | 1.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 9 SQ. FT. | R-SA17 (A-C)-08 | 1.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B248S | STAIRWELL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 600 SQ. FT. | R-SA17 (A-C)-08 | 1.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B250 | WOMEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | 200 SQ. FT. | 18765 S02A-C | 1-2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2020 (PROJECT #18765). NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| B250V | WOMEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | 11 SQ. FT. | 18765 S03A-C | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| B252 | CLEANER | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 12 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|--|---------------------------------|-------------------------------|------------------------------|-------------|---------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B254 | MEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | 200 SQ. FT | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | DRYWALL CEILING - ADDITIONAL SAMPLING IS RECOMMENDED. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| | | VINYL SHEET FLOORING | WHITE VINYL SHEET FLOORING | FLOOR | | S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17196). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | N/A |
| | | VINYL SHEET FLOORING | BLACK MASTIC | BELOW FLOOR | | S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17196). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | N/A |
| B254V | MEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | 72 SQ. FT | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | DRYWALL CEILING - ADDITIONAL SAMPLING IS RECOMMENDED. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| B260 | CLASSROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ.FT | 17973 S04A | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05 | 2 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1250 SQ. FT | 17973 S04A | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM / CEILING SPACE | 15 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | LIMITED ACCESS TO FITTINGS - VIEWED THROUGH HATCHES | 4 |
| | | DOOR CAULKING | YELLOW CAULKING | DOOR TO BV242 | | 17973 S05A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17973). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | VINYL SHEET FLOORING | BROWN SPECKLED SHEET FLOORING | FLOOR | | 17059 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17059). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| B260K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | NORTH WALL | | 18474 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18474). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 3 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| B264 | CLASSROOM | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 75+ | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | SELECT FITTINGS REMOVED IN 2018 (MAPLE PROJECT #17222). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | | | | NO | | | | ALL DRYWALL REMOVED IN 2018 DUE TO RENOVATIONS (MAPLE PROJECT #17178). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | VINYL SHEET FLOORING | BROWN SPECKLED SHEET FLOORING | FLOOR | | 17059 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17059). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | TRANSITION AREAS BETWEEN BLADEN WING AND HIGHLAND HALL | REMNANTS OF RECREATION WING | | | | | | | SUSPECT | | | | ANY MATERIAL THAT IS A REMNANT OF THE RECREATION WING SHOULD BE ASSESSED FOR THE PRESENCE OF ASBESTOS PRIOR TO DISTURBANCE. | N/A |
| B300E | ELEVATOR | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|------------------|----------------------------------|-----------------------------|---------------------------|-------------|-----------------|-----------|------------|------------------------|-----------|---------------|-------------|---|---|-----|
| B300K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 | |
| | | VINYL SHEET FLOORING | GREY COLORED SHEET FLOORING | FLOOR | 600 SQ. FT | 17892 S03 | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | DOOR CAULKING | GREY DOOR CAULKING | DOUBLE DOORS OUTSIDE B304 | 150 SQ. FT | 17892 S01 | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 150 SQ. FT | 17892 S02 | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| B300L | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WEST WALL | 150 SQ. FT. | 18009 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18009). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| B300S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1500 SQ. FT | R-SA19 (A-C)-08 | 1.25 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | MASTIC ASSOCIATED WITH STAIRCASE | YELLOW AND WHITE MASTIC | STAIRCASE TREADS | | | 17892 S04 | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| B300V | VESTIBULE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | VESTIBULE | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 | |
| B304 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 25622-024-2A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #25622-024) | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DOOR | DOOR | DOOR | | | | | NO | | | | | NO ACM INSULATION WAS FOUND WITHIN DOOR CAVITY DURING FACILITIES INSPECTION IN MARCH 2023. | N/A |
| B306 | EMRG OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 500 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DOOR INSULATION | GRAY INSULATION IN DOOR | DOOR | | | | | | | | | | DOOR WITH ACM INSULATION WAS REMOVED IN 2023 AND A NEW DOOR INSTALLED (WSP PROJECT #23596713). | N/A |
| B308 | STORAGE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 520 SQ. FT. | R-SA96 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | VERY MINOR DAMAGES BEHIND THE DOOR | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B309 | WOMEN'S WASHROOM | NEW DRYWALL CEILING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. RENOVATED IN 2015. REFER TO PROJECT DCM2015-05. | N/A | |
| B309V | WOMEN'S WASHROOM | NEW DRYWALL CEILING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. RENOVATED IN 2015. REFER TO PROJECT DCM2015-05. | N/A | |
| B309K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | ELBOWS | GENERAL ROOM | 6 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 | |
| B310 | CLEANERS | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B311 | MEN'S WASHROOM | NEW DRYWALL CEILING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. RENOVATED IN 2015. REFER TO PROJECT DCM2015-05. | N/A | |
| B311V | MEN'S WASHROOM | NEW DRYWALL CEILING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. RENOVATED IN 2015. REFER TO PROJECT DCM2015-05. | N/A | |
| B316 | STORAGE ROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 446 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | VERY MINOR DAMAGES AT THE OLD CABINETRY | 4 | |
| B318 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 400 SQ. FT. | SA66 | 0.25 | CHRYSOTILE | NO | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED. MONITOR MINOR CRACKS PRESENT DURING FUTURE ASSESSMENTS. | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B320 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED. MONITOR MINOR CRACKS PRESENT DURING FUTURE ASSESSMENTS. | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B322 | STORAGE | VINYL FLOOR TILE | 12"X12" RED FLOOR TILES | FLOOR | 40 SQ. FT. | R-SA65 | 5 | CHRYSOTILE | YES | GOOD | B | NON-FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | | S05A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2020 (PROJECT #18765) | N/A |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|-----------------|---------------------------------|--------------------------------|---------------------|--------------|----------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B324 & B325 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| | | NEW CARPET FLOOR | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B326 | STORAGE | VINYL FLOOR TILE | 12"X12" RED FLOOR TILES | FLOOR | 100 SQ. FT. | R-SA65 | 5 | CHRYSOTILE | YES | GOOD | B | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 90 SQ. FT. | R-SA20(A-E)-08 | 2 | CHRYSOTILE | YES | GOOD | B | NON-FRIABLE | | 4 |
| B326K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 3000 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | ELBOWS AND FITTINGS | CEILING SPACE | 85-100 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| B328S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1000 SQ. FT. | R-SA20(A-E)-08 | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B328V | VESTIBULE | PARGING CEMENT ON PIPE FITTINGS | ELBOWS | GENERAL ROOM | 13 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 72 SQ. FT. | R-SA20(A-E)-08 | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B330 | LOCKER ROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 585 SQ. FT. | SA20(A-E)-08 | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 3 SQ. FT. | SA20(A-E)-08 | 2 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B330S | STAIRCASE | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B332V | VESTIBULE | PARGING CEMENT ON PIPE FITTINGS | ELBOWS | GENERAL ROOM | 2 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| | | WINDOW GLAZING | WINDOW GLAZING ON DOUBLE DOORS | DOOR | | A05A-C | ND | ND | NO | | | | SAMPLED BY WSP IN 2023 (PROJECT #23595187). | N/A |
| B334 | OFFICE | PARGING CEMENT ON PIPE FITTINGS | ELBOWS | GENERAL ROOM | 14 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 25622-024-3A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #25622-024). | N/A |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B335 | OFFICE | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | ELBOWS | ABOVE CEILING TILES | 6 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | D | FRIABLE | | 4 |
| B335A | STORAGE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 50 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| B335K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 22 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | 3 FITTINGS REMOVED IN OCT. 2023 BY ENVIROSAFE ACCORDING TO UTSC NOTICE OF ASBESTOS REMOVAL. | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 200 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| B337 | CLEANERS | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | N/A | |
| B339 | ELECTRICAL ROOM | NO SUSPECT ACM OBSERVED | | | | | | | | | | | | N/A |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building component.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|----------------|-----------------------------------|--|---|-------------|----------------------------------|-------|------------|------------------------|-----------|---------------|--|--|---|-----|
| B340 | CLASSROOM | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 1 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 | |
| | | CEILING PANELS | SIPOREX CEILING PANELS | CEILING | | | | | | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND (BEIGE) | BULKHEADS / BEAM ENCLOSURES ON CEILING | UNKNOWN | 25948-1A | 1 | CHRYSOTILE | YES | GOOD | B | NON-FRIABLE | | ASBESTOS-CONTAINING DJC IS PRESENT ON 7 BEAM ENCLOSURES RUNNING NORTH-SOUTH (BENEATH SIPOREX CEILING PANELS). SAMPLED BY OHE IN 2020 (PROJECT #25948). NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND (TAN) | BULKHEAD AT CEILING, NORTH WALL | UNKNOWN | 23595185 A01-2A | 1 | CHRYSOTILE | YES | GOOD | B | NON-FRIABLE | | BULKHEAD IS LOCATED ABOVE BLACKBOARD AND WINDOWS ON EXTERIOR WALL. SAMPLED BY WSP IN 2023 (PROJECT #23595185).NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND (BEIGE), MOSTLY NEW (2019) | EAST AND WEST WALLS | UNKNOWN | 17779 S04A-B | 0.5 | CHRYSOTILE | YES | GOOD | B | NON-FRIABLE | | MAJORITY OF DRYWALL ON EAST AND WEST WALLS (BETWEEN EXTERIOR WALL AND BULKHEAD ADJACENT TO B340A/B) WAS REMOVED ON MARCH 14-16, 2019 UP TO A HEIGHT OF 9' (MAPLE PROJECT #17779). SOME ASBESTOS-CONTAINING DRYWALL REMAINS >9' (ABOVE UPPER CONDUIT), AND BEHIND PODIUM AND FIRE PULL STATION. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND (WHITE) | NORTH WALL | | 17779 S01A-C; 23595185 A02A-C | | ND | NO | | | | | WALL IS LOCATED BEHIND BLACKBOARD AND BETWEEN WINDOWS ON EXTERIOR WALL. SAMPLED BY MAPLE IN 2019 (PROJECT #17779) AND WSP IN 2023 (PROJECT #23595185). | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND (WHITE AND OFF-WHITE) | BULKHEAD ADJACENT TO B340A/B | | 17779 S02A-C, S03A-C | | ND | NO | | | | | BULKHEAD WAS SAMPLED AT BOTTOM (S02A-C) AND TOP (S03A-C) BY MAPLE IN 2019 (PROJECT #17779). | N/A |
| | | VINYL SHEET FLOORING | GREY-BLUE VINYL SHEET FLOORING | FLOOR | | 17779 S05A-C; 23595185 A03A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17779) AND WSP IN 2023 (PROJECT #23595185). | N/A |
| | | FLOOR MASTIC | BLACK AND YELLOW MASTIC | FLOOR UNDER VSF, ALONG SOUTH SIDE OF ROOM | | 18179 S01A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #18179). | N/A |
| | | FLOOR MASTIC | BLACK AND BROWN MASTIC | FLOOR UNDER VSF | | 18098 S01A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #18098, EMC LAB REPORT #A50688). | N/A |
| | | FLOOR MASTIC | BROWN MASTIC ASSOCIATED WITH VSF | FLOOR UNDER VSF | | 17779 S05A-C; 23595185 A03A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17779) AND WSP IN 2023 (PROJECT #23595185). | N/A |
| | | GRAY LEVELLER MATERIAL | GRAY LEVELLER MATERIAL | FLOOR UNDER VSF | | 23595185 A03B-C, A03-2A | | ND | NO | | | | | SAMPLED BY WSP IN 2023 (PROJECT #23595185). | N/A |
| | | VINYL FLOOR TILE | RED VINYL FLOOR TILE (REMNANTS) | FLOOR UNDER VSF | | 17779 S06A-C | 1 | CHRYSOTILE | YES | GOOD | C | NON-FRIABLE | | SAMPLED BY MAPLE IN 2019 (PROJECT #17779). SEE PHOTOS OF FLOOR TILE IN CURMANN REPORT #19046-1 FROM AUG. 2019 PARTIAL FLOOR REPLACEMENT PROJECT. REMNANTS OF ACM FLOOR TILE ARE EMBEDDED IN CONCRETE TOPPING. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| | | FLOOR MASTIC AND FIBROUS MATERIAL | YELLOW MASTIC AND BEIGE FIBROUS MATERIAL ASSOCIATED WITH VFT | FLOOR UNDER VFT | | 17779 S06A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17779). | N/A |
| | | CAULKING | WHITE / GREY CAULKING | WINDOWS | | 18406 S01A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #18406, EMC LAB REPORT #A54033). | N/A |
| CAULKING | BLACK CAULKING | WINDOWS | | 18406 S02A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #18406, EMC LAB REPORT #A54033). | N/A | | |
| B340A | STORAGE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL (PERIMETER -OLD) | 1000 SQ. FT | 16737-S01 & R-SA66 | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2017 (PROJECT #16737). TO VIEW PROJECT SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 | |
| | | NEW DRYWALL WALLS | | WALL (PARTITION - NEW) | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. | N/A | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|----------------|---------------------------------|--|------------------|-------------|-----------------|-------|------------|------------------------|-----------|---------------|-------------|---|---|-----|
| B342 | ELECTRICAL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | 25622-032-01A-C | 1 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | SAMPLED BY OHE IN 2023 (OHE PROJECT #25622-032). THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 150 SQ. FT | 25622-032-01A-C | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY OHE IN 2023 (OHE PROJECT #25622-032). | 4 | |
| B344E | ELEVATOR | NO SUSPECT ACM OBSERVED | | | | | | | | | | | | N/A | |
| B344K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 5 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 100 SQ. FT | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 | |
| B344S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 596 SQ. FT. | 25622-024-4A-C | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY OHE IN 2022 (OHE PROJECT #25622-024). | 4 | |
| B344V | VESTIBULE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 430 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B346 | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | UNKNOWN | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | YELLOW & BLACK MASTIC | MASTIC BELOW CARPET | ENTRANCE OF ROOM | | 17972 S02A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | VINYL FLOOR TILE | 12"X12" RED FLOOR TILES | FLOOR | | | | | NO | | | | | REMOVED ACCORDING TO UTSC NOTICE OF PROJECT - JULY 2020. | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | | | | | | NO | | | | | REMOVED ACCORDING TO UTSC NOTICE OF PROJECT - JULY 2020. | N/A |
| B346A | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346B | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346C | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346D | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346E | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346F | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346G | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346H | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346J | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B346L | TESTING CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B347 | WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B349 | WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 30 SQ. FT | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B355 | CLASSROOM | VINYL FLOOR TILE | 12"X12" RED FLOOR TILES | FLOOR | | | | | | | | | ACM FLOOR TILES WERE REMOVED IN 2020 (MAPLE PROJECT #17972). | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | | | | | | | | | | REMOVED ACCORDING TO UTSC NOTICE OF PROJECT - JULY 2020. | N/A | |
| | | BLACK MASTIC | MASTIC ASSOCIATED WITH VINYL FLOOR TILE BELOW CARPET | FLOOR | | 17972 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | CAULKING | AROUND BLACKBOARDS | WALLS | | 17972 S03A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17972). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building compound.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|--------------------------|---------------------------------|--|-----------------------------|----------------------|----------------------|-------|------------|------------------------|-----------|---------------|-------------|--|--|-----|
| B355C | TESTING CENTRE | REFER TO B355 | | | | | | | | | | | ALL ACM REMOVED IN 2020. REFER TO B355 FOR PROJECT DETAILS. | N/A | |
| B355D | TESTING CENTRE VESTIBULE | VINYL FLOOR TILE | 12"X12" RED FLOOR TILES | FLOOR | | | | | | | | | ACM FLOOR TILES WERE REMOVED IN 2020 (MAPLE PROJECT #17972). | N/A | |
| | | FLOOR MASTIC | FLOOR MASTIC (BLACK, YELLOW & BLACK) | FLOOR BELOW CARPET | | 17972 S01A-C, S02A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17972). | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | | 17972 S04A-C | | ND | NO | | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17972). | N/A |
| B357K | CORRIDOR | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B358K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 88 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 25980-2A & 3A | 0.5-1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY OHE IN 2020 (PROJECT #25980). | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. + 2 L. FT. | 25980-2A & 3A | 0.5-1 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B359 | CLASSROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 400 SQ. FT. | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | VINYL FLOOR TILE | 12"X12" RED FLOOR TILES | FLOOR BELOW CARPET | 1165 SQ. FT. | R-SA65 | 5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | CARPET OBSERVED THROUGHOUT THE ROOM. ASBESTOS FLOOR TILES MAY STILL BE PRESENT BENEATH THE CARPET. | 4 | |
| B360 | CLASSROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 400 SQ. FT. | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B361 | CLASSROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT. | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT. | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B363 | CLASSROOM | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT. | R-SA21 (A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B366 | STORAGE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | SMALL ADJACENT STORAGE ROOM | 5 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | LOCATED AT ENTRANCE TO THE ROOM | 4 | |
| B368 | ELECTRICAL ROOM | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A | |
| B369K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 9 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT. | SA21(A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B369S | STAIRWELL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | | | | | | | A | | | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1500 SQ. FT. | R-SA21(A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B370 | ART GALLERY | NO SUSPECT ACM OBSERVED | NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS | | | | | | NO | | | | | N/A | |
| B370A | ART GALLERY | NO SUSPECT ACM OBSERVED | NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS | | | | | | NO | | | | | N/A | |
| B370K | ART GALLERY | NO SUSPECT ACM OBSERVED | NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS | | | | | | NO | | | | | N/A | |
| B371 | ART GALLERY | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 17167 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17167). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| B373 | ELECTRICAL | NO SUSPECT ACM OBSERVED | NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS | | | | | | NO | | | | | N/A | |
| B375 | ART GALLERY | NO SUSPECT ACM OBSERVED | NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS | | | | | | NO | | | | | N/A | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|--|---------------------------------|--|-------------------|----------------------|----------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B380 | RALPH CAMPBELL LOUNGE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 17323 S01-S03 | | ND | NO | | | | SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17323). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 10 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A/B | FRIABLE | | 4 |
| B380A | ELECTRICAL | NEW DRYWALL WALLS | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | NEW DRYWALL WALLS | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B380V | VESTIBULE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 5 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A/B | FRIABLE | | 4 |
| B390 | BOOK STORE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 65 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A/B | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 4 L. FT. + 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | NEW VINYL FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B390A | BOOK STORE - STORAGE ROOM BY TURNSTILES | VINYL FLOOR TILE | 12"X12" RED FLOOR TILES | FLOOR | 63 SQ. FT. | R-SA65 | 5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING | 24 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 227 SQ. FT. | R-SA21(A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | AT PIPE PENETRATE | 3 SQ.FT. | R-SA21(A-C)-08 | 1.75 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B390B | BOOK STORE - STORAGE ROOM BESIDE EXTERIOR DOOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW VINYL FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 1 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A/B | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 L. FT. + 3 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B390C | BOOK STORE - STORAGE ROOM BY CHECKOUT | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW VINYL FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 4 L. FT. + 4 SQ. FT. | R-SA21(A-C)-08 | 1.75 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 20 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A/B | FRIABLE | | 4 |
| B390D | BOOK STORE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY MAPLE AND WAS FOUND NOT TO CONTAIN ASBESTOS, HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. | 4 |
| | | NEW VINYL FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B390E | ELEVATOR | NO SUSPECT ACM OBSERVED | NO SUSPECT ACM OBSERVED - NEW BUILDING MATERIALS | | | | | | | | | | | N/A |
| B390V | BOOK STORE - VESTIBULE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 150 SQ. FT. | R-SA21(A-C)-08 | 1.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|------------------|---------------------------------|------------------------------|-----------------------------|--------------|----------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B400 | OFFICE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 4 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 420 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | AT PIPE PENETRATE | 2 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B400E | ELEVATOR | NO SUSPECT ACM OBSERVED | | | | | | | | | | | | N/A |
| B400K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | WINDOW CAULKING | BLACK CAULKING | INTERIOR CAULKING | | 17892 S05 | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | WINDOW CAULKING | GREY CAULKING | INTERIOR CAULKING | | 17892 S06 | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | WINDOW CAULKING | DARK AND LIGHT GREY CAULKING | EXTERIOR CAULKING | | 17892 S07 | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17892). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 18 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | 1 FITTING REPAIRED IN 2014. | 4 |
| B400S | STAIRCASE | PARGING CEMENT ON PIPE FITTINGS | ELBOWS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 600 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B405 | JANITOR'S CLOSET | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 2 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| B428K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 300 SQ. FT. | SA23(A-G)-08 | 2.25 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 25 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CORRIDOR WALL BY THE STAIRS | UNKNOWN | S01B | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18521). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B428S | STAIRWELL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1500 SQ. FT. | R-SA23(A-G)-08 | 2.25 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | R-SA23(A-G)-08 | 2.25 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CORRIDOR WALL BY THE STAIRS | | | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18521). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| B430 | REFER TO B428K | | | | | | | | | | | | | N/A |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|----------------------|---------------------------------|------------------------|------------------|--------------|----------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B430K | CORRIDOR | NEW FIBREGLASS INSULATION | FITTINGS | GENERAL ROOM | | | | | NO | | | | PREVIOUSLY IDENTIFIED ASBESTOS-CONTAINING PARGING CEMENT OBSERVED TO BE REPLACED WITH FIBERGLASS INSULATION AND COVERED IN PVC | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 2000 SQ. FT. | SA23(A-G)-08 | 2.25 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 3 SQ. FT. | SA23(A-G)-08 | 2.25 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B432 | 4TH FLOOR STUDY AREA | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILINGS / WALLS | UNKNOWN | | | SUSPECT | NO | GOOD | A | NON-FRIABLE | SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01. | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. THE SPACE WAS RENOVATED IN 2011. REFER TO PROJECT DCM2011-01. | N/A |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. THE SPACE WAS RENOVATED IN 2011. REFER TO PROJECT DCM2011-01. | N/A |
| B442 | 4TH FLOOR STUDY AREA | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILINGS / WALLS | UNKNOWN | | | SUSPECT | NO | GOOD | A | NON-FRIABLE | SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01. | N/A |
| B444 | 4TH FLOOR STUDY AREA | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILINGS / WALLS | UNKNOWN | | | SUSPECT | NO | GOOD | A | NON-FRIABLE | SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01. | N/A |
| B445 | CUSTODIAL ROOM | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 2 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |
| B446 | 4TH FLOOR STUDY AREA | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILINGS / WALLS | UNKNOWN | | | SUSPECT | NO | GOOD | A | NON-FRIABLE | SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01. | N/A |
| B447 | BELL ROOM | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B448 | 4TH FLOOR STUDY AREA | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILINGS / WALLS | UNKNOWN | | | SUSPECT | NO | GOOD | A | NON-FRIABLE | SPACE WAS RENOVATED IN 2011, HOWEVER RESIDUAL ASBESTOS DJC MAY REMAIN. REFER TO PROJECT DCM2011-01. | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 3 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| B450 | ELECTRICAL ROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING / WALLS | 150 SQ. FT. | R-SA24(A-C)-08 | 1.25 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 6 SQ. FT. | R-SA24(A-C)-08 | 1.25 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | PARGING CEMENT ON PIPE FITTINGS | ELBOWS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |
| B450E | ELEVATOR | NO SUSPECT ACM OBSERVED | | | | | | | | | | | | N/A |
| B450K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 200 SQ. FT. | SA23(A-G)-08 | 2.25 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | | | | | | | | | | REMOVED IN 2014 | 4 |
| B450S | STAIRWELL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 600 SQ. FT. | 25622-024-5A-C | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY OHE IN 2022 (OHE PROJECT #25622-032). | 4 |
| B450V | VESTIBULE | NEW CARPET FLOOR | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | 35 | R-SA24(A-C)-08 | 1.25 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|------------------|---------------------------------|------------------------|---------------|----------------------|-----------------------------|----------|------------|------------------------|-----------|---------------|-------------|---|-----------------------------------|-----|
| B452 | STUDY AREA | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT. | R-SA68 & R-SA24(A-C)-08 | 0.5-1.25 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B453 | MEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | 4 L. FT. | R-SA96 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 200 SQ. FT. | R-SA96 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B455 | WOMEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 200 SQ. FT. | R-SA96 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B457 | STUDY AREA | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 25-30 | R-SA70 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 | |
| B460K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 500 SQ. FT. | SA23(A-G)-08 & 18521 S01A | | | SUSPECT | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18521). DESPITE SAMPLE RESULT, FURTHER SAMPLING IS RECOMMENDED. | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | REMOVED | | | | | | NO | | | | OBSERVED TO BE REMOVED. ROOM WAS RECENTLY RENOVATED | N/A | |
| B466 | COMPUTER LAB | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT. | R-SA96 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 2 L. FT. + 2 SQ. FT. | R-SA96 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 25 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 | |
| B469 | COMPUTER ROOM | NEW DRYWALL WALLS | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 40-50 | R-SA70 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 | |
| B469K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 17016 S01A-C & 18521 S01C,D | | ND | NO | | | | SAMPLED BY MAPLE IN 2018 AND 2020 (MAPLE PROJECT #17016 & 18521 RESPECTIVELY). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 10 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | AREA/ROOM RECENTLY RENOVATED | 4 | |
| B471 | COMPUTER LAB | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 17167 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17167). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW DRYWALL WALLS | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B472 | COMPUTER OFFICE | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 35 | R-SA70 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | AREA/ROOM RECENTLY RENOVATED | 4 | |
| B473 | COMPUTER LAB | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW DRYWALL WALLS | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B476 | DATA CENTRE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | DJC01A-C & DL-01 | | ND | NO | | | | SAMPLED BY WSP GOLDER IN 2022 (GOLDER PROJECT #22532220). NOT SUSPECTED TO CONTAIN ASBESTOS. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. | N/A | |
| | | NEW VINYL FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | AREA/ROOM RECENTLY RENOVATED | 4 | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|-----------------------------------|---|---|---------------------------------------|--------------|---------------------------|-------|------------|------------------------|-----------|---------------|-------------|--|---|-----|
| B478 | ELECTRICAL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL/CEILING | 150 SQ. FT. | R-SA24(A-C)-08 | 1.25 | CHRYSOTILE | YES | GOOD | B | NON-FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 6 SQ. FT. | R-SA24(A-C)-08 | 1.25 | CHRYSOTILE | YES | POOR | B | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 | |
| | | CAULKING | GREY CAULKING | EXTERIOR CAULKING (ON ROOF) | | 27295-4A-C | | ND | NO | | | | | SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 18 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | AREA/ROOM RECENTLY RENOVATED | 4 | |
| B478K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT. | 25622-024-6A-C | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | AREA/ROOM RECENTLY RENOVATED | 4 | |
| B478S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 600 SQ. FT. | R-SA66 | 0.25 | CHRYSOTILE | SUSPECT | GOOD | A | NON-FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B480 | DATA CENTRE | NEW FIBERGLASS PIPE INSULATION | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW CERAMIC FLOOR TILES | | | | | | | | NO | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW DRYWALL WALLS | | | | | | | | NO | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | CAULKING | BLACK CAULKING | EXTERIOR (ROOF) PIPING FOR HVAC UNIT | | 27295-3B,C | | | | NO | | | | SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | NEW FIBERGLASS PIPE INSULATION | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B480A | DATA CENTRE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW CERAMIC FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1000 SQ. FT. | R-SA97 | 0.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | NEW DRYWALL WALLS ARE ALSO LIKELY PRESENT. PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED. MATERIAL HAS BEEN PREVIOUSLY SAMPLED BY MAPLE AND WAS FOUND NOT TO CONTAIN ASBESTOS. HOWEVER ADDITIONAL SAMPLING IS RECOMMENDED. | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | S01A-4C | | ND | NO | | | | SAMPLED BY MAPLE IN 2020 (OHE PROJECT #18629). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| B480K | CORRIDOR (RENOVATED IN 2009-2010) | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | NORTH WALL AND WEST WALL | | 27295-2A-C | | ND | NO | | | | SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | CAULKING | BLACK CAULKING | EXTERIOR, BEHIND THE DOOR AND ON ROOF | | 27295-3A, D, E, F & G | | ND | NO | | | | SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | VINYL FLOOR TILES | 12"X12" BEIGE WITH GREY AND BROWN STREAKS | FLOOR | | 27295-5A-C | | ND | NO | | | | SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | MASTIC ASSOCIATED WITH TILES | BLACK MASTIC | FLOOR | | 27295-5A-C | | ND | NO | | | | SAMPLED BY OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW FIBERGLASS PIPE AND DUCT INSULATION | | | | | | | | NO | | | | RENOVATED IN 2009-2010 | N/A |
| | | NEW CERAMIC FLOOR TILES | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B480V | VESTIBULE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 27295-1A-C & 18629 S05A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2020 (OHE PROJECT #18629) AND OHE IN 2021 (OHE PROJECT #27295). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| B481 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | NORTH, SOUTH & WEST WALL | | 18104 S01A-C & DJC01-06 | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18104). ALSO SAMPLED BY GOLDER IN 2021 (GOLDER PROJECT #21507744). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B481A | ELECTRICAL | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|---------------------|---------------------------------|--------------------------|------------------------|--------------|----------------|-------|------------|------------------------|-----------|---------------|-------------|---|---|-----|
| B482 | COMPUTER LAB | DRYWALL | GYPSUM BOARD & PAPER | WALL | | A01a-c | | ND | NO | | | | SAMPLED BY WSP IN 2023 (WSP PROJECT #23595185). SAMPLE TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | NORTH, WALL RECEPTACLE | 700 SQ. FT. | S02B | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18442). SAMPLE TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | N/A |
| B483 | ALL GENDER WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT. | R-SA97 | 0.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B485 | ALL GENDER WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT. | R-SA97 | 0.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B486 | STORAGE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 3 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| B487 | COMPUTING HELP DESK | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 14 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | AREA/ROOM RECENTLY RENOVATED. INCLUDES FORMED ROOM B488 | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1300 SQ. FT. | S01E | 1 | CHRYSOTILE | YES | GOOD | 4 | NON-FRIABLE | SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18521). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | NEW VINYL SHEET FLOORING | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B490 | COMPUTER LAB | PARGING CEMENT ON PIPE FITTINGS | ELBOWS AND FITTINGS | CEILING | 20 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT. | R-SA97 | 0.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 2 L. FT. | R-SA97 | 0.75 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B494 | COMPUTER LAB | PARGING CEMENT ON PIPE FITTINGS | ELBOWS AND FITTINGS | CEILING | 20 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT. | R-SA97 | 0.75 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| B498 | COMPUTER LAB | SPRAYED FIREPROOFING | SPRAY APPLIED INSULATION | CEILING SPACE | | 17994 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 1 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 25622-024-7A-C | | ND | NO | | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #25622-024) | N/A |
| B498A | OFFICE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 6 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| B498C | STORAGE | SPRAY APPLIED FIREPROOFING | SPRAY APPLIED INSULATION | CEILING SPACE | | 17994 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| B498D | DATA CLOSET | SPRAY APPLIED FIREPROOFING | SPRAY APPLIED INSULATION | CEILING SPACE | | 17994 S01A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 5 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|------------------|------------------------------------|--------------------------------|---------------|--------------|-----------------|-------|------------|------------------------|-----------|---------------|-------------|---|-----------------|
| 5TH FLOOR | OFFICE AREAS | NEW DRYWALL JOINT COMPOUND & WALLS | DRYWALL JOINT COMPOUND | WALLS | 7500 SQ. FT. | N/A | | | NO | | | | THE MAJORITY OF THE 5TH FLOOR OFFICE AREAS WERE RENOVATED IN EARLY 2012. SEVERAL AREAS/OFFICE ROOMS WERE RENOVATED OR CONSTRUCTED WHERE NEW, NON-ASBESTOS DRYWALL JOINT COMPOUND WAS USED. REFER TO DRAWING A2 OF THE 2015 GOLDER REPORT FOR FURTHER DETAIL REGARDING LOCATIONS OF BOTH NEW, AS WELL AS ORIGINAL, ASBESTOS-CONTAINING DRYWALL JOINT COMPOUND EXIST. | N/A |
| B500 | OFFICE | NEW VINYL SHEET FLOORING | NEW 2009 | FLOOR | | | | | NO | | | | VINYL SHEET FLOORING IS NOW OVERLAIN BY 2'X2' CARPET TILE FLOORING. THIS RENOVATION REPORTEDLY TOOK PLACE EARLY IN 2012. | N/A |
| B500E | ELEVATOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B500K | CORRIDOR | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B500K | CORRIDOR | NEW VINYL SHEET FLOORING | NEW 2009 | FLOOR | | | | | NO | | | | | N/A |
| B500K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 678 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B500S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALLS | 600 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B500S | STAIRWELL | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B502 | OFFICE | VINYL FLOOR TILE | 12"X12" LIGHT BROWN FLOOR TILE | FLOOR | 150 SQ. FT. | R-SA67 | 5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | CONCEALED WITH CARPETING | 4 |
| B502 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B502 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B502 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B503 | OFFICE | NEW CARPET FLOOR | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B503 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B503 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B504 | OFFICE | VINYL FLOOR TILE | 12"X12" LIGHT BROWN FLOOR TILE | FLOOR | 150 SQ. FT. | R-SA67 | 5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | CONCEALED WITH CARPETING | 4 |
| B504 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B504 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B505 | KITCHENETTE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL OF ASBESTOS-CONTAINING DRYWALL IN SEPTEMBER 2011. | 4 |
| B505 | KITCHENETTE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 2 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B505 | KITCHENETTE | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B505 | KITCHENETTE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B505 | KITCHENETTE | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B506 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B506 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B507 | WOMEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING SPACE | 90 SQ. FT. | R-SA68 & S06A-B | 1-2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2020 (PROJECT #18765) | 4 |
| B508 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B509 | MEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING SPACE | 90 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B510 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B510K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 48 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | A | FRIABLE | | 4 |
| B510K | CORRIDOR | NEW VINYL SHEET FLOORING | NEW 2009 | FLOOR | | | | | NO | | | | VINYL SHEET FLOORING IS NOW OVERLAIN BY 2'X2' CARPET TILE FLOORING. THIS RENOVATION REPORTEDLY TOOK PLACE EARLY IN 2012. | N/A |
| B510K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1275 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B511 | BELL ROOM | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |

Level of Accessibility

- A - Accessible and exposed to all occupants of the building.
- B - Accessible only to maintenance staff and exposed to view without moving a building component.
- C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

- 1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
- 2 - Perform asbestos removal/repair for compliance with the regulations.
- 3 - Type 2 asbestos procedures required to enter area.
- 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
- N/A - Not applicable.

Definitions

- ACM - Asbestos-Containing Materials
- SA - Sample representative
- R-SA - Sample referenced to a visually similar homogeneous sample material.
- ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|-----------|---------------------------------|------------------------|--------------|-------------|---------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B512 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT | R-SA68 & S07C | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2020 (PROJECT #18765) | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT | R-SA68 & S07C | 2 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B513 | OFFICE | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| B513A | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| | | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B514 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1332 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B515 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 720 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B516 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 675 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | REMOVED | | | | | | NO | | | | ACM FITTINGS REMOVED IN 2012 | N/A |
| B517 | OFFICE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 3 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | NOT OBSERVED. MAYBE LOCATED WITHIN RADIATOR UNITS. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 450 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| B518 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | CARPET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B519 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 - ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | < 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | CARPET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B519A | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 - ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | < 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B519K | CORRIDOR | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 800 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | S08A-C | | | ND | NO | | | SAMPLED BY MAPLE IN 2020 (PROJECT #18765) | N/A |
| B519S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 750 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B520 | OFFICE | PARGING CEMENT ON PIPE FITTINGS | REMOVED | | | | | | NO | | | | OBSERVED TO BE REMOVED | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|------------------|---------------------------------|------------------------|-------------------------------|------------|---------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B521 | OFFICE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 25 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B/C | FRIABLE | | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B522 | MEN'S WASHROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 456 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | 100 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| B523 | WOMEN'S WASHROOM | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | CEILING | 100 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| B524 | ELECTRICAL | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B525 | CLEANERS | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B526 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B526A | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| | | | | | | | | | | | | | | |
| B526B | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| B526C | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 2 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 2 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | MANY FITTINGS WERE OBSERVED TO BE REMOVED | 4 |
| B526D | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| B526E | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 2 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B526K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011 | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE (BY ROOM B526C) | 24 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 |
| B527 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 340 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 4 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | ADDITIONAL SAMPLING IS RECOMMENDED | 4 |
| B528 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| B529 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 480 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | PARTIAL REMOVAL IN SEPTEMBER 2011. NOT ACCESSIBLE DURING THE 2023 REASSESSMENT. | 4 |
| B530 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B530K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 480 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B534 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 400 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|--------------|---------------------------------|------------------------|---------------|-------------|---------------|-------|------------|------------------------|-----------|---------------|-------------|---|-----------------|
| B536 | OFFICE | PARGING CEMENT ON PIPE FITTINGS | REMOVED | | | | | | NO | | | | OBSERVED TO BE REMOVED | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 300 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B538 | ELECTRICAL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 125 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B538E | ELEVATOR | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B538K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 400 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 1 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 |
| B538S | STAIRWELL | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | NEW DRYWALL WALLS OBSERVED | N/A |
| B538V | VESTIBULE | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B540 | BOARDROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B544 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B546 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B548 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B550 | OFFICE | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B551 | WAITING AREA | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | | | | | | | | SAMPLED BY MAPLE IN 2017 (PROJECT #17005). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | 2 SF OF MOULD-IMPACTED DRYWALL REMOVED IN 2018 (MAPLE PROJECT #17753). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| B560 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B560K | CORRIDOR | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 60 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B/C | FRIABLE | 2 FITTINGS REPAIRED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1000 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B562 | OFFICE | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B563 | KITCHENETTE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B564 | OFFICE | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B566 | OFFICE | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B570 | OFFICE | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | MONITOR MINOR CRACKS | 4 |
| B570 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required |
|-------------|--------------------|-----------------------------------|------------------------|--------------|------------|---------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------|
| B572 | OFFICE | NEW CARPET FLOOR | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B573 | COPY ROOM / OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 2 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| B574 | OFFICE | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | MONITOR MINOR CRACKS | 4 |
| B575 | BOARDROOM | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 450 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW 2'X2' GREEN VINYL FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B576 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 250 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | MONITOR MINOR CRACKS | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B578 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 200 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B580 | ELECTRICAL | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 8 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B/C | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 150 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | B | NON-FRIABLE | | 4 |
| B580K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | | | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B/C | FRIABLE | | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 330 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B580S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 600 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B584 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW CARPET FLOOR | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B586 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 6 L. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 |
| | | NEW CARPET FLOOR | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B587 | CLOSET | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | | N/A |
| B588 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW CARPET FLOOR | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B590 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| B590K | CORRIDOR | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | GENERAL ROOM | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | LOCATED ABOVE THE DOOR TO ROOM B592. 6 FITTINGS AT PARTITION WALL REMOVED IN 2019 (MAPLE PROJECT #17974). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B592 | OFFICE | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 |
| B593 | OFFICE | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 460 SQ. FT | 17634 S01A-E | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2018 (MAPLE PROJECT #17634). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|----------------|-------------------------|---------------------------------|------------------------|-----------------------------------|-------------|-------------------|-------|------------|------------------------|-----------|---------------|-------------|--|-----------------------------------|-----|
| B594 | OFFICE | NEW 2'X2' CARPET FLOOR TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 324 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 6 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | POOR | A | NON-FRIABLE | THE DAMAGED ASBESTOS-CONTAINING DRYWALL FINISH SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05. | 2 | |
| B595 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL (WEST) | 300 SQ. FT. | R-SA68 & 27641-3A | 0.5-1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | WEST WALL SAMPLED BY OHE IN 2022 (PROJECT #27641). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL (NORTH AND EAST) | | 27641-2A-C | | ND | NO | | | | NORTH AND EAST DRYWALL WALLS ARE NEW. ABATED IN 2019 (MAPLE PROJECT #17974). | N/A | |
| | | CAULKING | BLACK | WINDOW | | 27641-1A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (PROJECT #27641). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | MASTIC | YELLOW | BASEBOARD | | 27641-4A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (PROJECT #27641). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X2' CARPET FLOOR TILES | | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 7 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| B596 | OFFICE | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 1 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | C | FRIABLE | | 4 | |
| | | NEW VINYL SHEET FLOORING | | FLOOR, CONCEALED BELOW CARPET | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B598 | MECHANICAL | NO SUSPECT ACM OBSERVED | | | | | | | NO | | | | N/A | | |
| | | GASKET | BROWN | PIPE | | 27540-1A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (PROJECT #27540). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | MECHANICAL SYSTEM INSULATION | PIPE INSULATION | AHU 1 ON THE ROOF | | 27186-1A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (PROJECT #27186). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| 5TH FLOOR ROOF | ROOFTOP MECHANICAL ROOM | CAULKING | DARK GREY | VENT ALONG WALL | | 28244-01A-C | | | NO | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). ABATED BY CURMANN IN 2022 (CURMANN PROJECT #22078) | N/A | |
| | | CAULKING | BLACK | METAL PANEL BELOW VENT | | 28244-02A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | MASTIC | DARK GREY | DUCT WORK | | 28244-03A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | MASTIC | GREY | DUCT WORK | | 28244-04A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | MASTIC | LIGHT GREY | DUCT WORK | | 28244-05A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | CAULKING | GREY-BLACK | BOTTOM OF SOUTHEAST CONCRETE WALL | | 28244-06A-C | | ND | NO | | | | SAMPLED BY OHE IN 2022 (OHE PROJECT #28244). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| B610 | AHU ON ROOF | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 6 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 | |
| B610S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 400 SQ. FT. | R-SA68 | 0.5 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |
| B620 | AHU ON ROOF | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 9 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 | |
| B620S | STAIRWELL | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 400 SQ. FT. | 16556-S01 | 1 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | SAMPLED BY MAPLE IN 2017 (PROJECT #16556). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | 4 | |
| | | NEW VINYL SHEET FLOORING | | | | | | | NO | | | | NOT SUSPECTED TO CONTAIN ASBESTOS | N/A | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
B - Accessible only to maintenance staff and exposed to view without moving a building component.
C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
2 - Perform asbestos removal/repair for compliance with the regulations.
3 - Type 2 asbestos procedures required to enter area.
4 - Regular inspection/surveillance of ACM for compliance with the regulations.
N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
SA - Sample representative
R-SA - Sample referenced to a visually similar homogeneous sample material.
ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|--|--------------------|-----------------------------------|-------------------------|---|-------------|--|-------|------------|------------------------|-----------|---------------|-------------|---|---------------------------|-----|
| ACADEMIC RESOURCE CENTRE (FORMERLY BLADEN WING) | | | | | | | | | | | | | | | |
| ARC/BV | HALLWAY | MASTIC | YELLOW MASTIC | FLOOR | | MAS01A-C | | ND | NO | | | | SAMPLED BY GOLDER IN 2022 (PROJECT #22532220(3000)). | N/A | |
| AC200 | IITS SERVICE DESK | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC200A | IITS STORAGE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC200V | VESTIBULE/CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 1000 SQ. FT | SA18 (A-C)-08 | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A |
| AC201 | IITS MEETING ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC201K | CORRIDOR | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | MAPLE SAMPLE No.: 17994 S03A-G and OHE SAMPLE No.: 26377-1A to 26377-1E. | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). SAMPLED BY OHE IN 2021 (PROJECT #26377). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A |
| AC201S | STAIRCASE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | | 26377-2A to 26377-2E | 2 | CHRYSOTILE | YES | GOOD | A | NON-FRIABLE | | 4 | |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 10 | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | | 4 | |
| AC202 | CLIENT SERVICES | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC203 | OFFICE | VINYL FLOOR TILE | 12"X12" GREY FLECK | FLOOR | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | VINYL FLOOR TILE | 12"X12" GREY FLECK | BLACK MASTIC ASSOCIATED WITH FLOOR TILE | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 150 SQ. FT | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | UNKNOWN | R-SA60 | 50-75 | CHRYSOTILE | SUSPECT | GOOD | B | FRIABLE | ALL PIPE FITTINGS PRESENT ABOVE CEILING ARE PAINTED BLACK AND ARE INACCESSIBLE. PARGING CEMENT MAY BE PRESENT ON PIPE FITTINGS THAT WERE NOT IDENTIFIED DURING THE 2019 ASSESSMENT. | 4 | |
| AC205 | MEETING ROOM | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 1 EACH | 28445-1A-C | 60 | CHRYSOTILE | YES | GOOD | B | FRIABLE | SAMPLED BY OHE IN 2023 (PROJECT #28445) | 4 | |
| AC205A | KITCHENETTE | VINYL SHEET FLOORING | DARK GREY SPECKLED | FLOOR | | 17994 S04A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 150 SQ. FT | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 10 EACH | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | PRESENT ABOVE CEILING AT WALL TO AC203 | 4 | |
| AC206K | CORRIDOR | VINYL FLOOR TILE | 12"X12" GREY FLECK | FLOOR | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | VINYL FLOOR TILE | 12"X12" GREY FLECK | BLACK MASTIC ASSOCIATED WITH FLOOR TILE | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 750 SQ. FT | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | 2 EACH | R-SA60 | 50-75 | CHRYSOTILE | YES | GOOD | B | FRIABLE | PRESENT ABOVE CEILING IN FRONT OF AC205A | 4 | |
| | | DUCT MASTIC | YELLOW-GREY DUCT MASTIC | DUCT WORK | | | | | SUSPECT | GOOD | C | NON-FRIABLE | MATERIAL NOT SAMPLED DURING THE 2019 ASSESSMENT | 4 | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|-------------------------------|-----------------------------------|------------------------|---|------------|---------------|--------------|------|------------------------|-----------|---------------|------------|--|---|-----|
| AC207 | OFFICE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 350 SQ. FT | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A | |
| | SMALL SECTION OF OFFICE SPACE | VINYL FLOOR TILE | 12"X12" GREY FLECK | FLOOR | | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | VINYL FLOOR TILE | 12"X12" GREY FLECK | BLACK MASTIC ASSOCIATED WITH FLOOR TILE | | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT | | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | BULKHEAD | 10 SQ. FT | | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' FLAT TEXTURED | CEILING | | | | | NO | | | | DATE STAMPED (09/19/2005) | N/A | |
| AC207A | OFFICE | VINYL FLOOR TILE | 12"X12" GREY FLECK | FLOOR | | | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | VINYL FLOOR TILE | 12"X12" GREY FLECK | BLACK MASTIC ASSOCIATED WITH FLOOR TILE | | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 500 SQ. FT | | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A |
| AC270 | STAFF LOUNGE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC270A | WASHROOM | DRYWALL | DRYWALL JOINT COMPOUND | WALL | | DJC03A-C | ND | ND | NO | | | | SAMPLED BY GOLDER IN 2021 (PROJECT #21482724). ORIGINAL FINISHES WERE RETAINED DURING LIBRARY PHASE 1 RENOVATION. REFER TO PROJECT DCM2019-10. | N/A | |
| AC270V | WASHROOM VESTIBULE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC271 | COPY ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC272 | OFFICE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC273 | OFFICE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC273A | STORAGE ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC274 | OFFICE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC275 | OFFICE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC275K | CORRIDOR | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC276 | OFFICE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC277 | STUDY ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC278 | STUDY ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC279 | STUDY ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC280 | LIBRARY STACKS | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC280A | LIBRARY LOUNGE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC281 | STUDY ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC282 | STUDY ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC283 | STUDY ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|--------------------|-----------------------------------|------------------------|---|-------------|---------------|-------|------------|------------------------|-----------|---------------|------------|---|---|-----|
| AC284 | SERVER ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC284A | TELECOM ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC285 | STUDY ROOM | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC286 | ONE BUTTON STUDIO | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC287 | LIBRARY RESERVE | NOT SUSPECTED TO CONTAIN ASBESTOS | | | | | | | | | | | FULLY RENOVATED IN 2023 (GOLDER PROJECT #21482724). REFER TO PROJECT DCM2019-10. | N/A | |
| AC290 | OPEN LIBRARY SPACE | VINYL FLOOR TILE | 12"X12" GREY FLECK | FLOOR | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | VINYL FLOOR TILE | 12"X12" GREY FLECK | BLACK MASTIC ASSOCIATED WITH FLOOR TILE | | 17994 S02A-C | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | BULKHEAD | 1000 SQ. FT | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 5000 SQ. FT | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' FLAT TEXTURED | CEILING | | | | | | NO | | | | DATE STAMPED (09/19/2005) | N/A |
| | | PARGING CEMENT ON PIPE FITTINGS | FITTINGS | CEILING SPACE | UNKNOWN | R-SA60 | 50-75 | CHRYSOTILE | SUSPECT | GOOD | B | FRIABLE | | ALL PIPE FITTINGS PRESENT ABOVE CEILING ARE PAINTED BLACK AND ARE INACCESSIBLE. PARGING CEMENT MAY BE PRESENT ON PIPE FITTINGS THAT WERE NOT IDENTIFIED DURING THE 2021 ASSESSMENT. | 4 |
| AC290S | STAIRCASE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 100 SQ. FT | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A | |
| AC290T | STAIRCASE | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | WALL | 100 SQ. FT | 17994 S03A-G | | ND | NO | | | | SAMPLED BY MAPLE IN 2019 (PROJECT #17994). TO VIEW PROJECT-SPECIFIC REPORTS, SEE FACILITIES AND/OR HEALTH & SAFETY. | N/A | |
| | | NEW 2'X4' LAY-IN CEILING TILES | 2'X4' TEXTURED PINHOLE | CEILING | | | | | NO | | | | DATE STAMPED (05/20/2003) | N/A | |
| AC390A | IITS | REFER TO AC390M | | | | | | | | | | | REFER TO AC390M | N/A | |
| AC390B | IITS | REFER TO AC390M | | | | | | | | | | | REFER TO AC390M | N/A | |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected

| Room Number | Area | Material | Description | Location | Qty/Unit | Sample Number | % | Type | ACM (Yes, No, Suspect) | Condition | Accessibility | Friability | Comments | Action Required | |
|-------------|------------------|------------------------|--------------------------------------|----------------------------------|----------|---------------|-------|------------|------------------------|-----------|---------------|-------------|---|--|-----|
| AC390M | IITS - MEZZANINE | CEILING PANELS | SIPOREX CEILING PANELS | CEILING | -- | -- | -- | -- | | | | | NOT SUSPECTED TO CONTAIN ASBESTOS. | N/A | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND (BEIGE / TAN) | BEAM ENCLOSURES ON CEILING | UNKNOWN | DJC10A-E | 45293 | CHRYBOTILE | YES | GOOD | B | NON-FRIABLE | ASBESTOS-CONTAINING DJC IS PRESENT ON BEAM ENCLOSURES (BENEATH SIPOREX CEILING PANELS). SAMPLED BY WSP IN 2022 (PROJECT #22572864). | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND (BEIGE) | EXTERIOR WALL | UNKNOWN | DJC-05A-C | 1 | CHRYBOTILE | YES | GOOD | B | NON-FRIABLE | ALL DRYWALL BETWEEN THE FLOOR AND THE TOP OF EXTERIOR WINDOWS IS NON-ASBESTOS (INSTALLED IN 2024). ASBESTOS-CONTAINING DJC IS STILL PRESENT ON EXTERIOR WALL BETWEEN THE CEILING AND THE TOP OF THE EXTERIOR WINDOWS. SAMPLED BY WSP IN 2021 (PROJECT #21482724). | 4 | |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | UPPER WALL (SOUTH) | UNKNOWN | | | | | SUSPECT | GOOD | B | NON-FRIABLE | INACCESSIBLE UPPER DRYWALL FINISHES (DIRECTLY OPPOSITE EXTERIOR WINDOWS ON MEZZANINE AC390M) SHOULD BE TREATED AS SUSPECT ACM. ADDITIONAL SAMPLING IS RECOMMENDED PRIOR TO REMOVAL OR REPAIRS. | 4 |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND (WHITE) | INTERIOR WALLS AROUND DOORWAYS | | DJC12A-C | | | ND | NO | | | | SAMPLED BY WSP IN 2022 (PROJECT #22572864). | N/A |
| | | DRYWALL JOINT COMPOUND | DRYWALL JOINT COMPOUND | PERIMETER WALL-MOUNTED RAD UNITS | | | | | | | | | | ASBESTOS-CONTAINING DJC WAS REMOVED BEHIND PERIMETER WALL-MOUNTED RAD UNITS IN 2023 (WSP PROJECT #CA0006405.2779). | N/A |
| | | VINYL FLOOR TILE | 9X9 ORANGE VINYL FLOOR TILE | FLOOR | | | | | | | | | | REMOVED IN 2023 (WSP PROJECT #CA0006405.2779). | N/A |
| | | FLOOR MASTIC | BLACK MASTIC | FLOOR | | VFT02A-C | | | ND | NO | | | | SAMPLED BY WSP IN 2022 (PROJECT #22572864). NON-ASBESTOS FLOOR MASTIC WAS REMOVED IN 2023 ALONG WITH ASBESTOS-CONTAINING VFTS (WSP PROJECT #CA0006405.2779). | N/A |
| | | CARPET MASTIC | YELLOW MASTIC | FLOOR | | CM02A-C | | | ND | NO | | | | SAMPLED BY WSP IN 2022 (PROJECT #22572864). NON-ASBESTOS CARPET MASTIC WAS REMOVED IN 2023 ALONG WITH ASBESTOS-CONTAINING VFTS (WSP PROJECT #CA0006405.2779). | N/A |
| | | LEVELLING COMPOUND | LEVELLING COMPOUND | FLOOR | | | | | | | | | | REMOVED IN 2023 (WSP PROJECT #CA0006405.2779). | N/A |
| | | CAULKING | LIGHT GREY CAULKING | FLOOR | | CLK02A-C | | | ND | NO | | | | SAMPLED ALONG FLOOR AND CONCRETE BLOCK WALL BY WSP IN 2022 (PROJECT #22572864). | N/A |
| | | CAULKING | RED FIRESTOP CAULKING | FLOOR PENETRATIONS IN AC390A | | CLK03A-C | | | ND | NO | | | | SAMPLED BY WSP IN 2022 (PROJECT #22572864). | N/A |
| | | CAULKING | GREY CAULKING | WINDOWS (INTERIOR) | | CLK01A-C | | | ND | NO | | | | SAMPLED BY WSP IN 2022 (PROJECT #22572864). | N/A |
| | | CAULKING | BROWN CAULKING | WINDOWS (EXTERIOR FLASHING) | | CLK04A-C | | | ND | NO | | | | SAMPLED BY WSP IN 2022 (PROJECT #22572864). | N/A |

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building component.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 - Immediate clean-up of fallen ACM/debris likely to be disturbed.
 2 - Perform asbestos removal/repair for compliance with the regulations.
 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.
 N/A - Not applicable.

Definitions

ACM - Asbestos-Containing Materials
 SA - Sample representative
 R-SA - Sample referenced to a visually similar homogeneous sample material.
 ND - None detected