

oom Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
ALL	ALL AREAS	BROWN FIRESTOP	PIPE PENETRATION	CEILING SPACE	UNKNOWN	18297-S15A	5	CHRYSOTILE	GOOD	YES	В	FRIABLE	OBSERVED TO BE PRESENT IN ROOM H216C. SAMPLED BY MAPLE IN 2019 (PROJECT #18297), AND PRESUMED TO BE PRESENT IN OTHER AREAS OF THE BUILDING. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
ALL	ALL AREAS	BEIGE CAULKING	BETWEEN DOOR FRAME AND WALL	DOOR	UNKNOWN	18297-S04A-C	1	CHRYSOTILE	GOOD	SUSPECT	A	NON-FRIABLE	SAMPLED IN STAIRWELL H501S BY MAPLE (PROJECT #18297), AND PRESUMED TO BE PRESENT IN OTHER AREAS OF THE BUILDING. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
ALL	ALL AREAS	BLACK CAULKING	DOOR CAULKING - GAP BETWEEN DOOR & GLASS	DOOR	UNKNOWN	26417-1A	5	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED IN STAIRWELL H316S BY OHE (PROJECT #26417), AND PRESUMED TO BE PRESENT IN OTHER AREAS OF THE BUILDING. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
			BLACK ROOFING MATERIALS	ROOF	UNKNOWN	S01A-C, S02A- C, S07A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #17080). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
			WHITE CAULKING	ROOF	UNKNOWN	S04A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #17080). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
ROOF	ROOF	ROOFING MATERIALS	BLACK CAULKING	ROOF	UNKNOWN	S05A-C, S06A- C		ND		NO			SAMPLED BY MAPLE (PROJECT #17080). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
			GREY CAULKING	ROOF	UNKNOWN	S03A-C	1	CHRYSOTILE	GOOD	YES	С	NON-FRIABLE	SAMPLED BY MAPLE (PROJECT #17080). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
H100K	CORRIDOR	CEILING TILE	2'X4' SMALL PINHOLE & LENGTHWISE FISSURES	CEILING	50 SQ. FT.					NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	4
H102	ELEVATOR ROOM	NO SUSPECT ACM OBSERVED								NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		26254-1A-C		ND		NO			SAMPLED BY OHE (PROJECT #26254) IN 2020.	N/A
H103	ELEVATOR LOBBY	CEMENT PARGING	GREY	WALL (CEILING SPACE)		27467-1A-C		ND		NO			SAMPLED BY OHE (PROJECT #27467) IN 2022	N/A
пюз	ELEVATOR LOBB	CEILING TILE	2'X4' SMALL PINHOLE & LENGTHWISE FISSURES	CEILING	200 SQ. FT.	25995-2B		ND		NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	7 FITTINGS REMOVED IN 2018 (CURMANN PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND OR HEALTH AND SAFETY) 4
H103A	ELECTRICAL ROOM	CEILING TILE	2'X4' SMALL PINHOLE & LENGTHWISE FISSURES	CEILING		25995-2C		ND		NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A
		CEILING TILE	2'X4' SMALL PINHOLE & SMALL FISSURES	CEILING		25995-3C		ND		NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A
		CEILING TILE	2'X4' SMALL AND BIG PINHOLES	CEILING		25995-4A-C		ND		NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	4	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE		4
		CEILING TILE	2'X4' SMALL PINHOLE & BUMPS	CEILING		25995-1C		ND	1	NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A
H103B	VACANT ROOM	CEILING TILE	2'X4' SMALL PINHOLE & SMALL FISSURES	CEILING		25995-3B		ND		NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.	25622-023-4A- C		ND		NO			SAMPLED BY OHE (PROJECT #25622-023 IN 2022)	N/A
		NEW LAY-IN CEILING TILES				C				NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		CAULKING	CAULKING AROUND DOOR FRAME	DOOR	UNKNOWN	A07a, A08a	2	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY WSP IN 2023 (PROJECT #23595185)	4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		26254-2A-J		ND	<u> </u>	NO			SAMPLED BY OHE (PROJECT #26254) IN 2020.	N/A
		MASTIC	YELLOW	BEHIND VINYL BASEBOARD		26254-3A-C		ND		NO			SAMPLED BY OHE (PROJECT #26254) IN 2020.	N/A
H103C	VACANT ROOM	VINYL SHEET FLOORING	GREY WITH MOSAIC PATTERN	FLOOR		26254-4A-C		ND	ļ	NO			SAMPLED BY OHE (PROJECT #26254) IN 2020.	N/A
				UNDER THRESHOLD STRIP		26254-5A-C		ND		NO			SAMPLED BY OHE (PROJECT #26254) IN 2020.	N/A
		CEILING TILE NEW LAY-IN CEILING TILES	2'X4' SMALL PINHOLE & BUMPS	CEILING		25995-1A		ND		NO NO			SAMPLED BY OHE (PROJECT #25995) IN 2020. NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
H103D	VACANT ROOM	NEW LAY-IN CEILING TILES							1	NO		1	NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
		PARGING CEMENT INSULATION ON MECHANICAL	FITTINGS	CEILING SPACE	8	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE		4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.	25622-023-5A- C		ND		NO			SAMPLED BY OHE (PROJECT #25622-023 IN 2022)	N/A
H103E	VACANT ROOM	CEILING TILE	2'X4' PINHOLE & BUMPS	CEILING		25995-1B		ND	-	NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A
		CEILING TILE	2'X4' PINHOLE & BUMPS 2'X4' PINHOLE & LONG FISSURES	CEILING		25995-1B 25995-2A		ND		NO			SAMPLED BY OHE (PROJECT #25995) IN 2020. SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A N/A
		CEILING TILE	2'X4' PINHOLE & LONG FISSURES 2'X4' PINHOLE & SMALL FISSURES	CEILING	1	25995-2A 25995-3A		ND	1	NO			SAMPLED BY OHE (PROJECT #25995) IN 2020.	N/A N/A
		NEW LAY-IN CEILING TILES			1			ND		NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		PARGING CEMENT INSULATION ON MECHANICAL	FITTINGS	CEILING SPACE	1	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	AT ENTRANCE IN CORNER	4
H103F	STORAGE ROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.	R-SA98		SUSPECT	GOOD	SUSPECT	A	NON-FRIABLE	APPEARS TO BE REMOVED, NOT OBSERVED DURING THE 2021 REASSESSMENT SURVEY	N/A
IIIVOF		DRYWALL NEW LAY-IN CEILING TILES	DRYWALL JOINT COMPOUND	WALL	250 SQ. FT.	R-SA98		SUSPECT	GOOD	SUSPECT NO	A	NON-FRIABLE		

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

 3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations. N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 1 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
H103G	ELEVATOR	NO SUSPECT ACM OBSERVED								NO				N/A
H103K	CORRIDOR	CEILING TILE	2'X4' SMALL PINHOLE & LENGTHWISE FISSURES	CEILING - ADJACENT TO DOOR TO ROOM H103				ND		NO	А	NON-FRIABLE	SAMPLED BY OHE (PROJECT #25995) IN 2020.	4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	20	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	NO ACM FITTINGS OBSERVED TO BE PRESENT BELOW DROP CEILING FOLLOWING OCT. 2023 RENOVATION. ACM FITTINGS REMAIN ABOVE CEILING TILES.	4
		CAULKING AROUND DOORFRAME	WHITE CAULKING	MAIN DOOR TO H111K	1 DOOR	CLK01A	2	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE	SAMPLED BY WSP IN 2023 (WSP PROJECT #CA0006434.4467(007)).	4
		VINYL SHEET FLOORING	NEW - 2023	FLOOR						NO			NEW - 2023	N/A
		WHITE LEVELLER MATERIAL	WHITE LEVELLER MATERIAL	FLOOR UNDER VSF		VFT01A-C		ND		NO			SAMPLED BY WSP IN 2023 (WSP PROJECT #CA0006434.4467(007)).	N/A
		VINYL FLOOR TILE	12"X12" OFF WHITE / BEIGE FLOOR TILE	FLOOR									ALL ASBESTOS-CONTAINING FLOOR TILES WERE REMOVED IN 2023 (WSP PROJECT #CA0006434.4467(007)).	N/A
H104	CARETAKER LUNCHROOM	FLOOR MASTIC	BLACK MASTIC	FLOOR UNDER VFT		VFT01A-C, VFT02A-C		ND		NO			ALL FLOOR MASTIC WAS SAMPLED BY WSP IN 2023 (WSP PROJECT #CA0006434.4467(007)) AND SUBSEQUENTLY REMOVED AS PART OF PROJECT.	N/A
		TRANSITE MATERIAL	TRANSITE COUNTERTOP	COUNTER									REMOVED IN 2023 (WSP PROJECT #CA0006434.4467(007)).	N/A
		BRICK MORTAR	BRICK MORTAR	WALL		MTR01A-C		ND		NO			SAMPLED BY WSP FROM CLAY BRICK WALL SEPARATING FORMER ROOMS H104A / 104C IN 2023 (WSP PROJECT #CA0006434.4467(007)). WALL WAS DEMOLISHED AS PART OF PROJECT.	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC01A-C		ND		NO			SAMPLED BY WSP IN 2023 (WSP PROJECT #CA0006434.4467(007)).	N/A
		CEILING TILE	2' X 4' CEILING TILE WITH PINHOLE AND HEAVY TEXTURE	CEILING		CT01A-C		ND		NO			SAMPLED BY WSP IN 2023 (WSP PROJECT #CA0006434.4467(007)).	N/A
		BLACK MATERIAL IN PIPE INSULATION	BLACK MATERIAL IN FIBREGLASS INSULATION ON PIPE STRAIGHTS SERVICING RADS	CEILING		INS01A-C		ND		NO			SAMPLED BY WSP IN 2023 (WSP PROJECT #CA0006434.4467(007)).	N/A
H105	LAB	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	7	R-SA73	50-75	CHRYSOTILE	GOOD	YES	A	FRIABLE	LOCATED AT ENTRANCE. SOME PIPE FITTING INSULATION HAS BEEN REMOVED AND REPLACED WITH NON-ASBESTOS, FIBERGLASS INSULATION.	4
		TRANSITE MATERIAL	TRANSITE COUNTERTOP	COUNTER	30 SQ. FT.	N/A	N/A		GOOD	SUSPECT	А	NON-FRIABLE	APPEARS TO BE REMOVED, NOT OBSERVED DURING THE 2021 REASSESSMENT SURVEY	N/A
H105C	LAB	NO SUSPECT ACM OBSERVED												N/A
H106 H106E	STORAGE ELEVATOR	NO SUSPECT ACM OBSERVED NEW VINYL SHEET FLOORING								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
H107	ELECTRICAL	NO SUSPECT ACM OBSERVED								NO			ACM MAY BE PRESENT WITHIN THE INTERNAL COMPONENTS OF ELECTRICAL EQUIPMENT	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	9	R-SA73	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE		4
H108S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA73	50-75	CHRYSOTILE	POOR	YES	A	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING MSI SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES OR REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
H109	ELECTRICAL	NO SUSPECT ACM OBSERVED								NO				N/A
H110	PIPE TUNNEL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	181	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE	1 FITTING REMOVED IN 2018 (MAPLE PROJECT #16940). 4 FITTINGS REMOVED IN 2019 (MAPLE PROJECT #18151). APPROXIMATELY 23 LINEAR FT. REMOVED IN 2020 (OHE PROJECT #25966). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA73	50-75	CHRYSOTILE	FAIR	YES	В	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING MSI SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES OR REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
H110A	PIPE TUNNEL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE	1 FITTING REMOVED IN 2018 (MAPLE PROJECT #16940). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	4	R-SA73	50-75	CHRYSOTILE	GOOD	YES	A	FRIABLE		4
H110S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA73	50-75	CHRYSOTILE	FAIR	YES	В	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING MSI SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES OR REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
H111	GEO LAB / ENV SCIENCES	FLOOR TILE AND MASTIC	9"X9" BROWN FLOOR TILE AND MASTIC	FLOORS	90 SQ. FT	SA86	1.8	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	ASBESTOS DETECTED IN BOTH THE FLOOR TILES AND THE MASTIC.	4
		NEW DRYWALL WALLS						1	1	NO		1	NOT SUSPECTED TO CONTAIN ASBESTOS	N/A

Level of Accessibility A - Accessible and exposed to all occupants of the building. B - Accessible only to maintenance staff and exposed to view without moving a building compound. C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required 1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

Definitions ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 2 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
H111A	GEO LAB / ENV SCIENCES	FLOOR TILE AND MASTIC	9"X9" BROWN FLOOR TILE AND MASTIC	FLOORS	90 SQ. FT	SA86	1.8	CHRYSOTILE	GOOD				ASBESTOS DETECTED IN BOTH THE FLOOR TILES AND THE MASTIC.	4
		NEW DRYWALL WALLS								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H111K	CORRIDOR	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H112	CLEANERS SHAFT	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	IN SHAFT	20	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM - AT RADIATOR UNIT (LIKELY ADDITIONAL QUANTITIES IN THE CEILING SPACE)	2	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
H112A	CLEANERS	CEILING TILE	2'X4' SMALL PINHOLE & LENGTHWISE FISSURES	CEILING	100 SQ. FT.				GOOD	SUSPECT	А	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		PLASTER	PLASTER	CEILING		25622-023-7A- C		ND		NO			SAMPLED BY OHE (PROJECT #25622-023) IN 2022	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS		25622-023-6A- C		ND		NO			SAMPLED BY OHE (PROJECT #25622-023) IN 2022	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	10	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	2 FITTINGS AT RADIATOR REMOVED IN 2018 (MAPLE PROJECT #17660). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
H113	STORAGE	DRYWALL	DRYWALL JOINT COMPOUND	CEILING	500 SQ. FT.	R-SA98		SUSPECT	GOOD	SUSPECT	А	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		CEILING TILE	2'X4' SMALL PINHOLE & LENGTHWISE FISSURES	CEILING	45 SQ. FT.				GOOD	SUSPECT	А	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
H114	CARETAKER LUNCHROOM	NEW VINYL SHEET FLOORING NEW LAY-IN CEILING TILES	NEW - 2009							NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE		4
H114A	LOCKER ROOM / VESTIBULE	FLOOR TILE AND MASTIC	9"X9" BROWN FLOOR TILE AND MASTIC	FLOORS	300 SQ. FT.	R-SA86	1.8	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE	ACM DETECTED IN BOTH THE TILE AND MASTIC	4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	SHAFT	16	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE		4
H114V	LOCKER ROOM / VESTIBULE	REFER TO H114A											REFER TO H114A	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA73	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	6	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE		4
H114B	WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA73	50-75	CHRYSOTILE	POOR	YES	С	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING MSI SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES OR REMOVED FOLLOWING TYPE 2 GLOVE BAG PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	SHAFT(B/TOILETS)	20-25	R-SA1	50-75	CHRYSOTILE	GOOD	YES	B/C	FRIABLE	VIEWED FROM H114A	4
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H115	GROUNDS LUNCHROOM	NEW DRYWALL WALLS								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	14	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE		4
		PLASTER	ROUGH GREY PLASTER	WALL		18668 S01a-c	ND			NO			SAMPLED BY MAPLE (PROJECT #18668). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY	N/A
H115A	WASHROOM	PLASTER	OFF-WHITE TEXTURED PLASTER	WALL		18668 S03c	<0.5			NO			SAMPLED BY MAPLE (PROJECT #18668). THIS MATERIAL IS NOT CONSIDERED ASBESTOS-CONTAINING AS PER O. REG. 278/05. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY	NI/A
		GROUT	GROUT	WALL		18668 S02a-c	ND			NO			SAMPLED BY MAPLE (PROJECT #18668). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY	N/A
		CERAMIC TILE BACKING	CERAMIC TILE BACKING	WALL		18668 S03a-c	ND			NO			SAMPLED BY MAPLE (PROJECT #18668). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY	N/A
		CEILING TILE	2'X4' SMALL PINHOLE & LENGTHWISE FISSURES	CEILING		18657 S01a-c	ND			NO			SAMPLED BY MAPLE (PROJECT #18657). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY	4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	24	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
H116	MEN'S LOCKER ROOM	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR TO ROOM	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE	N/A

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

ACM – Asbestos-Containing Materials SA – Sample representative

N/A - Not applicable.

2023 ACM RE-ASSESSMENT

Page 3 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability Comments	Action Required
H116	MEN'S LOCKER ROOM	FLOOR TILE	9"X9" LIGHT BROWN FLOOR TILE	FLOORS	170 SQ. FT.	R-SA83	5	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	24	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE	4
H116A	MEN'S LOCKER ROOM	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOOR TO ROOM H116	10 SQ. FT.	01 A-G		ND		NO		SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		FLOOR TILE	9"X9" LIGHT BROWN FLOOR TILE	FLOORS	170 SQ. FT.	R-SA83	5	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE APPEARS TO BE REMOVED, NOT OBSERVED DURING THE 2020 REASSESSMENT SURVEY	N/A
H116V	VESTIBULE	FLOOR TILE AND MASTIC	9"X9" BROWN FLOOR TILE AND MASTIC	FLOORS	46 SQ. FT.	R-SA86	1.8	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE ACM DETECTED IN BOTH THE TILE AND MASTIC	4
H200	CLEANERS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	4	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE	4
		ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	EXTERIOR WALL	8 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	YES	B/C	NON-FRIABLE	4
H200A	SHAFT	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	50-65	R-SA73	50-75	CHRYSOTILE	GOOD	YES	B/C	6 FITTINGS REMOVED IN 2018 (MAPLE PROJECT #16940). TO FRIABLE VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
H200E	ELEVATOR	NO SUSPECT ACM OBSERVED			0.00 FT	D CA22	15.05		C00D	NO	D/C		N/A 4
H200K	CORRIDOR	ASBESTOS CEMENT BOARD DRYWALL	ASBESTOS CEMENT BOARD	WALL WALL WALL AND CEILING	8 SQ. FT. UNKNOWN	R-SA22 17190 S01a-c, 20911 S05a-c	15-25 ND	CROCIDOLITE ND	GOOD	YES NO	B/C	NON-FRIABLE SAMPLED BY MAPLE (PROJECTS #17190 AND #20911). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
		MASTIC	GREY AND BROWN FLOORING MASTIC	BELOW COOLER			ND	ND		NO		SAMPLED BY MAPLE (PROJECT #18603). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		CERAMIC TILE GROUT	CERAMIC TILE GROUT	WALL		A01a-c	ND	ND		NO		SAMPLED BY WSP IN 2023 (PROJECT #23595187). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		CERAMIC TILE GLUE	CERAMIC TILE GLUE	WALL		A02a-c	ND	ND		NO		SAMPLED BY WSP IN 2023 (PROJECT #23595187). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		VINYL SHEET FLOORING	VINYL SHEET FLOORING, BEIGE PANEL PATTERN	FLOOR		20911 S01a-c	ND	ND		NO		SAMPLED BY MAPLE IN 2023 (PROJECT #20911). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H201	VENDOR AREA	VINYL SHEET FLOORING	TAN SHEET FLOORING	FLOOR		20911 S02a-c	ND	ND		NO		SAMPLED BY MAPLE IN 2023 (PROJECT #20911). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY	N/A
		VINYL SHEET FLOORING	RED SHEET FLOORING	FLOOR		20911 S03a-c	ND	ND		NO		SAMPLED BY MAPLE IN 2023 (PROJECT #20911). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		VINYL SHEET FLOORING	GREY SHEET FLOORING	FLOOR		20911 S04a-c	ND	ND		NO		SAMPLED BY MAPLE IN 2023 (PROJECT #20911). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		FLOOR MASTIC	BROWN MASTIC	FLOOR UNDER VSF		20911 S02a-c, S03a-c, S04a-c	ND	ND		NO		SAMPLED BY MAPLE IN 2023 (PROJECT #20911). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		FLOOR MASTIC	OFF-WHITE MASTIC	FLOOR UNDER VSF		20911 S01a-c	ND	ND		NO		SAMPLED BY MAPLE IN 2023 (PROJECT #20911). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		GREY CEMENTITIOUS MATERIAL	GREY CEMENTITIOUS MATERIAL	FLOOR UNDER VSF		20911 S03a-c, S04a-c	ND	ND		NO		SAMPLED BY MAPLE IN 2023 (PROJECT #20911). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H201A	VENDOR AREA	DRYWALL	DRYWALL JOINT COMPOUND				ND	ND		NO		SAMPLED BY MAPLE (PROJECT #18765B). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H201S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA73	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE	4
		TAR UNDER FIBERGLASS	TAR	ABOVE CEILING	UNKNOWN				GOOD	SUSPECT	С	NON-FRIABLE PRIOR TO RENOVATIONS, ADDITIONAL ASSESSMENT AND SAMPLING IS RECOMMENDED.	4
		DRYWALL	DRYWALL JOINT COMPOUND				ND	ND		NO		SAMPLED BY MAPLE (PROJECT #18765B). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H202	KITCHEN AND COOLERS	MASTIC	GREY MASTIC	BASE OF WALL BY FREEZER			ND	ND		NO		SAMPLED BY WSP IN 2023 (PROJECT #23595187). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		CERAMIC TILE GROUT	CERAMIC TILE GROUT	WALL		A03a-c	ND	ND		NO		SAMPLED BY WSP IN 2023 (PROJECT #23595187). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		CERAMIC TILE MORTAR	CERAMIC TILE MORTAR	WALL		A04a-c	<0.25	CHRYSOTILE		NO		SAMPLED BY WSP IN 2023 (PROJECT #23595187). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H202A	CATERING ROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-023-8A- C	ND	ND		NO		SAMPLED BY OHE (PROJECT #25622-023) IN 2022.	N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 4 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
H202A	CATERING ROOM	TAR UNDER FIBERGLASS	TAR	ABOVE CEILING	UNKNOWN				GOOD	SUSPECT	С	NON-FRIABLE	PRIOR TO RENOVATIONS, ADDITIONAL ASSESSMENT AND SAMPLING IS RECOMMENDED.	4
H202E	ELEVATOR	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H204	CLEANERS CLOSET	NO SUSPECT ACM OBSERVED						1		NO				N/A
H205	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL		18765B-08-011 & 25622-031- 2A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18765B) AND OHE (PROJECT #25622-031) IN 2023. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		NEW LAY-IN CEILING TILES CEILING TILE	NON-ASBESTOS DRYWALL CEILING TILES	CEILING						NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
			12"X12" BEIGE VINYL FLOOR TILES AND	CEIEING						NO			PRIOR TO RENOVATIONS, ADDITIONAL ASSESSMENT AND	11/4
		FLOOR TILE AND MASTIC	MASTIC	FLOOR	200 SQ. FT				GOOD	SUSPECT	A	NON-FRIABLE	SAMPLING IS RECOMMENDED.	4
H205A	CLOSET	NO SUSPECT ACM OBSERVED								NO			LIMITED ACCESS FURTHER INVESTIGATION REQUIRED	N/A
H206K	CORRIDOR	NO SUSPECT ACM OBSERVED								NO				N/A
11007		DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-031-3A- C		ND		NO			SAMPLED BY OHE (PROJECT #25622-031) IN 2023.	N/A
H207	OFFICE	FLOOR TILE AND MASTIC	12"X12" BEIGE VINYL FLOOR TILES AND MASTIC	FLOOR	200 SQ. FT				GOOD	SUSPECT	A	NON-FRIABLE	PRIOR TO RENOVATIONS, ADDITIONAL ASSESSMENT AND SAMPLING IS RECOMMENDED.	4
H208	MEN'S CHANGE ROOM	DRYWALL	DRYWALL JOINT COMPOUND		UNKNOWN		2	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY MAPLE (MAPLE PROJECT #18765B). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
H208A	MEN'S CHANGE ROOM	NO SUSPECT ACM OBSERVED								NO			ACM SUSPECTED TO BE PRESENT IN INACCESSIBLE AREAS (E.G. WALL CAVITIES)	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL CAVITY	UNKNOWN	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	LIMITED ACCESS TO WALL CAVITY (PRESENT IN LARGE STALL WASHROOM)	4
H209	WOMEN'S CHANGE ROOM	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
11203		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	R-SA98	2	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY MAPLE (MAPLE PROJECT #18765B). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
		NEW LAY-IN CEILING TILES		1						NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H209A	CUSTODIAL CLOSET	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	R-SA98		SUSPECT	GOOD	SUSPECT	A	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H209K	CORRIDOR	DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-031-4A-		ND		NO			SAMPLED BY OHE (PROJECT #25622-031) IN 2023.	N/A
						С							, , ,	
H210	DISH ROOM	NEW DRYWALL WALLS	NEW - 2005							NO			NOT SUSPECTED TO CONTAIN ASBESTOS NOT SUSPECTED TO CONTAIN ASBESTOS. ACM IS SUSPECTED	N/A
		CEILING TILE	NON-ASBESTOS CEILING TILES	CEILING						NO			IN WALL CAVITY BEHIND THE SINK AND IN INACCESSIBLE AREAS.	N/A
		NEW DRYWALL WALLS	NEW - 2005							NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H210A	STORAGE ROOM	CEILING TILE	NON-ASBESTOS CEILING TILES	CEILING						NO			NOT SUSPECTED TO CONTAIN ASBESTOS. ACM IS SUSPECTED IN WALL CAVITY BEHIND THE SINK AND IN INACCESSIBLE AREAS.	N/A
H212	SEATING AREA	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		NEW LAY-IN CEILING TILES		AROUND DOORFRAME, INSIDE						NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H212A	SEATING AREA	DRYWALL	DRYWALL JOINT COMPOUND	H212A AROUND DOORFRAME, OUTSIDE		A04a-c	ND	ND		NO			SAMPLED BY WSP IN 2023 (PROJECT #23595185).	N/A
		DRYWALL	DRYWALL JOINT COMPOUND PLASTER FINISHES (SKIM COAT AND BASE	H212A		A06a-c	ND	ND		NO			SAMPLED BY WSP IN 2023 (PROJECT #23595185).	N/A
		PLASTER	COAT)	WALLS		A05a-c	ND	ND		NO			SAMPLED BY WSP IN 2023 (PROJECT #23595185).	N/A
H212S	SEATING AREA	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H213C H214	OFFICE - FOOD SERVICES	NO SUSPECT ACM OBSERVED	NEW - 2009	FLOORING MASTIC BELOW VSF	1700 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	<u>N/A</u>
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING		25622-031-5A- C		ND		NO			SAMPLED BY OHE (PROJECT #25622-031) IN 2023.	N/A
H214A	STUDY SPACE	ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	ABOVE WINDOWS - EXTERIOR SOFFIT OVERHANGS	500 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE		4
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H214V	VESTIBULE	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H214S	STAIRCASE	NO SUSPECT ACM OBSERVED	NEW - 2009	FLOORING MASTIC BELOW VSF	1700 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	NO YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	<u>N/A</u>
H215	LECTURE HALL	PLASTER	CEILING PLASTER	CEILING		25622-023-9A- C		ND		NO			SAMPLED BY OHE (PROJECT #25622-023) IN 2022	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	SHAFT	9	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE	SHAFT ACCESS DOOR LOCATED AT FRONT OF LECTURE HALL.	
H215A	STUDY SPACE	ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	ABOVE WINDOWS - EXTERIOR SOFFIT OVERHANGS	500 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE		4
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 5 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
H215B	STUDY SPACE	ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	ABOVE WINDOWS - EXTERIOR SOFFIT OVERHANGS	500 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE		4
112130	STODI SPACE	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H215V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL	FITTINGS	ABOVE CEILING	5	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE	NO FITTINGS OBSERVED ABOVE FALSE CEILING IN 2023.	4
H215S	STAIRCASE	PIPE FITTINGS NO SUSPECT ACM OBSERVED								NO				N/A
					ADDDOX 1500								SAMPLED BY MAPLE (PROJECT #18764). TO VIEW PROJECT-	
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	APPROX. 1500 SQ. FT.	18764-01E	1	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	APPROX. 7 SQ. FT.	18764-01E	1	CHRYSOTILE	POOR	YES	В	NON-FRIABLE	SAMPLED BY MAPLE (PROJECT #18764) IN 2020. THE DAMAGED ASBESTOS-CONTAINING DRYWALL SHOULD BE REPAIRED FOLLOWING TYPE 1 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
		CAULKING	GREY CAULKING	DOOR TO PROJECTION ROOM		18764-09A-C	1	CHRYSOTILE		YES	A	NON-FRIABLE	SAMPLED BY MAPLE (PROJECT #18764) IN 2020. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
		VINYL SHEET FLOORING	NEW - 2009	FLOOR						NO			VINYL FLOOR TILES WERE REMOVED IN 2009 AND REPLACED WITH VINYL SHEET FLOORING.	N/A
H216	LECTURE HALL	FLOOR MASTIC	BLACK MASTIC	FLOOR UNDER VSF	UNKNOWN		3	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		MECHANICAL SYSTEMS INSULATION	TAPE ON INSULATION	TAPE APPLIED TO SEAMS OF FOIL FACED FIBREGLASS BATT INSULATION		18764-02A-C	80	CHRYSOTILE		YES			SAMPLED BY MAPLE (PROJECT #18764). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
		FABRIC BACKING	FABRIC BACKING	BEHIND WOOD SLAT WALL		18764-03A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18764). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		MASTIC	BROWN MASTIC	BASEBOARD MASTIC		18764-06A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18764). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		PLASTER	GREY AND WHITE PLASTER	CEILING		25952-1A-C; 18764-1A-D, 18764-5A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18764). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY. SAMPLED BY OHE (PROJECT #25952) IN 2020. PORTIONS OF THE CEILING REMOVED IN 2020 (OHE PROJECT #26123).	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOOR						NO			VINYL FLOOR TILES WERE REMOVED IN 2009 AND REPLACED WITH VINYL SHEET FLOORING.	N/A
H216A	LECTURE HALL (SOUTH SIDE OF HW216)	FLOOR MASTIC	BLACK MASTIC	FLOOR UNDER VSF	UNKNOWN		3	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		PLASTER	PLASTER	CEILING BULKHEAD						NO			NOT SUSPECTED TO CONTAIN ASBESTOS (VISUALLY SIMILAR TO PLASTER IN H216)	N/A
H216B	STUDY SPACE	ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	ABOVE WINDOWS - EXTERIOR SOFFIT OVERHANGS	2 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE	LIMITED ACCESS	4
		ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	ABOVE WINDOWS - EXTERIOR SOFFIT OVERHANGS	500 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE	MINOR DAMAGES OBSERVED DURING THE 2022 REASSESSMENT, MONITOR FUTURE CONDITION	4
		DRYWALL	NEW - 2020										NEW - 2020	N/A
		BLACK CAULKING	INTERIOR WINDOW CAULKING	EXTERIOR WALL		18297 S14A-C		ND		NO			SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18297). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
H216C	MEETING ROOM	WHITE CAULKING	AT DRYWALL BULKHEAD	WEST SIDE		18297 S16A-C		ND		NO			SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18297). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
		BROWN FIRESTOP	PIPE PENETRATE	ENTERING EXTERIOR WALL	2 SQ. FT.	18297 S15A	5	CHRYSOTILE	GOOD	YES	В	FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18297). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
		NEW LAY-IN CEILING TILES			1					NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOOR						NO			VINYL FLOOR TILES WERE REMOVED IN 2009 AND REPLACED	N/A
H216K	LECTURE HALL (NORTH SIDE OF HW216)	FLOOR MASTIC	BLACK MASTIC	FLOOR UNDER VSF	UNKNOWN		3	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	WITH VINYL SHEET FLOORING. VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	
		PLASTER	PLASTER	CEILING BULKHEAD						NO			NOT SUSPECTED TO CONTAIN ASBESTOS (VISUALLY SIMILAR TO PLASTER IN H216)	N/A
H216S	STAIRCASE	NO SUSPECT ACM OBSERVED			1					NO				N/A
H216T	UNDERNEATH STAIRCASE	NO SUSPECT ACM OBSERVED								NO				N/A
					1	1		1	1			1		

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 6 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
		DRYWALL	DRYWALL JOINT COMPOUND	WALL IN LOWER LEVEL AND MEZZANINE			1	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2020 (MAPLE PROJECT #18764). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
H217	PROJECTION ROOM (2 FLOORS)	DRYWALL	DRYWALL JOINT COMPOUND	WALL IN LOWER LEVEL AND MEZZANINE	120 SQ. FT.	18764-11A-12C	1	CHRYSOTILE	POOR	YES	А	NON-FRIABLE	THE DAMAGED DRYWALL SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
		FLOOR TILE AND MASTIC	12"X12" GREY FLOOR TILE AND MASTIC	LOWER LEVEL		18764-08A-C	2	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	ACM DETECTED IN BOTH THE TILE AND MASTIC	4
		CAULKING	GREY CAULKING	DOOR TO PROJECTION ROOM		18764-09A-C	1	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE	SAMPLED BY MAPLE (PROJECT #18764) IN 2020. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
H217S	PROJECTION ROOM	REFER TO H217											Refer to H217	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS		3	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
H218	STORAGE ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2	R-SA73	50-75	CHRYSOTILE	POOR	YES	В	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING MSI SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
		CEILING TILE	2'X4' CEILING TILE WITH LARGE WIDTHWISE FISSURES	=		R-SA11 & R- SA120-(A-F)-06		ND		NO				N/A
H218A	STORAGE ROOM	CEILING TILE	2'X4' CEILING TILE WITH LARGE WIDTHWISE FISSURES	E		R-SA11 & R- SA120-(A-F)-06		ND		NO				N/A
H219	WOMEN'S WASHROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL						NO			ALL ASBESTOS-CONTAINING MATERIALS WERE ABATED DURING THE WASHROOMS RENOVATION PROJECT (PROJECT #DCM2010-11)	N/A
H219K	CORRIDOR	NO SUSPECT ACM OBSERVED								NO				N/A
H220	STAIRWELL	NO SUSPECT ACM OBSERVED								NO				N/A
H220A	STUDY SPACE	ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	ABOVE WINDOWS - EXTERIOR SOFFIT OVERHANGS	500 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE		4
11220A	STODI SPACE	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H220S	STAIRWELL	NO SUSPECT ACM OBSERVED								NO				N/A
H220T	STAIRCASE	NO SUSPECT ACM OBSERVED								NO				N/A
H221	MEN'S WASHROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL						NO			ALL ASBESTOS-CONTAINING MATERIALS WERE ABATED DURING THE WASHROOMS RENOVATION PROJECT (PROJECT #DCM2010-11)	N/A
H222	CLEANERS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	5	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	8	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
H222A	CLEANERS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA73	50-75	CHRYSOTILE	POOR	YES	В	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING MSI SHOULD BE REMOVED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
H223A	VENDOR KIOSK	DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		20908 S01a-c	ND	ND		NO			SAMPLED BY MAPLE IN 2023 (PROJECT #20908). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H223K	CORRIDOR	NO SUSPECT ACM OBSERVED								NO				N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	3	R-SA73	50-75	CHRYSOTILE	GOOD	YES	A	FRIABLE		4
H223S	STAIRWELL	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	1	R-SA73	50-75	CHRYSOTILE	POOR	YES	A	FRIABLE	THE DAMAGED ASBESTOS-CONTAINING MSI SHOULD BE REPAIRED FOLLOWING TYPE 2 ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
H224	ELECTRICAL	NO SUSPECT ACM OBSERVED											ACM MAY BE PRESENT WITHIN THE INTERNAL COMPONENTS OF ELECTRICAL EQUIPMENT	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALLS AND CEILING		20910 S01a-c	ND	ND		NO			SAMPLED BY MAPLE IN 2023 (PROJECT #20910). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		CERAMIC FLOOR TILE	RED CERAMIC TILE	FLOOR		20910 S02a-c	ND	ND		NO			SAMPLED BY MAPLE IN 2023 (PROJECT #20910). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H224A	BOTTEGA	GREY CEMENTITIOUS MATERIAL	GREY CEMENTITIOUS MATERIAL	FLOOR UNDER CERAMIC TILE		20910 S02a-c	ND	ND		NO			SAMPLED BY MAPLE IN 2023 (PROJECT #20910). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		MORTAR	TAN MORTAR	BEHIND STONE ON WALL		20910 S03a-c	ND	ND		NO			SAMPLED BY MAPLE IN 2023 (PROJECT #20910). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		NEW LAY-IN CEILING TILES	CEILING TILES	CEILING ADJACENT TO BOTTEGA						NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required 1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.

Definitions ACM – Asbestos-Containing Materials SA – Sample representative

N/A - Not applicable.

2023 ACM RE-ASSESSMENT

Page 7 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H224E	ELEVATOR	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE ELEVATOR DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
H224K H225	CORRIDOR DINING AREA	NO SUSPECT ACM OBSERVED NO SUSPECT ACM OBSERVED								NO NO				N/A N/A
H225A	DINING AREA	NO SUSPECT ACM OBSERVED								NO			LIMITED ACCESS ABOVE CEILING TILES - PRIOR TO RENOVATIONS ADDITIONAL ASSESSMENT FOR HAZARDOUS MATERIALS IS RECOMMENDED.	N/A
H225K	CORRIDOR	ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	ABOVE WINDOWS - EXTERIOR SOFFIT OVERHANGS	800 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE		4
H300	CLEANERS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	12	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
H300A	MEZZANINE	NO SUSPECT ACM OBSERVED								NO				N/A
H301E	ELEVATOR	VINYL SHEET FLOORING		FLOORS	75 SQ. FT	R-SA111-(A-B)- 06		ND		NO			ELEVATOR SHAFT WAS NOT INVESTIGATED - ASSESSMENT REQUIRED	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	15-20	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	2 FITTINGS REMOVED IN CORRIDOR BESIDE H300A IN OCT. 2023 (WSP PROJECT # CA0006434.4467(008)).	4
		TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE ELEVATOR DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H301K	CORRIDOR	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
ISUIK	CORRIDOR	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	4
H301S	STAIRWELL	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
H301V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	4	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	ONLY 1 FITTING OBSERVED DURING 2020 REASSESSMENT- PRESUMED TO BE PRESENT	4
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H302A H302B	ROOMS/OFFICE ROOMS/OFFICE	NO SUSPECT ACM OBSERVED NO SUSPECT ACM OBSERVED								NO NO				N/A N/A
H302C	ROOMS/OFFICE	NO SUSPECT ACM OBSERVED								NO				N/A
H302E	ROOMS/OFFICE	NO SUSPECT ACM OBSERVED								NO				N/A
H302F	ROOMS/OFFICE	NO SUSPECT ACM OBSERVED								NO				N/A
		PLASTER	PLASTER FINISH ON WALL (FINISH COAT + BASE COAT)	WALL		PLA-01-d-e		ND		NO			SAMPLED BY GOLDER (PROJECT #21500921). TO VIEW PROJECT SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		CEILING TILE	2'X2' LENGTH WISE FISSURE	CEILING SPACE		ACT-01a-c		ND		NO			SAMPLED BY GOLDER (PROJECT #21500921). TO VIEW PROJECT SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		GREY CAULKING	GREY CAULKING AROUND DRYWALL SHEETS	CEILING SPACE		CLK-02a-c		ND		NO			SAMPLED BY GOLDER (PROJECT #21500921). TO VIEW PROJECT SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H302G	ROOMS/OFFICE	OFF-WHITE CAULKING	OFF-WHITE CAULKING AROUND DRYWALL SHEETS	CEILING SPACE		CLK-03a-c		ND		NO			SAMPLED BY GOLDER (PROJECT #21500921). TO VIEW PROJECT SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-02a-c		ND		NO			SAMPLED BY GOLDER (PROJECT #21500921). TO VIEW PROJECT SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		CARPET MASTIC	CARPET MASTIC	FLOOR		CM-01a-c		ND		NO			SAMPLED BY GOLDER (PROJECT #21500921). TO VIEW PROJECT SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H302K	ROOMS/OFFICE	NO SUSPECT ACM OBSERVED								NO		1		N/A
H302L	ROOMS/OFFICE	NO SUSPECT ACM OBSERVED								NO				N/A
H302V	ROOMS/OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2				GOOD	YES	С	FRIABLE	3 FITTINGS REMOVED IN NOV 2022 (GOLDER PROJECT #22565808). 2 FITTINGS REMAIN.	4
H305	DINING HALL ABOVE MARKET PLACE	DOOR	BROWN CORE OF DOOR	DOOR		S01A-C		ND		NO			SAMPLED BY MAPLE (MAPLE PROJECT #17017). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
1000	DINING HALL ABOVE MARKET PLACE	DOOR	BROWN MASTIC BELOW LAMINATE	DOOR		S02A-C		ND		NO			SAMPLED BY MAPLE (MAPLE PROJECT #17017). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H305S	MARKET PLACE - SEATING AREA	NO SUSPECT ACM OBSERVED								NO			NO ACCESS ABOVE CEILING	N/A
H306	ELECTRICAL ROOM	NO SUSPECT ACM OBSERVED								NO				N/A
H306E	ELEVATOR	NO SUSPECT ACM OBSERVED				1		1	1	NO		1		N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 8 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Acti Requ
110001/	0000000	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	9	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	OBSERVED OUTSIDE LOCATION H305	4
H306K	CORRIDOR	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N//
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/
H307	CLEANERS ROOM	NO SUSPECT ACM OBSERVED								NO				N
		CEILING TILE	1'X1' LENGTH WISE FISSURE	CEILING SPACE		SA4-A-08		ND		NO				N/
H308	CLASSROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.	SA98 & SA12-A 08		SUSPECT	GOOD	SUSPECT	А	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	1
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	15	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE		
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL SPACE	17	R-SA73	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE		
H308K	CORRIDOR	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL OUTSIDE H308K	10 SQ. FT.	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N
		ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	WALL AT TOP OF STAIRS	9 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	YES	А	NON-FRIABLE		
H308S	STAIRCASE	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
H300		CEILING TILE	1'X1' LENGTH WISE FISSURE	CEILING SPACE		SA4-B-08		ND		NO				
H309	CLASSROOM	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
H309A	CLASSROOM	CEILING TILE	1'X1' LENGTH WISE FISSURE	CEILING SPACE		SA4-B-08		ND		NO				
IJUJA	ULASSRUUM	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
H309B	CLASSBOOM	CEILING TILE	1'X1' LENGTH WISE FISSURE	CEILING SPACE		SA4-B-08		ND		NO				
13096	CLASSROOM	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
	0.0000000	CEILING TILE	1'X1' LENGTH WISE FISSURE	CEILING SPACE		SA4-B-08		ND		NO				
309C	CLASSROOM	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	15	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	ADJACENT TO H308	
Н309К	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL SPACE	24	R-SA73	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE		
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
H309S	STAIRCASE	NO SUSPECT ACM OBSERVED								NO				-
		CEILING TILE	1'X1' LENGTH WISE FISSURE	CEILING SPACE		SA4-C-08		ND		NO				1
H310	CLASSROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	SA12-B-08		SUSPECT	GOOD	SUSPECT	А	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	-
		PARGING CEMENT INSULATION ON MECHANICAL								NO				
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	12	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE		
H310K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL SPACE	24	R-SA73	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE	2 FITTINGS REMOVED IN 2018 (MAPLE PROJECT #17708). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
310S	STAIRCASE	NO SUSPECT ACM OBSERVED								NO				
310V	VESTIBULE	NO SUSPECT ACM OBSERVED								NO				
311A	PROJECTION ROOM	REFER TO H217								NO				
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	11	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	1 FITTING REMOVED IN 2019 (MAPLE PROJECT #17705). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR	
H311K	CORRIDOR	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	EXTERIOR WALL (TOP OF STAIRCASE H311T)									HEALTH AND SAFETY. REMOVED IN 2019 (MAPLPE PROJECT #17705). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH	
										NO			AND SAFETY.	
H311S	PROJECTION ROOM	REFER TO H217								NO				
H311T	STAIRCASE	ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	WOODEN BULKHEAD BETWEEN H335K AND STAIRCASE H311T	250 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE		
1 311V	VESTIBULE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	2				GOOD	SUSPECT	С	FRIABLE		
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
										NO				-
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	
H312	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WEST AND SOUTH WALL	UNKNOWN	18215 S01A	1	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY MAPLE (PROJECT #18215) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
H313	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	EAST, SOUTH AND WEST WALL		18215 S02A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18215) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

2 – Perform asbestos removal/repair for compliance with the regulations.

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 9 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
H313A	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	4
	001	DRYWALL	DRYWALL JOINT COMPOUND	SOUTH WALL		18215 S03A-C	ND	ND		NO			SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18215). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	160 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H314	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	
H315	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	
H315A	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	160 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H315K	CORRIDOR	NO SUSPECT ACM OBSERVED								NO				N/A
		CAULKING, BLACK	DOOR CAULKING - GAP BETWEEN DOOR AND GLASS, STAIR A, FLOOR 3	DOOR		26417-1A	5	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE	SAMPLED BY OHE (OHE PROJECT #26417) IN 2021. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
H316S	STAIRWELL	CAULKING, GREY	DOOR CAULKING - GAP BETWEEN DOOR AND GLASS, STAIR A, FLOOR 3	DOOR		26417-2A-C	<0.5	CHRYSOTILE	GOOD	NO	A		SAMPLED BY OHE (PROJECT #26417) IN 2021. THIS MATERIAL IS NOT CONSIDERED ASBESTOS-CONTAINING AS PER O. REG. 278/05. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H316V	VESTIBULE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	400 SQ. FT.	25622-023-1A- C	1	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE	SAMPLED BY OHE (PROJECT #25622-023) IN 2022.	4
H317A	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	
H317	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations. N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 10 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
H318	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	4
H318	OFFICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H319	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H320	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H321	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	С	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H322	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	С	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
Н323	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	С	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	2 4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H324	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	С	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required 1 – Immediate clean-up of fallen ACM/debris likely to be disturbed. 2 – Perform asbestos removal/repair for compliance with the regulations.

3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

N/A - Not applicable.

2023 ACM RE-ASSESSMENT

Page 11 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
H324	OFFICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H325	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	0 4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H326	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	O 4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H327	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	0 4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H328	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	0 4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H329	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	0 4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H330	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	0 4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H331	OFFICE	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	C	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	0 4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.

Definitions ACM – Asbestos-Containing Materials SA – Sample representative

N/A - Not applicable.

2023 ACM RE-ASSESSMENT

Page 12 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Require
H331	OFFICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	SA12-B-08		SUSPECT	GOOD	SUSPECT	А	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
H331A	OFFICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H331K	CORRIDOR	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE™ PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	SA12-C-08		SUSPECT	GOOD	SUSPECT	A	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
H332A	OFFICE	CEILING TILE	1'X1' LENGTH WISE FISSURE	CEILING SPACE		R-SA11		ND		NO			RECOMMENDED	N/A
	OTTICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H332S	STAIRWELL	NO SUSPECT ACM OBSERVED NEW LAY-IN CEILING TILES								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
H332V	VESTIBULE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	25622-023-2A-	1	CHRYSOTILE	GOOD	YES	Α	NON-FRIABLE	SAMPLED BY OHE (PROJECT #25622-023) IN 2022.	4
11332.V	VESTIBULE	NEW VINYL SHEET FLOORING				С				NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		PRESUMED ASBESTOS CEMENT BOARD	CEMENT BOARD	MAY BE PRESENT BEHIND	UNKNOWN				GOOD	SUSPECT	С	NON-FRIABLE		4
H333	OFFICE	VINYL SHEET FLOORING	NEW - 2009	RADIATORS FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		PRESUMED ASBESTOS CEMENT BOARD	CEMENT BOARD	MAY BE PRESENT BEHIND RADIATORS	UNKNOWN				GOOD	SUSPECT	С	NON-FRIABLE		4
H334	OFFICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		PRESUMED ASBESTOS CEMENT BOARD	CEMENT BOARD	MAY BE PRESENT BEHIND RADIATORS	UNKNOWN				GOOD	SUSPECT	С	NON-FRIABLE		4
H335	OFFICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		DRYWALL	DRYWALL JOINT COMPOUND	SOUTH WALL	150 SQ. FT.	18207 S01A	1	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18207). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
		PRESUMED ASBESTOS CEMENT BOARD	CEMENT BOARD	MAY BE PRESENT BEHIND RADIATORS	UNKNOWN				GOOD	SUSPECT	с	NON-FRIABLE		4
H335K	CORRIDOR	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	WOODEN BULKHEAD BETWEEN H335K AND STAIRCASE H311T	250 SQ. FT.	R-SA22	15-25	CROCIDOLITE	GOOD	YES	В	NON-FRIABLE		4
H400	CLEANERS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	11	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
H401E	ELEVATOR	NO SUSPECT ACM OBSERVED								NO				N/A
H401S	STAIRWELL	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE OUTSIDE OF H400	5	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	OUTSIDE OF H400	4
H401K	CORRIDOR	PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE	PRESUMED ASBESTOS-CONTAINING TRANSITE [™] PANELS ARE LIKELY LOCATED WITHIN THE RADIATOR UNITS, BUT ARE CONCEALED DUE TO THE OUTER WOODEN PANELS. PRIOR TO RENOVATIONS WHICH MAY AFFECT THE RADIATORS, AN INTRUSIVE INVESTIGATION SHOULD OCCUR TO DETERMINE THE PRESENCE OF ASBESTOS-CEMENT PANELS WITHIN THE RADIATOR UNITS.	D 4
		NEW LAY-IN CEILING TILES NEW VINYL SHEET FLOORING								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
H402	CLASSROOM	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	575 SQ. FT.	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	ORANGE 9"x9" VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 13 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
		PLASTER	PLASTER	ABOVE CEILING TILES		PLA01A-C	ND	ND		NO			NON-ASBESTOS PLASTER CEILING IS LOCATED ABOVE ACOUSTIC CEILING TILES. SAMPLED BY WSP IN 2023 (PROJECT #CA0006434.4467(009)).	N/A
H402	CLASSROOM	PAPER BACKING	PAPER BACKING	ABOVE PLASTER CEILING		PAP01A-C	ND	ND		NO			SAMPLED BY WSP IN 2023 (PROJECT #CA0006434.4467(009)).	N/A
	-	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	33	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	NOT OBSERVED DURING 2021 REASSESSMENT- PRESUMED TO BE PRESENT	4
H402K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	2	R-SA1	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	NOT OBSERVED DURING 2021 REASSESSMENT- PRESUMED TO BE PRESENT NOT SUSPECTED TO CONTAIN ASBESTOS	4 N/A
	-	NEW LAY-IN CEILING TILES NEW VINYL SHEET FLOORING								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		NEW VINTE SHEET FEOORING								NO			SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW	11/A
		CEILING TILE	1'X1' GLUE IN CEILING TILES	CEILING		17846 S06		ND		NO			PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		TAN MASTIC	CEILING MASTIC	CEILING		17846 S07		ND		NO			SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H403	OFFICE	PLASTER	SMOOTH PLASTER	CEILING		17846 S08		ND		NO			SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		17846 S09		ND		NO			SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
	-	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		CEILING TILE	1'X1' GLUE IN CEILING TILES	CEILING		17846 S04		ND		NO			SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
	-	TAN MASTIC	CEILING MASTIC	CEILING		17846 S05		ND		NO			SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
	HUMANITIES RESEARCH	DRYWALL	DRYWALL JOINT COMPOUND	WALL		17846 S02		ND		NO			SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H403A		DRYWALL DRYWALL JOINT COMPOUND WALL 17846 S02 ND ND NO PROJECT-SPECIFIC REP NTRE NEW VINYL SHEET FLOORING GREEN VINYL SHEETING FLOORS 17846 S01 ND ND NO SAMPLED BY MAPLE (I VINE VINE GREEN VINYL SHEETING FLOORS 17846 S01 ND ND NO SAMPLED BY MAPLE (I	SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A										
		BROWN MASTIC	FLOOR MASTIC	FLOORS		17846 S01		ND		NO			SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		DOOR CAULKING	DOOR CAULKING	DOOR	UNKNOWN	17846 S03	1	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE	SAMPLED BY MAPLE (PROJECT #17846) IN 2019 . TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
		TEXTURE COAT	TEXTURE COAT	CEILING SPACE	525 SQ. FT.	SA2-C-08		ND		NO				N/A
	-	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	12	R-SA1	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE	NOT OBSERVED DURING 2021 REASSESSMENT, PRESUMED TO BE PRESENT	4
	-	NEW LAY-IN CEILING TILES								NO				N/A
	TEACHING ASSISTANTS	DRYWALL	DRYWALL JOINT COMPOUND	WALLS		18297 S01B-C, S02A	ND	ND		NO			SAMPLED BY MAPLE (PROJECT #18297) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H404	OFFICE	PLASTER	WHITE AND BEIGE PLASTER	WALLS		18297 S01A-B, S02A-C	<0.5	TREMOLITE		NO			SAMPLED BY MAPLE (PROJECT #18297) IN 2019. THIS MATERIAL IS NOT CONSIDERED ASBESTOS-CONTAINING AS PER O. REG. 278/05. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
	-	YELLOW MASTIC	FLOORING MASTIC	BELOW VINYL SHEET FLOORING	UNKNOWN	18297 S03A-C	ND	ND		NO			SAMPLED BY MAPLE (PROJECT #18297) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		VINYL SHEET FLOORING	BEIGE VINYL SHEET FLOORING	FLOORS	1	VSF-01a-c		1	1	NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		BEIGE MASTIC	FLOOR ADHESIVE	FLOORS		VSF-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
	-	MASTIC	FLOOR MASTIC	FLOORS		FM-01a-c							SAMPLED BY GOLDER (PROJECT #21500921).	N/A
	-	CERAMIC TILE GROUT MASTIC	CERAMIC TILE GROUT BASEBOARD MASTIC	FLOORS BEHIND VINYL BASEBOARD		CTG-01-a-c BBM-01a-c				NO NO			SAMPLED BY GOLDER (PROJECT #21500921). SAMPLED BY GOLDER (PROJECT #21500921).	N/A N/A
	-	DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-01a-c			1	NO			SAMPLED BY GOLDER (PROJECT #21500921). SAMPLED BY GOLDER (PROJECT #21500921).	N/A N/A
		PLASTER	FINISH AND BASE COATS	WALL	1	PLA-01a-c		1	1	NO		1	SAMPLED BY GOLDER (PROJECT #21500921).	N/A
H404A	OFFICE	GREY MASTIC	DUCT/VENT MASTIC	CEILING SPACE	1	DM-01a-c		1	1	NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		BELLS AND SPIGOTS	BELLS AND SPIGOTS	ABOVE CEILING	7				GOOD	SUSPECT	С	NON-FRIABLE		4
		GREY/BLACK/BEIGE CAULKING	DOOR CAULKING	DOOR		CLK-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		ASBESTOS CEMENT BOARD	ASBESTOS CEMENT BOARD	LIKELY PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	20 SQ. FT	R-SA22	15-25	CROCIDOLITE	GOOD	YES	С	NON-FRIABLE		4
	-	NEW LAY-IN CEILING TILES	CEILING TILES	CEILING	1				1			1	NOT SUSPECTED TO CONTAIN ASBESTOS. CEILING TILES HAVE DATE STAMP OF 02/15/10.	N/A

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 14 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
		NEW LAY-IN CEILING TILES	CEILING TILES	CEILING									NOT SUSPECTED TO CONTAIN ASBESTOS. CEILING TILES HAVE DATE STAMP OF 02/15/10.	N/A
	-	CERAMIC TILE GROUT	CERAMIC TILE GROUT	FLOORS		CTG-01a-c							SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		MASTIC	FLOOR MASTIC	FLOORS		FM-01a-c							SAMPLED BY GOLDER (PROJECT #21500921). SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		VINYL SHEET FLOORING	BEIGE VINYL SHEET FLOORING	FLOORS		VSF-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921). SAMPLED BY GOLDER (PROJECT #21500921).	N/A
H404B	OFFICE	BEIGE MASTIC	FLOOR ADHESIVE	FLOORS		VSF-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
H404D	OFFICE									-			, , ,	
		GREY MASTIC	DUCT/VENT MASTIC	CEILING SPACE		DM-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		GREY/BLACK/BEIGE CAULKING	DOOR CAULKING	DOOR		CLK-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		PLASTER	FINISH AND BASE COATS	WALL		PLA-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		MASTIC	BASEBOARD MASTIC	BEHIND VINYL BASEBOARD		BBM-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL		DJC-01a-c				NO			SAMPLED BY GOLDER (PROJECT #21500921).	N/A
		VINYL SHEET FLOORING	GREY VINYL SHEET FLOORING	FLOOR		18297 S20A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18297) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		BLACK & YELLOW MASTIC	FLOORING MASTIC	BELOW VINYL SHEET FLOORING		18297 S20A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18297) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H404D	LANGUAGE RESOURCES ROOM	DRYWALL	DRYWALL JOINT COMPOUND	SOUTH, NORTH AND WEST WALLS		18297 S17A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18297) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
	·	SMOOTH PLASTER	SMOOTH PLASTER	SOUTH, NE AND SW WALLS		18297 S18A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18297) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		GREY CAULKING	CAULKING AROUND VENT	MIDDLE OF ROOM		18297 S19A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18297) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
	ľ	BELLS AND SPIGOTS	BELLS AND SPIGOTS	ABOVE CEILING					GOOD	SUSPECT	С	NON-FRIABLE		4
		NEW VINYL SHEET FLOORING	NEW - 2009					1		NO		1	NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H404K	CORRIDOR	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		NEW DRYWALL WALLS								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
			1							110			ACM MAY BE PRESENT AS COMPONENTS OF ELECTRICAL	
H405	ELECTRICAL ROOM	NO SUSPECT ACM OBSERVED								NO			EQUIPMENT	N/A
										NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H406	WOMEN'S WASHROOM	NEW DRYWALL CEILING								-				
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H406E	ELEVATOR	NO SUSPECT ACM OBSERVED								NO				N/A
H406K	CORRIDOR	NEW LAY-IN CEILING TILES								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
	Contractor	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		NEW DRYWALL CEILING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
	-	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		PARGING CEMENT INSULATION ON MECHANICAL	FITTINIOO		-	D 004	50 75		0000					
		PIPE FITTINGS	FITTINGS	WALL SPACE	7	R-SA1	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
H407	MEN'S WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL SPACE	1	R-SA1	50-75	CHRYSOTILE	POOR	YES	В	FRIABLE	RESIDUAL PARGING CEMENT FITTINGS PRESENT ON THREE FITTINGS WITHIN THE WALL SPACE. THE RESIDUAL DEBRIS SHOULD BE REMOVED FOLLOWING TYPE 2 GLOVE BAG ASBESTOS PROCEDURES, AS PRESCRIBED UNDER O.REG. 278/05.	2
		TEXTURE COAT	TEXTURE COAT	CEILING SPACE	672 SQ. FT.	SA84 & SA2-A- 08		ND		NO				N/A
H408	CLASSROOM					υð		-		NO		-		N1/A
		NEW LAY-IN CEILING TILES				-				-			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		NEW VINYL SHEET FLOORING	l					1		NO		1	NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H408A	MAIL ROOM	NEW DRYWALL WALLS AND CEILING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H408B	ROOM	NEW VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	NO YES	В	NON-FRIABLE		N/A 4
	-	NEW DRYWALL CEILING								NO			VINYL SHEET FLOORING). NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER	4
H409	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	NORTH, EAST AND SOUTH WALL		18215 S04A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18215) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
	·	PARGING CEMENT INSULATION ON MECHANICAL	FITTINGS	WITHIN RADIATOR UNITS AT					1	NO		1	NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY	N/A
		PIPE FITTINGS		THE PERIMETER WALL									ENVIROSAFE. VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER	

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

2 – Perform asbestos removal/repair for compliance with the regulations.

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 15 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
		DRYWALL	DRYWALL JOINT COMPOUND	EAST WALL	UNKNOWN	18215 S05A-C	1	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE	SAMPLED BY MAPLE (PROJECT #18215) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
H409A	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY ENVIROSAFE.	N/A
		PRESUMED ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS-CEMENT PANELS	PRESENT WITHIN RADIATOR UNITS AT THE PERIMETER WALL	125 SQ. FT.	N/A	N/A	OTHER - comments	GOOD	SUSPECT	с	NON-FRIABLE		4
		TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS TO WASHROOMS AND MECHANICAL ROOMS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
H409K	CORRIDOR	NEW LAY-IN CEILING TILES NEW VINYL SHEET FLOORING								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
		PARGING CEMENT INSULATION ON MECHANICAL	FITTINGS	ACROSS FROM RM HW409	1	R-SA1	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE		4
		PIPE FITTINGS PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	CEILING SPACE	1	R-SA1	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE	LOCATED ACROSS FROM THE DOOR TO ROOM H409.	4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	′ 4
H410	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	SA13-B-08		SUSPECT	GOOD	SUSPECT	A	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H411	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL		25622-031-6A- C		ND		NO			SAMPLED BY OHE (PROJECT #25622-031) IN 2023.	N/A
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H411A	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	SA13-B-08		SUSPECT	GOOD	SUSPECT	А	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H412	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	SA13-B-08		SUSPECT	GOOD	SUSPECT	А	NON-FRIABLE	APPEARS TO BE REMOVED, NOT OBSERVED DURING THE 2020 REASSESSMENT SURVEY	4
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (1) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
H413S	STAIRWELL	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		NEW LAY-IN CEILING TILES NEW VINYL SHEET FLOORING								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
H413V	VESTIBULE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (3) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H414	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (1) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
H415	OFFICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative R-SA – Sample referenced to a visually similar homogeneous sample material. ND – None detected

N/A - Not applicable.

2023 ACM RE-ASSESSMENT

Page 16 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Require
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
H415	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H416	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H417	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H418	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N//
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H419	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N//
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	2
H420	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	,
H421	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	
H422	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	
H423	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	
H424	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N
H425	OFFICE	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	·
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

 3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations. N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative R-SA – Sample referenced to a visually similar homogeneous sample material. ND – None detected

2023 ACM RE-ASSESSMENT

Page 17 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Require
H425	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H426	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (1) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H427	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE [™] ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H428	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (2) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
H428A	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY ENVIROSAFE.	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	18215 S06A	0.5	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY MAPLE (PROJECT #18215). TO VIEW PROJECT- SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY	4
		CEILING TILE	1'X1' LENGTH WISE FISSURE	CEILING SPACE		R-SA11		ND		NO				N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		ASBESTOS CEMENT BOARD	TRANSITE [™] ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
H428B	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY ENVIROSAFE.	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	EAST AND SOUTH WALL	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT	A	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		CEILING TILE NEW LAY-IN CEILING TILES	1'X1' LENGTH WISE FISSURE	CEILING SPACE		R-SA11		ND		NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H429S	STAIRWELL	MECHANICAL SYSTEMS INSULATION	FITTINGS	MECHANICAL SHAFT #20						YES		FRIABLE	ASBESTOS CONTAINING PIPE ELBOWS HAS BEEN REMOVED ACCORDING TO UTSC DESIGN & CONSTRUCTION MANAGEMENT REPORT	r n/A
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
1140014		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (8) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
H429V	VESTIBULE	NEW LAY-IN CEILING TILES NEW VINYL SHEET FLOORING								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	25622-023-3A-	0.5	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY OHE IN (PROJECT #25622-023) 2022.	4
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	R-SA82	5	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE		4
H430	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			VINYL SHEET FLOORING). REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (1) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
H431	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			NO FITTINGS OBSERVED DURING DEC. 2023 INSPECTION BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	R-SA82	5	CHRYSOTILE	GOOD	YES	А	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
H432	OFFICE	DRYWALL	DRYWALL JOINT COMPOUND	SOUTH WALL		18215 S07A-C		ND		NO			SAMPLED BY MAPLE (PROJECT #18215) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 - Type 2 asbestos procedures required to enter area.
 4 - Regular inspection/surveillance of ACM for compliance with the regulations.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

N/A - Not applicable.

2023 ACM RE-ASSESSMENT

Page 18 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Require
		ASBESTOS CEMENT BOARD	TRANSITE™ ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
H432	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			ALL (1) FITTINGS REMOVED IN DEC. 2023 BY ENVIROSAFE.	N/A
		VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	180 SQ. FT.	R-SA82	5	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	6	R-SA73	50-75	CHRYSOTILE	GOOD	YES	А	FRIABLE		4
H433	LANGUAGE LAB	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	SA13-D-08		SUSPECT	GOOD	SUSPECT	A	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		DRYWALL	DRYWALL JOINT COMPOUND	WALL	300 SQ. FT.	R-SA13-D-08		SUSPECT	GOOD	SUSPECT	A	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
H433A	MEETING ROOM	PLASTER	GREY PLASTER	WALL		25953-1A-C, 25953-2A-C				NO	A		SAMPLED BY OHE (PROJECT #25953) IN 2020.	N/A
		TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS TO WASHROOMS AND MECHANICAL ROOMS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
H433C	MAIL ROOM	DRYWALL	DRYWALL JOINT COMPOUND	WALL	UNKNOWN	R-SA13-D-08		SUSPECT	GOOD	SUSPECT	A	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
		NEW LAY-IN CEILING TILES NEW VINYL SHEET FLOORING								NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
H433K	CORRIDOR	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	14	R-SA73	50-75	CHRYSOTILE	GOOD	YES	В	FRIABLE		4
H434	MECHANICAL ROOM	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		PLASTER	PLASTER	WALL		SA3-B-08		ND		NO				N/A
		DRYWALL	DRYWALL JOINT COMPOUND	CEILING	120 SQ. FT.	SA13-E-08		SUSPECT	GOOD	SUSPECT	А	NON-FRIABLE	PRIOR TO RENOVATIONS ADDITIONAL SAMPLING IS RECOMMENDED	4
H435	MEN'S WASHROOM	NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL	2				GOOD	YES	С	FRIABLE		4
H435A	CLEANERS	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL, INACCESSIBLE FROM MEN'S WASHROOM	1	R-SA73	50-75	CHRYSOTILE	GOOD	YES	С	FRIABLE	ACM DEBRIS CLEANED IN 2019 (MAPLE PROJECT #18098). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	4
		NEW VINYL SHEET FLOORING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H436	WOMEN'S WASHROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	WALL CHASE BELOW SINK	2	R-SA73	50-75	CHRYSOTILE	GOOD	SUSPECT	С	FRIABLE		4
		PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	20	R-SA73	50-75	CHRYSOTILE	GOOD	YES	B/C	FRIABLE	REPAIRED IN 2009	4
H437	MECHANICAL	TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
		TEXTURE COAT	PAINTED TEXTURE COAT OVER PLASTER	WALL - ABOVE DOORS TO WASHROOMS AND MECHANICAL ROOMS	10 SQ. FT.	01 A-G		ND		NO			SAMPLED FROM VARIOUS LOCATIONS THROUGHOUT THE SCIENCE WING DURING THE 2016 REASSESSMENT.	N/A
H437K	CORRIDOR	VINYL SHEET FLOORING	NEW - 2009	FLOORING MASTIC BELOW VSF	UNKNOWN	N/A	N/A	CHRYSOTILE	GOOD	YES	В	NON-FRIABLE	VINYL FLOOR TILES WERE REMOVED IN 2009, HOWEVER ASBESTOS-CONTAINING MASTIC REMAINS (BENEATH THE NEW VINYL SHEET FLOORING).	4
5TH FLOOR	ALL AREAS	BEIGE CAULKING	DOOR CAULKING	ALL AREAS	UNKNOWN	18297 S04A	1	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	6 DOORS (IN ROOMS HW520, HW523, HW527 and HW528) INCLUDING CAULKING HAS BEEN REMOVED IN 2020 ACCORDING TO UTSC DESIGN AND CONSTRUCTION MANAGEMENT REPORT AND MAPLE PROJECT #18297 REPORT. THE CAULKING WAS SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18297). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY. ALL REMAINING BEIGE DOOR CAULKING PRESENT ON THE 5TH FLOOR SHOULD BE PRESUMED TO CONTAIN ASBESTOS.	
5TH FLOOR	ALL AREAS	BLACK MASTIC	FLOOR MASTIC	ALL AREAS									REMOVED 2020 (MAPLE PROJECT #18297).	4
H500	CLEANERS	NO SUSPECT ACM OBSERVED								NO				N/A
H501E	ELEVATOR	NO SUSPECT ACM OBSERVED								NO				N/A
H501K	CORRIDOR	ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

N/A - Not applicable.

2023 ACM RE-ASSESSMENT

Page 19 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition	ACM (Yes, No, Suspect)	Accessibility	Friability	Comments	Action Required
H501K	CORRIDOR	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	ABOVE CEILING	24				GOOD	YES	С	FRIABLE		4
H501S	STAIRWELL	NO SUSPECT ACM OBSERVED								NO				N/A
H502	MECHANICAL ROOM	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	FITTINGS	GENERAL ROOM	40	R-SA73	50-75	CHRYSOTILE	GOOD	YES	B/C	FRIABLE	INSULATION ON SOME OF THE PIPE FITTINGS WAS REMOVED IN 2022 (OHE PROJECT #28213)	4
H503	ROOF	ROOFING MATERIALS	ROOFING TAR AND FELT	ROOF	UNKNOWN	N/A	N/A	OTHER - comments	GOOD	SUSPECT		NON-FRIABLE	ACM IS SUSPECTED TO BE PRESENT IN THE ROOFING TAR AND FELT LAYERS. IF RENOVATION ACTIVITIES ARE SCHEDULED WHICH MAY AFFECT THE ROOFING MATERIALS, ADDITIONAL SAMPLING IS RECOMMENDED.	N/A
H503A	MECHANICAL ROOM	NO SUSPECT ACM OBSERVED								NO				N/A
		NEW DRYWALL WALLS AND CEILING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
H503B	MEN'S WASHROOM	VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC							NO NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
поозв	WEN'S WASHROOM	RED, GREY, LIGHT GREY AND WHITE CEMENTITIOUS MATERIAL						ND		NO			NEWOVED 2020 (WALLET NOOLOT #10251).	N/A
		NEW DRYWALL WALLS AND CEILING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		VINYL SHEET FLOORING	NEW - 2020							NO				N/A
H504	WOMEN'S WASHROOM	BLACK MASTIC	FLOOR MASTIC										REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		RED, GREY, LIGHT GREY CEMENTITIOUS MATERIAL						ND		NO				N/A
		DRYWALL	NEW - 2020							NO			NEW - 2020	N/A
		SMOOTH PLASTER	SMOOTH PLASTER	NORTH WALL	UNKNOWN	18297 S06A-C	ND	ND		NO			SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18297). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
H504K	CORRIDOR	BLACK MASTIC	FLOOR MASTIC										REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		BEIGE CAULKING	DOOR CAULKING	OUTSIDE H501S	UNKNOWN	18297 S04A	1	CHRYSOTILE	GOOD	YES	A	NON-FRIABLE	SAMPLED BY MAPLE IN 2019 (MAPLE PROJECT #18297). TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	
		VINYL SHEET FLOORING	NEW - 2020							NO				N/A
	055105	BLACK MASTIC	FLOOR MASTIC										REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H505	OFFICE	DRYWALL	NEW - 2020	WITHIN RADIATOR UNITS AT						NO			NEW - 2020	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL						NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020							NO				N/A
H505A	OFFICE	BLACK MASTIC	FLOOR MASTIC										REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H505K	CORRIDOR	NEW DRYWALL CEILING								NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A
		VINYL SHEET FLOORING	NEW - 2020							NO				N/A
H506	OFFICE	BLACK MASTIC	FLOOR MASTIC	WITHIN RADIATOR UNITS AT									REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL						NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020							NO				N/A
H507	OFFICE	BLACK MASTIC	FLOOR MASTIC	WITHIN RADIATOR UNITS AT									REMOVED 2020 (MAPLE PROJECT #18297).	N/A
			TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL									REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC							NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
H507A	OFFICE		TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT						NO			· · · · · · · · · · · · · · · · · · ·	
		ASBESTOS CEMENT BOARD		THE PERIMETER WALL									REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC							NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
H508	OFFICE			WITHIN RADIATOR UNITS AT						10				
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL						NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		CEILING TILE MECHANICAL SYSTEMS INSULATION	1'X1' LENGTH WISE FISSURE FITTINGS	CEILING SPACE STAIRWELL		R-SA11		ND		NO YES		FRIABLE	REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
H509S	STAIRWELL	ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT						NO		FRIABLE	REMOVED 2020 (MAPLE PROJECT #10297).	N/A
			Invirging Aspestos cement panees	THE PERIMETER WALL										
		NEW LAY-IN CEILING TILES VINYL SHEET FLOORING	NEW - 2020							NO NO			NOT SUSPECTED TO CONTAIN ASBESTOS	N/A N/A
H509V	VESTIBULE	BLACK MASTIC	FLOOR MASTIC										REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020							NO				N/A
H510	OFFICE	BLACK MASTIC	FLOOR MASTIC										REMOVED 2020 (MAPLE PROJECT #18297).	N/A
1010	UTICE	ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020							NO				N/A
		BLACK MASTIC	FLOOR MASTIC										REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H511	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL						NO			REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		DRYWALL	NEW - 2020							NO			NEW - 2020	N/A
l of Accessib	ility		Level of Actio	n Required		1	1	1	1	Definiti	ons	1		<u> </u>

Level of Accessibility A - Accessible and exposed to all occupants of the building. B - Accessible only to maintenance staff and exposed to view without moving a building compound. C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required 1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

Definitions ACM – Asbestos-Containing Materials SA – Sample representative

N/A - Not applicable.

2023 ACM RE-ASSESSMENT

Page 20 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition ACM (Yes, No, Suspect) Accessibility	Friability Comments	Action Required
		VINYL SHEET FLOORING	NEW - 2020						NO		N/A
11540		BLACK MASTIC	FLOOR MASTIC							REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H512	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		DRYWALL	NEW - 2020						NO	NEW - 2020	N/A
		VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
H513	OFFICE			WITHIN RADIATOR UNITS AT							
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
H514	OFFICE			WITHIN RADIATOR UNITS AT					NO.		
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
H515	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT					NO		N/A
				THE PERIMETER WALL						REMOVED 2020 (MAPLE PROJECT #18297).	
		VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
H516	OFFICE	ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
				THE PERIMETER WALL							
		VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
H517	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL	WITHIN RADIATOR UNITS AT PERIMETER						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
11317	OFFICE	PIPE FITTINGS	WALL						NO	RENOVED 2020 (MAPLE PROJECT #10297).	IN/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020						NO		N/A
H518	OFFICE	BLACK MASTIC	FLOOR MASTIC							REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020						NO		N/A
		BLACK MASTIC	FLOOR MASTIC							REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H519	OFFICE	DRYWALL	NEW - 2020	WITHIN RADIATOR UNITS AT					NO	NEW - 2020	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020						NO		N/A
H520	OFFICE	BLACK MASTIC DRYWALL	FLOOR MASTIC NEW - 2020						NO	REMOVED 2020 (MAPLE PROJECT #18297). NEW - 2020	N/A N/A
11020	OTTICE			WITHIN RADIATOR UNITS AT							
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING BLACK MASTIC	NEW - 2020 FLOOR MASTIC						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A N/A
		PARGING CEMENT INSULATION ON MECHANICAL	WITHIN RADIATOR UNITS AT PERIMETER						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H521	OFFICE	PIPE FITTINGS	WALL								
		DRYWALL	NEW - 2020	WITHIN RADIATOR UNITS AT					NO	NEW - 2020	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020						NO		N/A
		BLACK MASTIC PARGING CEMENT INSULATION ON MECHANICAL	FLOOR MASTIC WITHIN RADIATOR UNITS AT PERIMETER							REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H522	OFFICE	PIPE FITTINGS	WALL						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		DRYWALL	NEW - 2020						NO	NEW - 2020	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020						NO		N/A
11500		BLACK MASTIC	FLOOR MASTIC							REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H523	OFFICE	DRYWALL	NEW - 2020	WITHIN RADIATOR UNITS AT					NO	NEW - 2020	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020						NO		N/A
H524	OFFICE	BLACK MASTIC DRYWALL	FLOOR MASTIC NEW - 2020						NO	REMOVED 2020 (MAPLE PROJECT #18297). NEW - 2020	N/A N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
LIE25 A		REFER TO H525C	AND AND ADDEDT OF CEIVIENT FAINELS	THE PERIMETER WALL						NEWOVED 2020 (WAFEL FROJEGT #10297).	
H525A	MEETING ROOM	VINYL SHEET FLOORING	NEW - 2020						NO		N/A N/A
H525C	MEETING ROOM	BLACK MASTIC	FLOOR MASTIC							REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		DRYWALL	NEW - 2020						NO	NEW - 2020	N/A
		DRYWALL	NEW - 2020	WITHIN RADIATOR UNITS AT					NO	NEW - 2020	N/A
H525V	VESTIBULE	ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	THE PERIMETER WALL					NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		PARGING CEMENT INSULATION ON MECHANICAL	WITHIN RADIATOR UNITS AT PERIMETER						NO	REMOVED 2020 (MAPLE PROJECT #18297).	N/A

Level of Accessibility

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations.

N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative

2023 ACM RE-ASSESSMENT

Page 21 of 22



Room Number	Area #	Material	Description	Location	Qty/Unit	SA#	%	Туре	Condition ACM (Yes, No, Suspect) Accessibility	Friability	Comments	Action Required
H525S	STAIRWELL	MECHANICAL SYSTEMS INSULATION	FITTINGS	STAIRWELL					YES	FRIABLE	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		MECHANICAL SYSTEMS INSULATION	FITTINGS	STAIRWELL					YES	FRIABLE	REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		VINYL SHEET FLOORING	NEW - 2020						NO			N/A
		BLACK MASTIC	FLOOR MASTIC								REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H526	OFFICE	DRYWALL	NEW - 2020						NO		NEW - 2020	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL					NO		REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL					NO		REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H527	OFFICE	DRYWALL	NEW - 2020						NO		NEW - 2020	N/A
HJ27	OFFICE	MASTIC	BROWN WALL MASTIC						NO			N/A
		VINYL SHEET FLOORING	NEW - 2020						NO			N/A
		BLACK MASTIC	FLOOR MASTIC								REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL					NO		REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		DRYWALL	NEW - 2020						NO		NEW - 2020	N/A
		CAULKING	GREY CAULKING	EXPANSION JOINT	UNKNOWN	18274 S01		ND	NO	F	SAMPLED BY MAPLE (PROJECT #18274) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	N/A
H527K	SOUTH END CORRIDOR	CAULKING	YELLOW CAULKING	EXPANSION JOINT	UNKNOWN	18274 S02		ND	NO	F	SAMPLED BY MAPLE (PROJECT #18274) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	I N/A
		FIBROUS MATERIAL	BROWN FIBROUS MATERIAL	EXPANSION JOINT	UNKNOWN	18274 S03		ND	NO	F	SAMPLED BY MAPLE (PROJECT #18274) IN 2019. TO VIEW PROJECT-SPECIFIC REPORT, SEE FACILITIES AND/OR HEALTH AND SAFETY.	I N/A
		DRYWALL	NEW - 2020						NO		NEW - 2020	N/A
		ASBESTOS CEMENT BOARD	TRANSITE ASBESTOS CEMENT PANELS	WITHIN RADIATOR UNITS AT THE PERIMETER WALL					NO		REMOVED 2020 (MAPLE PROJECT #18297).	N/A
H528	OFFICE	PARGING CEMENT INSULATION ON MECHANICAL PIPE FITTINGS	WITHIN RADIATOR UNITS AT PERIMETER WALL						NO		REMOVED 2020 (MAPLE PROJECT #18297).	N/A
		DRYWALL	NEW - 2020						NO		NEW - 2020	N/A
		VINYL SHEET FLOORING	NEW - 2020				i		NO			N/A

A - Accessible and exposed to all occupants of the building.
 B - Accessible only to maintenance staff and exposed to view without moving a building compound.
 C - Accessible only to maintenance staff and concealed from view due to a building component.

Level of Action Required

1 – Immediate clean-up of fallen ACM/debris likely to be disturbed.

2 – Perform asbestos removal/repair for compliance with the regulations.

 3 – Type 2 asbestos procedures required to enter area.
 4 – Regular inspection/surveillance of ACM for compliance with the regulations. N/A - Not applicable.

Definitions

ACM – Asbestos-Containing Materials SA – Sample representative R-SA – Sample referenced to a visually similar homogeneous sample material. ND – None detected

2023 ACM RE-ASSESSMENT

Page 22 of 22